

Archæological Survey of India.

REPORTS

OF

A TOUR IN BUNDELKHAND AND REWA IN 1883-84;

AND OF

**A TOUR IN REWA, BUNDELKHAND, MALWA, AND
GWALIOR, IN 1884-85.**

BY

MAJOR-GENERAL A. CUNNINGHAM, C.S.I., C.I.E.,

ROYAL ENGINEERS [BENGAL RETIRED],

DIRECTOR-GENERAL OF THE ARCHÆOLOGICAL SURVEY OF INDIA.

VOLUME XXI.—PARTS I AND II.

"What is aimed at is an accurate description, illustrated by plans, measurements, drawings and photographs, and by copies of inscriptions of such remains as most deserve notice, with the history of them so far as it may be traceable, and a record of the traditions that are preserved regarding them."—**LORD CANNING.**

"What the learned world demand of us in India is to be quite certain of our data, to place the monumental record before them exactly as it now exists, and to interpret it faithfully and literally."—**JAMES PRINSEP.**

CALCUTTA :

PRINTED BY THE SUPERINTENDENT OF GOVERNMENT PRINTING, INDIA,

1885.

913.54061

ARCI R

VOL. 21.

Uttara Jaikrishna Public Library,

Acce No. 14005 Date 19/9/77

PREFACE.

IN this volume I have brought together the reports of my last two tours in Bundelkhand and Rewa, during the cold seasons of 1883-84 and 1884-85. During these tours I visited many places which had not been reported upon by the officers of the Archæological Survey. The most notable of these places were the great forts of Kālanjara and Ajaygarh, the strongholds of the Chandels of Mahoba, and their religious capital of Khajurāha, which possesses the most famous collection of magnificent temples in Upper India. I have taken the opportunity of giving a complete account of all the Chandel inscriptions at present known. These continue the genealogy for several generations after the fall of Mahoba.

On the south bank of the Jumna, a short distance above Allahabad, I visited a large ruined temple, which had been seen and sketched about 50 years ago by Major ~~Kittoe~~, who calls it the shrine of Karkotak Nāg.

At a short distance, on the way towards Allahabad, I visited a stone building at Chilla, which is said to have been the dwelling-house of the two Banāphar heroes Alha and Udal. It is surrounded by a fortified enclosure, and is important as being one of the very few old dwelling-houses that now exist.

In Rewa I made the discovery that the whole valley of the Tons River had been held by the Kalachuri Rajas of Chedi for at least two centuries prior to the advent of the Bāghel Rājputs. In the previous year my Assistant Mr. Garrick had found a short inscription on rock near the northern

boundary of Rewa giving the name of Gānggeya Deva, the Kalachuri Raja of Chedi, in the beginning of the 11th century. The name of his son Karna Deva is still remembered by the people in connexion with the fort of Gūrgi Masaun, the old capital of the district. Its foundation is attributed to Karan Dahariya, or Karna Dahaliya, Dahal being a well-known name of Chedi. Raja Karna reigned in the middle of the 11th century. Another inscription of the Kalachuri kings was found by my servants on a slab in one of the northern passes of the Rewa territory. It bears the name of Rāja Nara Sinha Deva *Dahaliya*, and is dated in the Samvat year 1216, or A.D. 1159. Two later names are preserved on copper-plates belonging to the large village of Kakareri, also in northern Rewa. These are Jaya Sinha Deva in A.D. 1175, and Vijaya Deva in A.D. 1196. I have found no traces of the Kalachuri kings of a later date than the last, even in Chedi itself. I conclude, therefore, that the Bāghel Rājputs, who now hold the country, must have obtained possession in the very beginning of the 13th century. This is rendered absolutely certain by the mention of two very curious names as the rulers of the country in the middle of the century. These names are given by the Muhammadan historians as Dalaki wa Malaki, which I have identified with the two contemporary princes of the Bāghel chronicles called Dalkeswara and Malkeswara.

In Rewa also the waterfalls of the Tons River at Kevati-Kund, Chachai, and Jhirna were visited. At the first place an old Pali inscription had been found a few years ago by Mr. Markham. On my visit a stūpa carved in outline was also found, proving that the cave was of Buddhist origin.

The numerous sources of the Ken or Kiyān River were next visited, with the expectation that some ancient sites might be found. Many old places were discovered, but most of the temples were in ruins. One very curious temple was found near Ganj in the Ajaygarh territory; the whole of the outer faces of the walls being carved to imitate rock-work. At

Lakhuria, only a short distance, a very important inscription was discovered. It bears the name of Raja Prithivi Sena of Vākātaka, in conjunction with that of his tributary Vyāghra Deva. The former was the father of Rudra Sena of Vākātaka, and the latter was the father of Jayanātha, whose copper-plate inscriptions have been found near Uchahara and at Kāri Talai. As these are dated in the years 174 and 177 of the Gupta era, the Lakhuria inscription of his father Vyāghra may be referred to the year 150 of the Gupta Kāl, shortly after the death of Skanda-Gupta. In fact it may have been the death of the great Gupta prince that led to the occupation of this part of the country by the king of Vākātaka.

A still older inscription was afterwards found in a cave near the top of the Ginja hill, about 40 miles to the south-west of Allahabad. The hill is an isolated peak of the Vindhyan range, 1,326 feet in height above the sea, and about 800 or 900 feet above the plain. The top is a narrow ridge of perpendicular sandstone rock about 200 feet in height. On the south face the cliff overhangs considerably, forming a large open hall, or rock shelter, about 100 feet long, and from 40 to 50 feet broad, and varying in height from 20 to 25 feet outside. It is closed at the two ends by rough walls, but the whole of the front is now open. On the rock at the back there is an inscription of two lines in red paint, with several rude drawings of men and animals. The characters of the inscription are of the earliest Gupta forms; but the opening is worded in the well-known style of the shorter Indo-Scythian inscriptions, as follows:—

Mahārājasya Sri Bhima Senasya
Sam (vatsare) 52, Gimha pakshe 4,
divasa 12, etaya purvayam, &c.

“In the reign of Maharaja Bhima Sena in the year Samvat 52, in the 4th fortnight of the hot season, the 12th day. On that date, &c.”

I take Bhima Sena to have been the Hindu Raja of Kosāmbi during the reign of the paramount Indo-Scythian king

Huvishka. The date, if referred to the Seleukidan era, corresponds with A. D. 140.

At Madanpur, about 50 miles to the north of Saugor, a new inscription of Prithvi Râja Chauhan was discovered. It records his conquest of the country of *Fejâkabhukti*. The same spelling of the name I have since found in a Mahoba inscription. This then was its original form, which soon became shortened to *Fejâhuti*, as written by Abu Rihân, just as *Tirabhukti* became *Tirahuti* and *Tirhut*. The usual Brahmanical derivation of the name of Jajhautiya, from Yajur-hota, is thus proved to be erroneous.

The last discovery which was made in the beginning of the present year was that of a Buddhist stûpa at Râjâpur, about 100 miles to the south of Gwalior. The stûpa is almost intact ; but it is quite plain, and possesses no railing and no inscriptions.

A. CUNNINGHAM.

CONTENTS.

PART I.

	PAGE		PAGE
1. Kosam, or Kausāmbi	1	26. Nachna, or Kuthara	95
2. Rithora	4	27. Jasso	99
3. Bar-Dewal	4	28. Chhota Deori	100
4. Rikhian Caves	7	29. Marhia	100
5. Chilla	8	30. Bargaon	101
6. Chitra-kuta	10	31. Simra	101
7. Gupt Godāvari	13	32. Besāni	101
8. Gonda, or Gora	13	33. Bāghelkhand, or Rewa	103
9. Rāsin, or Rājavāsini	15	34. Piāwan	112
10. Marpha	18	35. Alha Ghāt	114
11. Bilhāniya	19	36. Kevati-Kund	115
12. Kālanjar Fort	20	37. Ginja Hill	119
13. Do. Inscription	33	38. Katkā Obelisk	120
14. Ajaygarh Fort	46	39. Haliya	121
15. Do. Inscriptions	48	40. Dibhor	124
16. Bachon, or Bachaund	54	41. Adesar Hill	125
17. Khajurāha	55	42. Tura	126
18. Do. Inscriptions	63	43. Ahugi	126
19. Maniyagarh	69	44. Bardi and Bhopān	128
20. Mahoba Inscriptions	70	45. Durga-kho	128
21. Dahu Copper-plate	74	46. Bhuli	130
22. Gobari	76	47. Seopur, near Mirzapur	130
23. Raypur	76	48. Kālpī, on the Jumna	131
24. The Chandela Kingdom	77	49. Sultānpur, in Jālandhar	133
25. Map of N.-W. India by Ptolemy	90	50. Chini	134
		51. Chamba	134

PART II.

	PAGE		PAGE
1. Kevati-Kund, or Keonti	141	13. Bargaon	163
2. Rewa, or Bāghelkhand	143	14. Kundalpur	166
3. Gurgi-Masāun	149	15. Hindoria	167
4. Baijnāth	154	16. Damoh	168
5. Raypur-Kothi	156	17. Biya-Kund	169
6. Kiyān, or Ken River	156	18. Saurai	170
7. Paraini	158	19. Madanpur	171
8. Suror	158	20. Lalitpur	175
9. Chhoti Deori	158	21. Surahar	176
10. Simra	159	22. Jhaloni	176
11. Rithi	160	23. Terahi	176
12. Nānd-Chānd	160	24. Rājapur	178

PLATES.

	Pages of text in which referred to.
I.—Map of Bundelkhand and Bāghelkhand	<i>Passim</i>
II.—Map of Kosam, or Kausāmbī	1
III.—Plan of Bar Dewal Temple	4
IV.—View of do. do.	4
V.—Palace of Alha and Udal at Chilla	8
VI.—Temple at Gonda	13
VII.—Map of Rāsin, or Rājāvāsini	45
VIII.—Map of Kalanjara Fort	20
IX.—Kalanjara old Inscriptions	33
X.—Do. Inscriptions dated S. 1186, 1187, 1192, 1194	33
XI.—Ajaygarh: Map of Fort	46
XII.—Do. Inscriptions dated S. 1208, 1237, 1243	48
XIII.—Do. Do. dated S. 1317	48
XIV.—Do. Do. dated S. 1325, 1337, 1372, and 1460	48
XV.—Do. Inscription of Bhoja Deva	52
XVI.—Khajuraha: Early Inscriptions	63
XVII.—Do. Inscription dated S. 1011, and Rāsin	<i>ib.</i>
XVIII.—Do. Do. dated S. 1050, and Marpha	<i>ib.</i>
XIX.—Do. Do. dated S. 1058, of Kakkala	<i>ib.</i>
XX.—MSS.: Short Inscriptions	68
XXI.—Mahoba: Inscription of Kistū Varmma	71
XXII.—Do. Inscriptions	<i>ib.</i>
XXIII.—Do. Inscriptions	<i>ib.</i>
XXIV.—Map of North-West India, according to Ptolemy	60
XXV.—Nachna-Kuthara Temples	95
XXVI.—Do. Detail of Temple	96
XXVII.—Do. Inscriptions of Besān., Jasso	98
XXVIII.—Kalachuri: Inscriptions of Chhota Deori, Alhaghā, Piawan	100
XXIX.—Kevati-Kund Inscriptions	115
XXX.—Ginja Hill Cave Inscriptions	119
XXXI.—Haliya Sepoy's Inscription	121
XXXII.—Durga-kho Inscriptions	128
XXXIII.—Kalpi: Plan of Chaurasi Gun baz	131
XXXIV.—Map of South-West Bundelkhand and Malwa	143
XXXV.—Gurgi-Masāun	149
XXXVI.—Do.	<i>ib.</i>
XXXVII.—Do.	<i>ib.</i>
XXXVIII.—Bargaon: Temple of Somnath	163
XXXIX.—Bargaon: Somnath Temple—Edge of Roofing Slabs. Garud Temple—Face of Architrave	164
XL.—Nand-Chand	160
XLI.—Do.	<i>ib.</i>
XLII.—Kundalpur and Saurai: Slab Temples, Kundalpur	166

PART I.

REPORT OF A TOUR IN BUNDELKHAND AND REWA

IN

1883-84.

ARCHÆOLOGICAL SURVEY OF INDIA.

REPORT OF A TOUR IN BUNDELKHAND AND REWA IN 1883-84.

PART I.

I.—KOSAM, OR KAUSÂMBI.

IN his account of the famous city of Kausâmbi, the Chinese pilgrim Hwen Thsang describes two holy places which I failed to identify at my previous visits. These were the rock-cave of the venomous serpent, and the ancient brick-chamber in which the famous Bodhisatwa Vasubandhu composed his treatise named the *Vidyâ-mâtra-siddhi-shâstra*, for the refutation of the doctrine of the Hinayâna.

The first place is thus described by the pilgrim :¹ "At 8 or 9 *li*, or $1\frac{1}{2}$ mile, to the south-west of the town there is a rock-cave of a venomous dragon. After overcoming this dragon Buddha left his shadow in the cave. But, though this fact is recorded in history, there is nothing to be seen at the present day."

At my previous visits I had looked for this cave on the bank of the Jumna to the west of the city just outside the village of Pâli. The south-west bearing is quite impassable, as the general course of the Jumna above the city is from north-west to south-east. Before going to Kosam (which I have previously identified with the ancient Kausâmbi), I visited the hill of Prabhâsa, or Pabhosa, as it is generally called, as I had a suspicion that the *rock-cave* might be found in the *rocky* hill. It is true that the hill of Pabhosa is 3 miles to the north-west of the great fort of Garhwâ, but it

¹ Juhen's Hwen Thsang, Vol. II, p. 286.

is not more than 2 miles from the present villages of Kosam and Pāli, which formed the old city outside the walls of the fort.¹

On reaching the hill of Pabhosa I found that there was not only a cave high up in the face of the hill, but that there was also a Nāga, or serpent, of which everybody had heard, but which no one had seen. The serpent is believed to have his head in the Jumna while his tail remains in the cave, which is more than a quarter of a mile from the river. The Nāga is said to be seen once a year at the time of the Diwāli festival.

The cave is artificial, and is simply an old quarry with a pillar left in front for the support of the roof. In front there is a Jain temple, and there are three standing Jain figures cut in the rock above. The Jain temple was built by one Hira Lāl about 40 years ago. The whole face of the hill in front is now a mere mass of débris, the refuse of the quarry above. The room is said to be large enough to hold four bedsteads: it has two windows, as well as a door. On an eminence near the foot of the hill to the east there is a tank called Deo-Kund, with a small temple on its bank.

The Chinese pilgrim mentions that there was a stūpa of Asoka, about 200 feet high, beside the cave, but no traces of such a building could be found. It is very probable, however, that the present Jain temple occupies the site of some ancient building. The pilgrim also notes that close by there was a site where Buddha used to take exercise, and a second stūpa containing some of his hair and some nail-parings. Sick people used to visit the place, and pray for their recovery.

On the faces of the rock at several points there are short inscriptions, which may be only records of the quarry-men. They are all, however, written in characters of the Gupta period. One of them gives the name of *Vasu Deva*; a second reads *Savahāvinse*; while a third gives the name of *Yasa*, and a fourth reads *Adahāsīsam*. The quarries are, there-

¹ See Plate II for the position of the Pabhosa hill.

fore, as old as the time of the Guptas, from 200 to 400 A.D., and the cave and its legendary Nāga were, no doubt, in existence at the period of Hwen Thsang's visit to Kausāmbi in A.D. 636.

In searching for the brick-chamber of Vasubandhu to the south-west of Kausāmbi, I was led, by the pilgrim's description of its height being equal to that of a pavilion of two storeys, to examine a cave near the villages of Garauli and Gopsahsa, both to the south-east of the great fort. The cave has been excavated in a huge earthen mound, named Tikri, which rises from 45 to 50 feet above the general level of the country. Owing to its commanding position, overlooking the Jumna, the mound was used as a survey station, and it is probable that a few feet at the top were added by the surveyors. The excavation consists of two rooms facing the east. The outer room was 11 feet long by 8 feet 3 inches deep, with a doorway, 4 feet wide, leading into the inner chamber, which is 11 feet 6 inches broad by 13 feet 3 inches deep. This inner chamber has a long raised seat or couch on the south side. Both chambers are now only $4\frac{1}{2}$ to 6 feet in height. They had been inhabited lately by a fakir.¹

On the eastern face, just halfway up the slope, or about 15 feet above the ground, there is a brick wall, which appears to have been the back wall of another chamber. There are quantities of broken bricks at the foot of the mound, and in the fields close by, where fragments of stone are also found. The brick wall I take to be the remains of a lower storey, which agrees with Hwen Thsang's account of the residence of Vasubandhu as an ancient chamber of bricks—"d'un pavillon à deux étages."² I could find no trace of the great monastery of *kiu-shi-lo*, or *Gosirsha*, with its stūpa 200 feet in height. The name of *Gosirsha*, or *Gosira*, appears to be preserved in that of the neighbouring village of Gopsahsa; but there are no remains of walls now visible, although there are numerous fragments of stone and quantities of broken bricks scattered about.

¹ See Plate II for the position of the Tikri mound.

² Julien's Hwen Thsang, Vol. II, p. 286.

2.—RITHORA.

One mile and a half to the north-west of Mhow Ghat, and within sight of Kosam, there are two ruined temples, of small size, but of fine workmanship. The larger one is only $10\frac{1}{2}$ feet square outside, with a portico on the north in front of the entrance, supported on two nicely carved pillars. The temple has fallen backwards, and the enshrined figure is lying inside crushed beneath the roof. On the face of the door-step there are represented two crocodiles, each carrying two women with children in their laps. There is a figure of Káli outside, from which it may be inferred that the temple was dedicated to the worship of Siva. The pillars are of early mediæval style.

The second temple is similar to the first, and was also dedicated to Siva, as it still possesses a group of Hara-Gauri. The entrance doorway also is similar to that of the other temple ; but the jambs, which are still standing, have figures of the Ganges on her crocodile and the Jumna on her tortoise.

3.—BAR-DEWAL.

For my knowledge of this fine old temple I am indebted to an almost forgotten work of Major Kittoe¹. He calls the building a " Temple of Karkotak Nág," but this name is now quite unknown. His account of it is so very brief that I may give it in full:—

"The elegant ruin represented in the accompanying plate² is situated on the bank of the Jumna, on the Bundelkhand side, a few miles below the town of Mhow. It is dedicated to Siva under the denomination of Karkotak Nág. The work is executed in a most exquisite and elaborate style, in hard, close-grained sandstone. The greater part, indeed the main body, of the building has long since fallen to the ground ; the only portion remaining, and which I have faintly attempted to represent, is that still existing of the Nandi Sabha (or portico), in which Siva's bull Nandi is always placed. It is not

¹ Illustrations of Indian Architecture, by Markham Kittoe : Calcutta, Thacker and Co., 1838, long folio.

² I have given a representation of Kittoe's view in Plate IV, reduced to two-thirds of the original.

known who erected this truly beautiful specimen of Hindu sculpture and architecture. There is a small village close by, the superstitious inhabitants of which informed me that a huge black serpent, or *nâg*, inhabits the temple, and is occasionally visible."

This is all that he says regarding the temple, the rest of his notice being taken up with an account of the serpent Karkotak Nâg, and the story of Nala and Damayanti.

The temple is situated on the south bank of the Jumna, on a high bluff point close to the village of Kutharo. It is just 11 miles to the east of Mhow Ghât, and 25 miles to the west-south-west of Allahabad. Its position is rather inaccessible, as there is nothing but a pathway ascending and descending for 11 miles through the ravines of the Jumna on the west, and a similar pathway on the east for 4 miles, from the large village of Partâbpur, where the great stone quarries are situated.

The Bar-Dewal must have been a magnificent temple. Its position on a high projecting point overlooking the Jumna is a very fine one, and both in size and in decoration the fane was worthy of its site. It is, besides, raised on a plinth or platform of 11 feet.¹

It is a lingam shrine of Siva—and the name given to it by Kittoe of Karkotak Nâg is quite unknown. The entrance is to the east, as usual with lingam shrines. It consists of the usual sanctum containing the lingam with the entrance on the east. The Mahâ-mandapa, or great hall, is 25 feet square, the roof being supported on four magnificent columns, each upwards of 14 feet in height. These are placed 8 feet 8 inches apart on a raised platform 1 foot $3\frac{1}{2}$ inches in height. On each of the four sides immediately opposite each pillar there is a square pilaster nearly 10 feet high, at 5 feet distance; and between each pair of pilasters there are two octagonal pillars of the same pattern as the larger columns, and of the same height as the pillars. The architraves covering these pillars are massive beams about 2 feet square in section, and very elaborately ornamented on

¹ See Plate III for a plan of the temple.

each face. Between each pair of pillars there was formerly a cusped arch, of which one was still *in situ* when Kittoe sketched the temple.

The central roof of the Mandapa has fallen down ; but a portion of the side roof still remains, exactly as it was seen by Kittoe. The usual arrangement that I have seen is to cover this portion by overlapping stones, projecting one over the other from the outer and lower rows of pillars until the space between the two rows of pillars is roofed over. But in the present example the arrangement is quite different, the whole of the surrounding veranda, as it may be called, being roofed in by long sloping slabs which are very deeply cut with three horizontal recesses, which imitate the courses of the overlapping roofs. In these recesses there are rows of small seated Nāga kings, with snakes' hoods over their heads. On the west side three of these sloping slabs still remain *in situ*, and at the north corner there is a single slab of wedge shape, that is, narrow at the top and broad at the bottom, showing that the same arrangement of roof was continued at the angles.

In the accompanying plan I have attempted to restore the temple from the existing remains, either *in situ*, or lying on the ground below.

The dimensions of the platform were obtained from the existing angles.

The four great columns of the central hall, C, are still standing in their places.

Of the smaller pillars those marked P¹, P², are still *in situ*, as well as the base of P³. The positions of the others marked P. have been fixed on the authority of two small projecting brackets at right angles, on each of which were once supported the ornamental cusped arches, similar to those between the larger pillars. The presence of these small brackets shows decisively that there must have been four pillars on each of the three open sides of the hall. Only four of these pillars are now lying on the ground—two on the north side, and two on the south side ; but there are also some short architraves which once spanned these spaces, and some

narrow roofing slabs which could not have formed any part of the roof of the great central hall.

With these remains still existing it seems certain that there must have been a small porch, or hall, on each side to the north and south, and a third on the east side forming the entrance. I could not find any trace of the flight of steps, as the whole of the eastern front is now a confused mass of large stones.

Externally the view from the east would have presented three pyramidal domes in front; the middle one being higher than the others, with the tall spire of the sanctum behind.

The people differ as to the meaning of the word *Bar*. Some say it refers to a Bhar Raja who built it, but others refer it to a Bar, or Banyan, tree which grew near it. I think, however, that it was more probably only the *Barā Dewal*, or "great temple." There is a large village on the bank of the Jumna 1 mile to the west called Barha, and this may have given its name to the temple.

When Kittoe saw the temple just 50 years ago, the light-cusped arches between the pillars of the Mandapa were still in their places, as shown in his sketch. They fell down some years back, and three of them are said to have been taken to Allahabad by a Saheb.

There is no inscription now remaining, the only writing being a pilgrim's record of the last century.

There are plenty of large bricks lying about, but they could not have belonged to the temple itself, as it is built entirely of stone. Perhaps there was a surrounding wall of brick, with some subordinate buildings.

4.—RIKHIAN CAVES.

In the face of the hill nearly due south from Bar Dewal, and about a mile and a half distant, there are two large caves known by the name of Rikhian, or the dwellings of the Rishis. They are apparently old quarries, partly built up in front with dry stone walls to form rooms. Two pillars help to support this roof. The larger cave is $34\frac{1}{2}$ feet long by

17½ feet broad, and 6½ high. Inside, against the back wall, there is a large collection of statues, which were most probably taken from the Bar Dewal Temple after it had become ruinous. The principal statue is a figure of Vishnu with 12 arms. It is 4 feet high by 2½ feet broad. There are also figures of Kâli and Ganesa, and of 42 goddesses, which are most probably a portion of the Chaunsat Joginis, as several of them are represented with animals' heads. Amongst them is one with a leonine head and another with a porcine head, &c.

The second cave is 22 feet long by 16 feet broad, and 7 feet high, with one pillar in the middle to support the roof. It has a projecting porch in front of the entrance built with squared stones. It has also two holes, or small windows, to give light. Inside there is a seated figure of a three-headed goddess with 16 arms. It is 2 feet 8 inches high, by 1 foot 9 inches broad, and most probably represents Dûrgâ.

Outside there is a small temple with a sanctum only, 4 feet 10 inches square, and a flat roof, 9½ feet high. Two other temples in ruins are close by.

There is also a large tank, 600 feet in length, which is supplied by a small stream coming over a waterfall.

The place is considered holy, and is visited by numbers of pilgrims.

5.—CHILLA.

Chilla is a pretty, well-wooded village on the south side of the Jumna, 12 miles due east from Bar Dewal, and the same distance to the south-west of Allahabad. It is celebrated for its possession of a large stone dwelling-house, which is said to have been the residence of the two famous Banâphar heroes, Alha and Udal.

The building stands in the middle of a small fortified enclosure called Kot, which has a thick earthen rampart, faced with stone both inside and outside, and four towers at the corners. It has also a ditch all round, with a stone counterscarp.

The house itself is a square of 46 feet, each side divided by pillars and walls into 25 small bays, in five rows each way.

To the north is the entrance, with a long slab seat on each side, covered by a low roof, supported by short pillars. The middle compartment is open to the sky, and thus forms a small courtyard.¹ The five compartments on the south side form five separate rooms, each with its own door. The two compartments on the north-west are walled in to form a separate room with its door to the south. Similarly the two others on the north-east form a single room with a door to the west. Each of these rooms is lighted by a stout stone trellis, and two similar trellises give light to the inner parts of the body of the building. Each compartment is between 7 and 8 feet square, and the total height is 8 feet 10½ inches.

The roof is flat. Four pillars of the same pattern, but less massive, are now used to support some broken slabs of the roof. These are said to have been brought from above, where they supported a canopy where the inmates used to sit.

With its massive ramparts, which completely covered the building from view, the place was capable of being defended for some time.

All the doorways are slightly ornamented, but more especially the door sills. The corner rooms and side walls have stout stone trellises of a simple pattern. The pillars also are slightly decorated. There are no inscriptions, but the letter *n* of an early form was found in two places. From its form I should judge that the building must be as old as the 8th or 9th century.

This building is of some interest, as so few specimens now exist of early Indian domestic architecture. I have given in other volumes plans and descriptions of a stone dwelling-house at Ranod, and the fine palaces of Mân Singh at Gwalior; the former belonging to about the 8th century, and the latter to the early part of the 16th century A.D. A very interesting specimen of an intermediate period has been found by Mr. Beglar in Rājputāna in a palace of the famous Prithvi Raja, which, therefore, belongs to the latter half of the 12th century A.D.

¹ See Plate V for a plan of this building.

Outside the enclosure of Kot there are numerous remains of a large stone temple, in richly carved stones and broken statues, which would seem to show that Chilla was once a place of some importance.

6.—CHITRA-KUTA.

The holy hill of *Chitra-kuta*, or the "many-hued peak," is famous as the residence of Râma, Sitâ, and Lakshman during their exile from Ayodhya, and also as the abode of the sage Vâlmiki, the reputed author of the Râmâyana. It is situated on the left, or west, bank of the Paisuni River, about 5 miles to the south-west of Karwi, and 50 miles to the south-east of Banda. Its praises have been sung by Vâlmiki himself as the—

"Auspicious hill! where all day long
 "The lapwing's cry, the Koil's song,
 "Make all who listen gay;—
 "Where all is fresh and fair to see;
 "Where elephants and deer roam free." ¹

A paved foot-path, with a continuous belt of small temples, encircles the foot of the hill, which is crowded with pilgrims at all times of the year. The temples, however, are all modern, and there are no inscriptions. Fragments of sculpture and pieces of carved stone are found lying about the foot of the hill, but there is nothing to show that the place is an old one. Kâmtâ is the name of the village close by the hill, and the hill itself is often called *Kâmtâ*. The true name is *Kâmadâ-giri*, or the "hill of the giver of plenty," or the "desire-giving hill." The hill itself is still covered with jungle, but there are no Rishis, as the Brahmans of the present day all live in comfortable houses below.

Of late years the small town of Sitapur, situated also on the left bank of the Paisuni River, 1 mile to the north of Kâmtâ, has rivalled the fame of the holy Chitra-kuta. Here the river Paisuni forms a long straight reach, both broad and deep, on the banks of which there are numerous temples

¹ Griffith's Râmâyana.

and bathing ghâts, or flights of steps leading down to the water. Some of the temples are said to be old, but they are all so smudged with whitewash that it is quite impossible to judge of their antiquity. The name of Sitâpur is, however, quite modern, as it was given by Charan Dâs near the beginning of the present century. The old name was Jaysinghpur.

I saw many thousands of pilgrims on their way to Kâmtâ and Allahabad from Bhilsa and Sâgar. There was also a widowed Râni from Ratlâm. They came by different routes through Hirapur and Panna, as well as by Ajaygarh and Kâlanjar. There were also many pilgrims from Chattisgarh and Raypur in the Central Provinces, who had come by Amarkantak and Sohâgpur to Rewa, and then by Jetwar and Mârkandi on the railway, and thence over the hills to Râsin and Kâmtâ.

Whatever age may be assigned to the Râmâyana, it is certain that the story of Râma and his exile to the famous hill of Chitra-kuta must be still older. We know, indeed, that the story is certainly as old as the second century B.C., as it is represented amongst the sculptures of the Bharhut stûpa as an illustration of the Dasaratha jâtaka of the Buddhists. In the Râmâyana we read that Râma on his departure from Ayodhya went first to Sringiverapura on the Ganges (now Singor), and, after crossing the river, paid a visit to the sage Bharadwâja, whose hermitage was at the junction of the Ganges and Jumna. Bharadwâja told him to go to the hill of Chitra-kuta on the Mandâkini River. As these two names still survive in the holy hill of Chitra-kut and the small river Mandâkin which joins the Paisuni a little below Sitâpur, there can be little doubt as to the correctness of their identification. But there is a third name in the immediate vicinity which seems to offer a conclusive proof of the Chitra-kuta of Bundelkhand being the actual place intended by the poet.¹ This is the hill of Prasravan, which, as it is coupled with the Mandâkini, can only be another name for Chitra-kuta itself. Prasravana means literally "a cascade or waterfall," and might,

¹ See Griffith's Râmâyana, Vol. III, p. 298.

therefore, be applied either to a hill or to a stream. In the present instance I believe that it may be identified with the Paisuni, or Parsaroni, as it is also called. Now, this stream is famous for its cascades, and on that account must have received the name of the Prasravana Nadi, or "waterfall river." In the same way the hill of Chitra-kuta would be called the hill of Prasravana.

Similarly I believe that the Godâvari stream searched for in vain by Lakshman was not the distant Godâvari River which rises at Nâsik, but the holy Gupt-Godâvari, or "hidden Godâvari," which rushes forth from a cave in the hill a few miles to the south of Chitra-kut. But whatever may be thought of this identification of the Gupt Godâvari with the Godâvari River, it is certain that the Gupt Godâvari corresponds exactly with Bharadvâja's description of the Chitra-kuta Hill, whence Râma and Sita would—

" See the foaming torrent rave

" Impetuous from the mountain cave.¹

The Chitra-kut Hill of Bundelkhand still further corresponds with the Chitra-kuta of Vâlmiki in the various hues of its rocks from which it has derived its name, or, as Mr. Griffith has rendered it,—

" There a silvery sheen is spread,

" And there, like blood, the rocks are red ;

" There shows a streak of emerald green,

" And pink and yellow glow between."²

I have thought it necessary to give all these small coincidences, as Mr. Beglar has brought forward some very plausible arguments to prove that the Chitra-kuta of Bundelkhand is not the Chitra-kuta of Vâlmiki. His chief objection is the want of a torrent issuing from a mountain cave. But this I have now supplied in the Gupt Godâvari, which is a place of pilgrimage. Mr. Beglar proposes the hill of Râmgarh 150 miles to the south-east of Rewa and 160 miles to the west-south-west of Hazaribagh. It is true that a torrent issues from the Ramgarh Hill, which so far agrees with the

¹ Griffith's *Ramâyanâ*, Vol. II, p. 206.

² *Ibid.*, Vol. II, p. 375.

Chitra-kuta of Rama. But it is equally true that the Rāmgarh Hill is 200 miles from Allahabad, and therefore does not agree with Bharadvāja's description of Chitra-kuta as being only a "short distance" from the junction of the Ganges and Jumna.¹ Mr. Griffith says "4 leagues," which I take to be yojanas, equal to about 30 miles, instead of 60. But this is something very different from the 200 miles direct, or 250 miles by road of Rāmgarh from Allahabad. Then there is a very serious difficulty about a chariot getting to Rāmgarh, which stands in one of the most hilly and inaccessible districts in India. I do not think that a poet would take a chariot there even in a dream.

There are several claimants for other places connected with the wanderings of Rāma, as well as with those of the five Pāndus. Thus, there are three places named Bairāt, and several named Kundilpur, as well as two districts called Matsya-desā.

7.—GUPT GODĀVARI.

The Gupt Godāvari, or "concealed Godāvari," is a small stream which issues from a cave in the hills about 9 miles to the south-south-west of Chitra-kuta. The stream is one of the objects of pilgrimage. It is from 8 to 10 feet broad and 3 feet deep, and falls into the Godai Nala. The end of the cave, it is said, has never been reached. There is a long Nāgari inscription inside, but it is quite modern.

8.—GONDA, OR GODA.

Gonda is a large flourishing village 1 mile to the south of the present high road leading from Karwi to Banda. It is 13 miles from Karwi, and stands on the old road going to Kālanjar on the south-west and to Banda on the north-west.

To the east of the village, where an embankment has been thrown across the valley between two ranges of hills to form a tank, there is a pair of old temples standing together on the same platform. They are simply known as Chandeli Mandar, or the "Chandeli Temples," as all old buildings are

¹Wheeler's *Ramāyāna*, p. 190.

designated throughout Bundelkhand. By some they are attributed to Alha and Udai, and king Parmâl. But the attribution is very doubtful, the only certainty about them being their Chandel origin. Both temples have the river goddesses Gangâ and Yamunâ at the bottom of their door jambs, but they are not standing on their symbolic animals, the crocodile and tortoise. The animals, however, are present, but are made very small, and are mere accessories at the feet of the figures.

The larger temple is built on the usual plan of an entrance hall, a central hall, and a sanctum with the door to the east. It is 55 feet long by 48 feet 9 inches broad, and is still about 40 feet in height above the plain, but not more than 30 feet above its own terrace. It was originally dedicated to Vishnu, as there is a figure of that god over the middle of the entrance doorway. On each of the two sides there was a pillared portico, to which on the south side was attached a small temple 13 feet square outside, with the entrance on the north leading into the mandapa of the larger temple. This small fane was dedicated to Lakshmi, as shown by her figure over the centre of the entrance door. But at some later date both temples were appropriated by the Saivas, who placed lingams inside, which are still *in situ*.

The spire of the smaller temple is now gone, but nearly the whole height of the spire of the larger one is still standing, saving only the *kalas*, or pinnacle. The lower part is perpendicular, but the upper part is sloping with a very slight curve. On the perpendicular sides there are two rows of figures, each 2 feet in height. Amongst these are—

- 7 figures of Siva.
- 1 figure of Kâli, skeleton goddess.
- 1 „ of Ganesa.
- 6 figures of Vishnu.
- 1 figure of Brahma.
- 1 standing male figure not recognised.
- 1 figure broken.
- 4 figures lost.

TOTAL 22 the full number.

913.54061

ARCIR.

VOL. 21

In the upper part of the spire the angles only were ornamented, all the middle spaces being left quite plain.

The roof of the mandapa of the great temple is altogether gone, and the stones now cover the floor, and prevent accurate measurements being taken.

I searched in vain for inscriptions. There are a few pilgrims' records; but as none of them are dated, they are of little value. Such as they are, I have given them in the plate below the plan of the temple.¹

A. On left jamb of Vishnu Temple.

*tasâla *dasala.

B. Inside Vishnu Temple.

1. Krita Sri Râwat Totai Vinikoti patithâ.
2. Ma ** sara Deva miti.

C. Inside Lakshmi Temple.

Vasu Devaii Bhasara.

D. On left jamb of entrance.

Arjuna Deva.

9.—RÂSIN, OR RÂJAVÂSINI.

The old town of Rasin, or Râsin, is situated on the high road leading from Banda to Kâlanjar, and just midway between Karwi and Kâlanjar. It is 29 miles distant from Banda. It lies at the foot of a granite hill, and its numerous mounds, ruined temples, and broken sculptures, all show that it must once have been a place of considerable consequence. In the time of Akbar it was one of the mahals of Sirkâr Kâlanjar of the Suba of Allahabad. There are also many fine old tanks, of which I obtained the following names, but the list is said to be very incomplete :—

1. Adhika.
2. Amarâdei, on the hill.
3. Bahubâri, on the hill.
4. Bathkhor.
5. Chachai.
6. Chandâ-Maheswari, on the hill.
7. Chandi Talao.

¹ See Plate VI, both Temple and Inscriptions.

8. Chungwa Bhungwa.
9. Dhamsarā.
10. Dudkhari.
11. Godika.
12. Kariyā.
13. Khalukhal.
14. Kuthli.
15. Palti Pokhara.
16. Pothra.
17. Puraniya.
18. Rasandai, on the hill.
19. Sarwā Karwā.

Four of these tanks are shown in the accompanying map of Rāsin.¹ The Adhika Tal is a very fine sheet of water; but nothing is known regarding any of the makers of the tanks. The name of Rāsin is said to be only a contraction of Rājansi, but from one of the inscriptions it would appear that the old name was *Rājavāsini*, or the Royal Residence, which would naturally be shortened to Rājāsin and Rāsin.

The positions of the antiquities of Rāsin are all marked in the accompanying map by the letters A, B, C, D, E, F.

A.—On the side of the road, at the foot of the hill and to the north of the town, there are several Sati pillars, with a large standing female figure holding a child in her left arm, and several fragments, including a four-bracket capital, with human figures on the faces, and smaller figures in the angles.

B.—Is a small mound on the east side of the road faced with squared stones. On the top are several statues, of which the most prominent is a figure of Ganesa. The platform was certainly the site of a temple, and it is accordingly now called *Sivāla*, or the "Temple of Siva," and sometimes also *Ganesa* from the principal figure. But amongst the broken sculptures I found many fragments of a colossal figure, which after some trouble I succeeded in fitting together as a colossal figure of the skeleton goddess Kālī, 8 feet high and 4 feet broad. The figure has 24 arms, and is surrounded by a number of small skeleton females of the same kind, both sitting and standing. The goddess herself is represented

¹ See Plate VII.

standing on the back of a prostrate male figure. She has a deeply sunken stomach with a very long-tailed scorpion between the ribs.

On the mound there are several other sculptures, such as the goddess Devi (Durgā) with ten arms, a Mahesasuri Devi, and two Nandis, a large figure of Hanumân, 6 feet high, and the upper half of a statue of the Narasinha, or man-lion, of life-size. But the principal figure is the colossus of Kālī, which must certainly have been the statue enshrined inside, and which would therefore have given its name to the temple.

C—The principal object in this group of ruins is the entrance doorway of a temple, which is still standing apparently *in situ*, with some fragments built into a piece of rough wall on each side. The site is accordingly known simply as *Darwāja*, or "the Door." Amongst the stones collected here there is a complete pilaster, 5 feet 2 inches in height, and a piece of a twelve-sided pillar. There is also a ten-armed figure of Durgā, and several Sati stones, of which one bears a nearly obliterated inscription.

D—Is a Sivāla built of old materials.

E—Is a temple of Ratannāth, built on the top of the hill overhanging the town. It is not very old, and bears no inscription.

F—Is the famous temple of Chandā Maheswari, which is situated in a dense jungle on the top of the hill, about 1 mile to the east of the town in a direct line, but nearly 2 miles by the winding pathway. The building is much smaller than the Gonda temple, and has no figures on the outside, but only simple mouldings. The sanctum is only 12 feet outside, and 8 by $7\frac{3}{4}$ feet inside, with a niche in the back wall, and a lingam in the middle. The mandapa, or hall, in front is slightly oblong, being 18 feet 8 inches by 17 feet 7 inches. The hall is open at the sides, with two broad seats, $3\frac{1}{2}$ feet wide, backed by sloping parapets. There is a small portico in front, 9 feet wide by 6 feet deep. The enshrined statue of the goddess has four arms, and is 2 feet in height. Close by there is a tank hewn out of the rock 80 feet by 50 feet.

There are two inscriptions on the temple: 1st, an old record of the Chandeli period in two long lines, without date. The beginning is lost, and there is no King's name; 2nd, a record of seven short lines, dated in Samvat 1466 (A.D. 1409), which I read as follows:—

1. Siddhih!—Samvat
2. 1466 varshe Chaitra
3. Sudi 7 şane—Râjâ
4. dâsah Sri Râjavâsinya
5. Paramârddi Mahipateh-
6. tasya bhrityosti jai Pâlah,
7. Samogha Sura Pâlahah.

"In the Samvat year 1466, on Saturday, the 7th day of the waxing moon of Chaitra (Saturday, 23rd March 1409 A.D.), the king's slave in Râja-vâsini (the royal residence of Paramârddi, lord of the earth, whose servant was Jai Pâla Samogha, the son of Sura Pâla).¹"

I take the name of Paramârddi to refer to the Chandel king of two centuries earlier than the date of the inscription. Râja-vâsini I suppose to have been his royal residence, and perhaps to have been founded by him. It is, however, quite possible that there was a second Paramârddi at the date of this inscription in A.D. 1409, although no certain records of the Chandel Princes have yet been found of a later date than Samvat 1372, or A.D. 1315, of Vira Varmma II.

10.—MARPHA.

The great fort of Marpha is but little known, although it is as large and as lofty as either Kâlanjar or Ajaygarh. It is situated on a high projecting hill, just 4 miles to the south of Râsin, and 12 miles to the north-east of Kâlanjar.² I passed under the fort and within a mile of its walls on my way to visit Bilhariya temple, which is just 2 miles to the south of the fort. I did not visit the place myself, as it had been previously explored by both of my Assistants, Mr. Beglar and Mr. Carlleyle. The inscriptions spoken of by Pogson³

¹ See Plate XIV for a *fac simile* of this inscription.

² See the map in Plate I for the position of Marpha.

³ Pogson's *Bundelas*, page 135.

are not old, and are of very little value. There is one long inscription of three lines, dated in Samvat 1404, or A.D. 1347. It records a dedication. Two others in small letters are Jain records of the Mula Sangha, dated in Samvat 1407 and 1408. They contain no kings' names, and are confined to the names of the donors of the statues dedicated, and of the high priest at the time of dedication. I can find no mention of Marpha in any of the Muhammadan historians, and I am inclined to think that it was not occupied as a fort until Kālanjar had fallen.

The missionary Tieffenthaler, who visited Marpha in the middle of the last century, states that it was also called Mandefa. But I suspect that both the names are only corruptions of the original, which, from the inscription of Samvat 1404 mentioned above, would appear to have been *Madharppa*.

This inscription is dated in *Samvat 1404, Kārttika Sudi 14 Gurau*, in the *Sidhitungarājye*, or during the reign of *Sidhitunga*. There is nothing like this name either amongst the Bāghel chiefs of Rewa or the Chandel princes of Kālanjar.

The fort is now nearly deserted, and is overrun with jungle, in which both tigers and leopards find cover.

11.—BILHARIYA.

Ten miles to the south of Rāsin, in the midst of the valley, overlooked by the great fort of Marpha, there is a small stone temple on the top of a rocky hill called *Bilhariya Math*, or the Bilhariya temple. It is about 18 miles from the Majgowa station of the Jabalpur Railway, but the road lies over an uninhabited hill tract, and is now very rarely used.

The hill is 70 feet high. On the lower terrace towards the south there are the remains of two other temples, which have been dismantled to furnish materials for a small fort, at a short distance to the north, near the village of Bhagalanpurwa. Its walls are built entirely of squared stones, amongst which I recognized door jambs, pillars, amalaka fruit pinnacles, mouldings of many kinds, and several roofing slabs.

The temple on the hill is a small one, but it is highly ornamented, and is otherwise remarkable for its picturesque situation. It consists of a sanctum, $11\frac{3}{4}$ feet outside and $4\frac{1}{4}$ feet inside, with a portico in front, 9 feet square. The spire is still standing with the lower amalaka fruit *in situ*, but the upper part of the pinnacle is gone. On the outside there are two rows of figures, of which the lower ones are 19 inches in height. I recognized the following:—

	{ Lakshmi, four-armed, seated, being anointed by two elephants.
North	{ Siva and Pârvati, standing.
	{ Nearly naked female, exposing her person.
	{ Siva standing with Nandi.
West	{ Siva with trident.
	{ Vishnu.
	{ Siva naked, with sword and skull.
South	{ Ardhanârî, half male, half female figure.
	{ Naked female.
	{ Saraswati, four-armed.

The temple was dedicated to Vishnu, who is represented over the centre of the entrance with Brahmâ on his right and Siva on his left, and the Navagraha, or nine planets, arranged between them.

12.—KÂLANJAR FORT.

The fort of Kâlanjar is one of the most famous places in India. In A.D. 1023 it withstood the army of Mahmud of Ghazni, but was shortly surrendered, and the Raja was received into favour on presenting some highly complimentary verses to the great conqueror.¹ In 1545 it held out against the redoubtable Sher Shah, and was not captured until the besiegers had been roused to fury when their king had been mortally wounded by the bursting of a shell in the trenches. In 1812 it repulsed the assault of a British force under Colonel Martindell, but the fort was surrendered on the following morning, as the Raja doubted whether he would be able to

¹ Brigg's Ferishta, Vol. I, p. 67.

withstand a second assault. The terms were very favourable, as he received an estate of equal value in the plain.¹

Kālanjar is situated 90 miles to the west-south-west of Allahabad, and 60 miles to the north-west of Rewa. The fort stands on an isolated flat-topped hill of the Vindhya range, which here rises to a height of 800 feet above the plain. The lower part of the ascent is tolerably easy, but the middle portion is very steep, while the upper part is nearly perpendicular and quite inaccessible. The main body of the fort, which lies from east to west, is oblong in form, being nearly a mile in length by half a mile in breadth. At the north angle there is a large projecting spur nearly a quarter of a mile square, which overhangs the town; and on the middle of the southern face there is another projection of about the same size, but triangular in shape. The distance between the extreme points of these two projections is nearly 1 mile. The whole area is therefore considerably less than 1 square mile, while the parapet walls are nearly 4 miles in length.²

Kālanjar is often compared with Gwalior, under the belief that the two forts are about the same size. But Gwalior is $1\frac{3}{4}$ mile in length by half a mile in breadth, with a parapet of rather more than 5 miles in extent. Kālanjar, however, has the advantage of Gwalior in height, being upwards of 800 feet above the plain, while Gwalior is under 400 feet. But the water-supply of Gwalior is permanent and good, while that of Kālanjar is uncertain, and has failed on several important occasions.

Kālanjar has been occupied from the most remote times. According to Wilson, it is mentioned in the Vedas as one of the *tapasyasthānas*, or "spots adopted to practices of austere devotion."³ In the Mahābhārata it is stated that whoever bathes in the lake of the gods in Kālanjar acquires the same merit as if he had made a gift of 1,000 cows.⁴ In the Padma Purāna it is named as one of the nine holy places in Northern India.

¹ Pogson's Bundelas, p. 142.

² See Plate VIII for a map of the fort.

³ Sanskrit Dictionary, *in voce*.

⁴ Atkinson, Gazetteer of Bundelkhand, Art. *Kalanjar*.

"Renuka, Sukara, Kasi, Kāli, Kāla, Bateswarāh, Kālanjara, Mahākālā, Ukhala nava Kirttnāh,"—that is, "Renuka (near Agra), Sukara (Soron on the Ganges), Kāsi (Benares), Kāli, Kālā (or Karra on the Ganges), Bateswara (two of the name), Kālanjara, Mahākāla (or Ujain), are the nine famous *Ukhālas*."

But all these notices refer solely to the sanctity of the hill as the resort of *tapaswis*, or holy ascetics. The overhanging rocks afforded shelter to the Rishis, and the rain water percolating through the rocks from above gave them drink. The hills of Asirgarh and Gwālior were similarly occupied by holy ascetics before they were made into fortresses. At the former the famous saint Aswathāma gave his name to Aswathāmagiri, and at the latter place the holy hermit Gwālipā gave his name to Gwali-āwar. But the name of Kālanjarādri, or the hill of Kālanjara, is said to have been derived from Siva himself, who, as *Kāla*, or "Time," causes all things to decay (*jar*), and who is therefore the destroyer of all things, and the god of death. *Tapaswis*, or ascetics, of Kālanjara were therefore devoted to the worship of Siva.

The oldest historical mention of Kālanjara as a fortress is in A.D. 1023, when the place was besieged by Mahmud of Ghazni during the reign of the Chandel Raja Ganda¹ Deva. Its erection as a fortress is universally attributed to Chandra Varmma, the traditional founder of the Chandela family. But the inscriptions are silent as to Chandra Varmma, and give Nannuka as the founder of the family. There is, besides, good evidence to show that Kālanjara was a famous fortress even before the rise of the Chandelas. The Kalachuris of Southern India claim descent from a son of Siva, named Krishna, by a Brāhmani mother, who slew the king of Kālanjarapura, and *afterwards* took possession of the "nine-lakh country of *Dāhala Mandala*" (or Chedi).² Now the Chedis,

¹ The Raja is called Nanda by the Muhammadan historians, but his true name was Ganda, as recorded in all the inscriptions. In Persian letters, G might easily be changed to N by the substitution of a point for the "markaz" of "Gāf."

² Rice's Mysore Inscriptions, p. 64.

or Kalachuris, had possession of Dāhala Mandala (Tipurra or Tewar on the Narbada) as early as the 6th century, when they came into contact with Mangalisa Chalukya. Their occupation of Kālanjara must, therefore, have occurred some time earlier. I have already suggested that this event may have given rise to the Chedi or Kalachuri era, which, as I have shown, dates from A.D. 249. But the fort of Kālanjara must already have existed for some time before it attracted the notice of the Kalachuri chief Krishna. It seems highly probable, therefore, that the fortress may have been founded at least as early as the beginning of the Christian era.

The actual history of Kālanjara begins in A.D. 1019, when Mahmud of Ghazni advanced to the frontier of the Kālanjara Raja's dominions. The Raja collected a large army of 36,000 horse, 105,000 foot, and 640 elephants to oppose him. The result is thus related by the historian Nizām-ud-din Ahmad¹ :—

“When the Sultān approached his camp, he first sent an ambassador, calling upon him to acknowledge fealty and embrace the Muhammadan faith. Nanda refused these conditions, and prepared to fight. Upon this the Sultān reconnoitred Nanda's army from an eminence, and observing its vast numbers, he regretted his having come thither. Prostrating himself before God, he prayed for success and victory. When night came on, great fear and alarm entered the mind of Nanda, and he fled with some of his personal attendants, leaving all his baggage and equipments. The next day the Sultān, being apprized of this, rode out on horseback without any escort, and carefully examined the ground. When he was satisfied that there was no ambush and strategical device, he stretched out his hands for plunder and devastation. Immense booty fell into the hands of the Musalmāns, and 580 of Nanda's elephants, which were in the neighbouring woods, were taken. The Sultān, loaded with victory and success, returned to Ghazni.”

No reason is given by the historian for Mahmud's retirement. Ferishta, however, suggests that Mahmud must have been apprehensive about what might occur in the Punjāb and other countries in his rear, and was satisfied with what he

¹ Elliot's Muhammadan Historians, by Dowson, Vol. II, p. 464.

had done that year. It seems more probable, however, that Mahmud retired because he was doubtful of the result, and, like a prudent general, he went back to Ghazni to return with a large force.

Accordingly in A.H. 413 (A.D. 1022, or according to Ferishta one year later), Mahmud again undertook an expedition against the territory of Nanda (Ganda Deva).¹

"Having reached the fort of Gwâlior, he besieged it. Four days after, the chief of the place sent messengers promising 35 elephants, and solicited protection. The Sultân agreed to the terms, and from thence proceeded to Kâlanjar. This is a fort unparalleled in the whole country of Hindustân for its strength. He invested this fort also, and after a while, Nanda, its chief, presented 300 elephants, and sued for peace. As these animals were sent out of the fort without riders, the Sultân ordered the Turks to seize and mount them. The enemy perceiving this was much surprised, and Nanda sent a copy of Hindi verses in praise of the Sultân, who gave it to the learned men of Hind and other poets who were at his court, who all bestowed their admiration upon them. He was much pleased with the compliment, and in return conferred on him the government of 15 forts, besides some other presents. Nanda acknowledged this favour by sending immense riches and jewels to the Sultân, who then victoriously and triumphantly returned to Ghazni."

Kâlanjar is not mentioned again until after the occupation of Delhi by the Muhammadans, when Kutb-ud-din Aibak advanced to besiege it. According to the historian Hasan Nizâmi²

"The accursed Parmâr, the Rai of Kâlanjar, fled into the fort after a desperate resistance in the field, and afterwards surrendered himself, and 'placed the collar of subjection' round his neck, and on his promise of allegiance, was admitted to the same favours as his ancestor had experienced from Mahmud Subuktigîn, and engaged to make a payment of tribute and elephants, but he died a natural death before he could execute any of his engagements. His Dewân, or Mahtea, by name Aj Deo, was not disposed to surrender so easily as his master, and gave his enemies much trouble, until he was compelled to capitulate, in consequence of severe drought having dried up all the reservoirs of water in the forts.

¹ Tabakât-i-Akbari, in H. M. Elliot's Muhammadan Historians, Vol. II, p. 467.

² Tâj-ul-Maasir, in H. M. Elliott's Muhammadan Historians, Vol. II, p. 231.

"On Monday, the 20th of Rajab, the garrison, in an extreme state of weakness and distraction, came out of the fort, and by compulsion left their native place empty, and the fort of Kālanjar, which was celebrated throughout the world for being as strong as the wall of Alexander, was taken. The temples were converted into mosques and abodes of goodness, and the ejaculations of the bead-counters and the voices of the summoners to prayer ascended to the highest heaven, and the very name of idolatry was annihilated. Fifty-thousand men came under the collar of slavery, and the plain became black as pitch with Hindus. Elephants and cattle, and countless arms, also became the spoil of the victors."

The full name of this Raja was *Paramārddi Deva*, but he is usually known even to this day as *Paramāl* Raja, and to him the downfall of the Chandel dynasty is universally ascribed. According to Ferishta the Raja was assassinated by his minister, who again hoisted the Hindu flag on the fort.¹ But the place was soon reduced by the failure of the spring which supplied the garrison with water.

The government of Kālanjar was entrusted to Hazabbār-ud-din Hasan Arnal, and the fort thus became a part of the Muhammadan kingdom of Delhi. But it soon fell into the hands of the Hindus, probably during the weak reign of Aram Shah in A.H. 607, as it is related by Minhāj that Iltutmish sent a force against Kālanjar in A.H. 631, when the Raja fled.² The army returned with much plunder, but the fort remained in the possession of the Hindus.

Again, in A.H. 645 (A.D. 1247) Minhāj gives an account of a Raja with the mysterious name of Dalaki-Malaki, who occupied a hill fort to the south of the Jumna, who managed to escape from his fort while his women and children fell into the hands of the Muhammadans.

Four years later in A.H. 649 (A.D. 1251) the Muhammadan troops from Bayāna, Sultānkot, Kanauj, and Gwalior were sent to ravage the territories of Kālanjar.

Again, in A.H. 653 (A.D. 1255) Malik Kutlugh Khan, who had married the king's mother, rebelled, and being obliged to fly, took refuge in Kālanjar.

¹ Brigg's Ferishta, Vol. I, p. 197.

² Raverty's Tabakāt-i-Akbari, p. 733.

During all this time the fort was in the hands of the Hindus, and so it most probably remained for nearly three centuries more until it was taken by Sher Shah in A.D. 1545. During the strong reign of Ala-ud-din Khilji it might, no doubt, have been taken easily, but that king was too intent upon the plunder of the rich states of Southern India to care for the capture of a fort which had already been plundered by his predecessors. The shortness of Tughlak's reign alone prevented the annexation of Gwalior, Kālanjar, and other similar places. From the time of Muhammad Tughlak, when the Muhammadan dominions began to break up into a number of small states, Kālanjar remained in the quiet possession of the Hindus under the descendants of their old Chandela Rajas.

In A.H. 937 (A.D. 1530), a few months after his accession, Humāyun invested Kālanjar, but gave up the siege on the Raja expressing his fealty.¹

In A.H. 952 (A.D. 1545) Sher Shah laid seige to Kālanjar. According to Ahmad Yādgār his reason for attacking the place was because the Raja refused to give up Bir Singh Deo Bundela, who had sought refuge with him.² On Friday, the 9th of the 1st Rabia, while standing in the trenches, the king was badly wounded by a shell or rocket, which rebounded from the wall of the fort. On being carried to his tent he gave orders for an immediate assault. The historian Albas Khan³ says—

“Men came and swarmed out instantly on every side like ants and locusts, and by the time of afternoon prayers captured the fort, putting every one to the sword, and sending all the infidels to hell. About the hour of evening prayers the intelligence of the victory reached Sher Shah, and marks of joy and pleasure appeared on his countenance. Raja Kirat Singh, with 70 men, remained in a house. Kutb Khan the whole night long watched the house in person lest the Raja should escape. Sher Shah said to his sons that none of his nobles need watch the house, so that the Raja escaped out of the house, and the labour and trouble of this long watching was lost. The next day at sunrise, however, they took the Raja alive.

¹ Elliott's Muhammadan Historians, Vol. V, p. 189.

² Dowson's Note in Elliott's Muhammadan Historians, Vol. IV, p. 407.

³ Tārīkh-i-Sher Shah in Elliott, Vol. IV, p. 409.

"On the 10th Rabi-ul-awal, 952 A.H. (May 1545), Sher Shah went from the hostel of this world to rest in the mansion of happiness, and ascended peacefully from the abode of this world to the lofty heavens. The date was discovered in the words *azálash murd*, 'He died from fire.'"

When Islâm Shah reached the camp at Kâlanjar his first act was to order the Raja's execution.

In the early part of Akbar's reign the fort of Kâlanjar came into the hands of the Bâghel chief of Rewa, Raja Râmchandar, who in A.H. 977 (or A.D. 1569) made it over to Akbar. After that it remained for upwards of 120 years in the undisturbed possession of the Mughal kings of Delhi. Towards the end of the reign of Aurangzeb the fort was captured by the bold Bundela chief Chhatr Sâl. Apparently no attempt was made to recover it, and on the accession of Bahâdur Shah in A.D. 1707, the Emperor confirmed Chhatr Sâl in all his conquests.

On the death of the Bundela chief his dominions were divided between his sons, and the fort of Kâlanjar became part of the state of Panna, under the rule of Raja Hardeo Shâh. At the beginning of the present century the fort still belonged nominally to Panna, but was actually in the possession of a family of Brâhman brothers named Daryau Singh, Gangâdhar, and others. Daryau Singh and Gangâdhar were confirmed in their possession by the British Government. But as Daryau presuming on the strength of the fortress, gave shelter to bands of plunderers, and openly defied the British authority it was determined to take Kâlanjar from him, and thus to reduce his power of doing mischief. Kâlanjar was accordingly invested by Colonel Martindell in 1812, and, though his assault was repulsed, yet the chiefs were so doubtful of making a successful resistance that they surrendered the fortress the next day on the condition of receiving an estate of equal value in the plain below.¹ Since then Kâlanjar has remained in the hands of the British Government. At first it was held by a regular garrison, but since

¹ Pogson's Bundelas, and Gazetteer of Bundelkhand.

the mutiny the walls have been dismantled, and the fort is now held by a party of police.

The antiquities of Kālanjar were first noticed by Pogson, but they have since been very fully and ably described by Lieutenant Maisey (now General) in an interesting paper accompanied by numerous illustrations. I can add but little to his account of the antiquities of the place, but I have been fortunate in obtaining several inscriptions, and more especially some early ones, which escaped his notice.

There are two entrances to the fort of Kālanjar, of which the principal is on the north side towards the town, and the other at the south-east angle leading towards Panna. This latter, which is still called the Panna Gate, is now closed. The other entrance is guarded by seven different gates, which, beginning from below, are named as follows:—

- 1—Alam, or Alamgiri, Gate.
- 2—Ganes Gate.
- 3—Chandi, or Chau-burji, Gate.
- 4—Budh-bhadr Gate.
- 5—Hanumān Gate.
- 6—Lāl Darwāza.
- 7—Barā Darwāza.

The number of seven gates suggested to Colonel Pogson that Kālanjar must have been the “seat of solar worship” which he supposed to be confirmed by the name of *Ravi-chitra*, “the former word signifying the sun, and the latter a holy place.” But *Rava-chitra* simply means “sun-spotted;” and it is further unfortunate for the solar theory that during the Hindu rule there were only six gates, the lowest gate named the Alam Darwāza, having been added during the reign of the Emperor Aurangzeb Alamgir.

There is an ascent of about 200 feet up to the lowest gate, which is a battlemented building in the modern Muhammadan style. Over the archway outside there is a rhyming Persian inscription of three lines, recording the constructing of the gate by Muhammad Murād, during the reign of the Emperor Aurangzeb, when it was made as strong as the “wall

of Alexander." The following is the text of this inscription, as given by Lieutenant Maisey :—

الله هو الغني

شاه اورنگ زیب دین پرور	شد مرمت چون قلع کالنجر
چون محمد مراد از حکمش	ساخت درها محکم و خوشتر
از خرد سال جستمش میگفت	سد عظیم چو سد اسکندر

The date is given in the numerical value of the letters in the words سد عظیم, which represent—

$$60 + 4 + 70 + 900 + 10 + 40 = 1084 \text{ A.H.},$$

or A.D. 1673, in the 15th year of the reign of Aurangzeb Alamgir, after whom the gate received its name of Alam Darwāza.

Above this there is a steep ascent, chiefly by steps, to the second gate called the *Ganes Darwāza*.

At a short distance higher up in the bend of the road stands the third gate, named the Chandi Darwāza. As noted by Lieutenant Maisey, there is, in fact, a double gate, with four towers, on which account it is also known as the Chau-burji Darwāza, or "gate of the Four Towers." At this gateway there are several pilgrims' records of various dates, as given by Lieutenant Maisey, with the following dates : Samvat 1199, 1572, 1580, and 1600. The latest of these, Samvat 1600, or A.D. 1543, records the final capture of the fort by Sher Shah a mistake of two years. On the rock close by there is a much older inscription of fifteen lines, of the later Gupta period, which appears to have escaped the notice of Lieutenant Maisey. It is very nearly complete, but not in very good order. I can find neither date nor king's name in it.

The fourth gate, named Budha-bhadra Darwāza, is the gate of the "auspicious planet Mars (Budha)." It is also named the *Swarga-rohana*, or "Heaven-ascending Gate," owing to the stiff climb required to reach it. It possesses only one inscription of a pilgrim, dated in Samvat 1580, or A.D. 1523.

The fifth gate, or Hanumân Darwāza, is so named after a figure of the monkey-god carved on a slab resting against the

rock. There is also a reservoir called Hanumân-kund. There are, besides, numerous rock sculptures, which are very much weather-worn. Many, however, are still quite recognizable, such as Mahâdeva and Pârvati, Ganesa, the Bull Nandi, and the Lingam. Two inscriptions of pilgrims were noticed by Lieutenant Maisey, dated in Samvat 1530 and Samvat 1580. On the ascent beyond there are many weather-worn figures carved on the rock representing Kâli, Chandika, and the Lingam. There is also a small cave, or niche, containing a broken figure of Honumân. There are several short inscriptions of pilgrims, with the dates of Samvat 1560 and 1600.

The sixth gate, called the Lâl Darwâza, from its red colour, stands near the top of the ascent. To the west of this gate, in the Raoni, or *faussebraie*, immediately above the Bhairava-kund, there is a colossal figure of Bhairava cut in the rock. Here also are two figures of pilgrims represented carrying water in the usual manner in two vessels fixed to the end of a Banghi pole. Near one of them there is the following inscription in well-shaped Gupta characters :—

Samâdhigata pancha-mahâsabda-Sâmantâ Sri Vasanta.

"The illustrious Sâmantâ Vasanta (the possessor of the title of) pancha-mahasabdhâ."

The expression of *Samâdhigata pancha-mahasabdhâ* is commonly applied to *Sâmantas*, or petty chiefs, as I am informed by Pandit Bhagwân Lâl Indrajî. I take the figure of the water-carrier to represent the Sâmantâ himself.

Carved on the rock outside the Lâl Darwâza there is a long inscription of sixteen lines, which is unfortunately too much obliterated to be readable. In the fourth line I see the name of *Kâlanjarâdri*, or the "Hill of Kâlanjara."

A short ascent leads to the seventh, or uppermost gate, called *Bara Darwâza*, or the "Main Gate." As it stands now, it is undoubtedly modern, and its late date is confirmed by the only inscription attached to it of Samvat 1691, or A.D. 1634.

Inside the fort on the north face are four places of note named Sitakund, Sitasej, Pâtâl Gangâ, and Pându-kund.

Sītasej is a small cave, or recess, containing a stone bed and pillow for the use of a hermit.

The Pātāl Gangā is a large deep well, or reservoir, cut in the rock. The water is deep, and is constantly dripping and trickling from the roof and sides. The oldest inscription found here is of Samvat 1339, or A.D. 1282. The next is of Samvat 1500, or A.D. 1443; and a third of Samvat 1540, or A.D. 1483. Next comes a record of the Emperor Humāyun in Persian, dated in the year A.H. 936, or A.D. 1529-30. The latest is of Samvat 1640, or A.D. 1583, during the reign of Akbar.

The Pāndu-kund is a "shallow circular basin, about 12 feet in diameter," into which the water is constantly trickling from the crevices in the horizontal strata of rock. This *kund* is undoubtedly old, as it possesses a short inscription in Gupta characters reading "*Manoratha* * *"

Near the middle of the east face there is a natural hollow, in the bottom of which has been excavated in the rock a small reservoir with steps all round. This is called the *Budhi*, or *Burhya Tāl*. Its waters are believed to possess very great healing powers, as the leprous Rāja Kirat Brim, or Kirtti Varmma, after having bathed in the tank, found himself healed. This Raja is commonly called Krim Koth, or "Krim, the leper."

At the south-east angle is situated the Panna, or Bansākar Gate, which is now closed. The latter is the old name, the former having been given since the British occupation. It is covered by a small outwork. There are three gates. There are some pilgrims' records of Samvat 1550 and 1600, and near the Bhairon-ka-Jhirka, or Bhairava's well, there is an old record of Samvat 1195, or A.D. 1138, and a single sculpture of a pilgrim carrying two water vessels on a banghi-pole. Above the kund there is a colossal figure of Bhairava carved in the rock. The oldest pilgrim's record is Samvat 1194, or A.D. 1137. Amongst other figures there is a second water-carrier.

Near the middle of the south face is the *Mrig-dhāra*, or "Antelope's Spring," a small pool in an inner chamber

of the rampart into which water is constantly trickling. It is no doubt supplied, as suggested by Lieutenant Maisey, from the great reservoir of Kot-Tirth on the high ground close by.

Kot-Tirth is a large reservoir, nearly 100 yards in length, with several flights of steps and many remains of sculpture. Kot-Tirth, or the "Fort-Holy Place," is the chief object of pilgrimage in Kālanjar. In the south-east corner there is said to be a deep hole, and this was probably the original holy pool of the place, which was eventually enlarged to its present size. The Brāhmans declare that it is fed by springs; but as it occupies the highest ground in the fort, and there are no higher hills in the neighbourhood, its only feeders must be the springs of heaven during the rainy season. The name is also written Koti-Tirth, or the "ten million places of Pilgrimage," and Koth-tirth, or "the "Leprosy place of pilgrimage," where lepers are cured by bathing.

The great lingam of Nilakantha is situated in an outwork in the middle of the west face of the fort. The upper gate, leading into the outwork, is attributed to Raja Parmāl, or Paramārdi Deva, who reigned from A.D. 1167 to 1203. There are several inscriptions, but all of the 16th century of the Samvat, being dated respectively in Samvat 1540, 1547, 1557, and 1574. A second gate, which leads into the courtyard of the temple, has no inscription. But on the rock on the right hand of the descent there are numerous small caves and niches, with many statues and several inscriptions which will be noticed presently.

The actual shrine of the Nilakantha lingam is a small cave with the remains of a fine *mandapa*, or hall in front. The façade of the cave has been very rich, but it is now much broken and hidden by numerous coats of whitewash. On the jambs of the door there are figures of Siva and Pārvati with the Ganges and Jumna Rivers. These are of the Gupta period. The pillars of the hall are later, and belong to the time of the Chandels. The roof of the Mandapa is now gone, but most of the pillars and pilasters still remain, forming a square with four on each side, and four in the middle. In

roofing, the corners were cut off to form an octagon, as shown in Lieutenant Maisey's plan.¹ The lingam is made of a dark-blue stone, $4\frac{1}{2}$ feet high, and has silver eyes. It is at present the chief object of worship at Kālanjar, and, to judge by the pilgrims' records, it has been equally popular for many centuries.

Just outside the Mandapa of Nilakantha there is a deep *kund*, or rock-cut reservoir, called Swarga Rohina; and to the right of the kund in a rock recess, or niche, there is a colossal figure of Kāl Bhairav, 24 feet in height, standing in 2 feet of water. The sculpture is 17 feet broad. It is mentioned by Abul Fazl as being 18 cubits in height.² The figure has 18 arms, and is ornamented with the usual garland of skulls, with snake earrings and snake armlets, and a serpent twined round the neck. In the hands are various objects, of which the most prominent are a sword, a bowl of blood, &c. Beside this statue there is a figure of the skeleton goddess Kālī, 4 feet in height, which is now standing in water upwards of a foot in depth. The water trickles from above and falls on these figures. Beyond this sculpture there is a closed postern in the wall of the outwork, above which, on the outside, there is an inaccessible cave.

13.—KĀLANJAR INSCRIPTIONS.

In arranging the Kālanjar inscriptions I have begun with those inside the fort, which have dates. There are several older records both inside and outside, but as it is difficult to arrange them chronologically, I have placed them at the end of the account. Two of these belong to the Gupta period.

The earliest dated inscriptions at Kālanjar are found in the temple and on the rock of the Nilkanth outwork. They are limited to a period of 72 years during the reigns of Madana Varma and his son Paramārddi Deva, immediately prior to the Muhammadan conquest in A.D. 1203. The

¹ Bengal Asiatic Society's Journal, 1847, p. 193.

² Ain-i-Akbari, Vol. II, p. 29.

latest is in fact dated in the preceding year, Samvat 1258, or A.D. 1201-02. These inscriptions are the following :—

A.—Plate X.—Pillar in Nilkanth Temple.

Deva (?) Sri Nilakantha
 ma (?) nityam pranamiti.
 Aum! Sam 1186 Mahārāja Sri
 Madana Varmma Deva || mahā
 pratihāra Sangrāma Sinha||
 Mahā Nāchani Padmāvati||
 lānshuh Auji.

Adoration to Nilakantha

-was made * * * * *

Aum! In the Samvat year 1186 (A.D. 1129) during the reign of the fortunate king Madana Varmma Deva, the chief door-keeper, Sangrāma Sinha, (and) the chief dancing-girl, Padmāvati—written by Auji.”

The inscribers were, no doubt, two of the permanent attendants attached to the Nilakantha shrine, one being the chief door-keeper and the other the chief of the dancing-girls.

The last words *lānshuh Auji* I have given as explained by a Brahman.

B.—Plate X.—Piece of Broken Pillar.¹

Aum! Samvat 1187 Jyeshtha Sudi 9
 Sri mad Madana Varmma Deva||
 Kālanjarādri Sri Tri
 -salka * rdi ārā * na Sri (*end*)

(Incomplete).

“Aum! In the Samvat year 1187 (A.D. 1130), on the 9th day of the waxing moon of Jyeshtha, during the reign of the fortunate Madana Varmma Deva, on the hill of Kālanjara, Sri Trisalka” * *

This inscription is incomplete, as it ends abruptly with the word Sri in the 4th line.

C.—Plate X.—Rock near Nilakantha.

This inscription is engraved on the rock to the left, or north, side of the temple of Nilakantha. It was copied by Lieutenant Maisey, but the text and translation afterwards pub-

¹ Now lying at the police station in the town, and said to have been brought from the temple of Nilakantha.

lished by the editors of the Bengal Asiatic Society's Journal (1848, p. 321) contain so many errors that I have no hesitation in giving a fresh reading of the text—

1. Aum Swasti ! parama bhaṭṭāraka Mahārājadhiraṇa parameswara parama-ma
2. heswara Sri Kālanjarādhipati Sri Man Madana Varmma Deva charanambu
3. jārādhana tatparo dhimān dharmmaparāyana Mahārājapu
4. -tra Sri Solhāṇa suta mahā Sahanika maha selaita Kuma
5. rakula Kamalaṇḍu Mahārājaputra Sri Vachha Rājāḥ || Deva Sri
6. Kavidyanka Achhoda Rāūt Sri Udanah || Deva Sri Ni
7. lakanthasya Sutradhāra Sri Rāma suta Rupakāra Sri Laha
8. ḍa tad Babri Rupakāra Sri Lakshmi-dhara sāntyo mūrtti rēshi
- * 9. teti || Samvat 1188 Kārttika Sudi 8 Sanai ||.

“Aum-Swasti. During the reign of the supreme lord, the king of kings, the mighty sovereign, the chief of Kālanjara, the fortunate Madana Varmma Deva, then Maha Selaita, the Mahā Sahanika, son of the king's son Solhana, together with Sri Vatsa Raja Deva, the son of Prince Kamalāṇḍu * * * and the Rāūt Sri Udanah, set up this image of Nilakantha.

“Sculptors Sri Lāhada, son of the architect Sri Rāma and Sri Lakshmidhara.

“The Samvat year 1188 (=A.D. 1131) on the 8th day of the waxing moon of Karttika, on Saturday.

D.—Plate X on Rock near Nilakantha beside a figure of Narasinha.

1. Aum ! Dikshita Sri Prithvidhara sutaḥ Ṭhakkura Sri Sa
2. lhaṇa Pabhuvatasya tanayena Ṭhakkur Sri Nri Sin
3. hena Deva Sri Nri Sinhasya Mūrttiriyam Kārāpi
4. teti || Samvat 1192 Jyestha sudi 9 Ravan.

This is No. 5 of Lieutenant Maissey's inscriptions, but the editors of the Bengal Asiatic Society's Journal have misread the well-known title of *Thakkur* as *Sarkkāra*.¹ Immediately below it there is a second inscription to the same purpose,

¹ Bengal Asiatic Society's Journal. 1848, page 322.

but with the name of Râlhaṇa, instead of Salhaṇa. It reads as follows :—

Lower half of D.

1. Aum ! Dikshita Sri Prithivi-dhara Su
2. -taḥ Râlhaṇa ; tat Sutena Sri
3. Nri Sinhena Nri Sinha Mû
4. -rttiḥ Karapiteyam.

“Aum! This image of Nrisinha was caused to be made by Ṭṭakur Sri Nrisinha Deva, son of Ṭṭakur Sri Salhaṇa Pabhuvata, son of Dikshita Sri Prithivi-dhara, Samvat 1192, Sunday, 9th day of the waxing moon of Jyeshtha (A.D. 1135).”

“Aum! This image of the Nrisinha was caused to be made by Sri Nrisinha, son of Râlhaṇa, son of Dikshita Sri Prithivi dhara.”

E.—In a kotri or cell to the north of Nilakanṭha.

This inscription of 7 lines is in good order, but unfortunately it conveys no information of any interest. It opens with a dedication to Śiva, and closes with the date of *Samvat 1194, Chaitra badi 5 Budhau*. It is simply a record of two Brahmans (*dwija*) of the Bharadwāja gotra. The date is equivalent to A.D. 1137, Wednesday, 23rd February.

F.—Broken Inscription on Rock to north of Nilakanṭha.

This inscription is unfortunately broken on both sides and rather more than one-half of the lower part on the right is gone. There are 20½ lines of the small letters, and 7½ lines of much larger letters. At first I thought that there were two distinct records; and this is quite possible, but as the latter part is joined to the former in the middle of a line, it looks more like a continuation. As the words *Mahesa mûrtti* occur in the 6th line, I conclude that the record most probably refers to the great lingam of Mahesa, or Nilakanṭha. In the 12th line I see the name of Kâlanjarâdri, or “hill of Kâlanjara,” and in the last line there is the date of Samvat 1195, or A.D. 1138, in the middle of the reign of Madana Varmma.

G.—On Pavement of Nilakanṭha Temple.

1. Samvat 1222 Kshatravansodbhava Sri Lakshmana Suta Vâsu Deva nityam pranamati.
2. Pameṇa suta Sri Vara || Hara Deva suta Vâsabhu nityam praṇamati.

These two lines simply record the visits of pilgrims to the shrine of Nilakantha in S. 1222, or A.D. 1165. The first line gives the name of Vâsu Deva, the son of Sri Lakshmana, of the exalted Kshatra race. The second line gives the names of Pamena's son Sri Vara, and Hara Deva's son Vâsablu.

H.—On a large black stone, inside the Temple.

This is No. 1 of Lieutenant Maisey's inscriptions.¹ It consists of 52 lines. The date has been wrongly read by the translator as Samvat 1298, or A.D. 1241, instead of 1258, or A.D. 1201, which it actually is, and which it certainly ought to be, as Paramârddi Deva, the chief object of the record, died soon after the capture of the fort on 27th April 1203 A.D. The translator has not given any version of the first 24 lines, as they contain only a eulogistic and glowing address to Śiva and Pârvati.

The remainder of the inscription is given as follows :—

25. "He, the greatest of kings, having drunk, like draughts of honey and curds, the shining fame of the kings, his enemies, introduced a rule for collecting the land revenue without resistance from any foe (or he became the husband of the earth, which without resistance completed the ceremony of marriage).

26. "Some having been easily made prisoners and kept in his own house, were afterwards released. In a moment he caused some of them to wander from house to house; some he made to enjoy happiness; some, the fathers and children, with unceasing compassion for them, were seeking safety for their life within the walls (of some castle). Of the long arm of this king his enemies were afraid as of their *fatal* enemy.

"27. The king of Dashârna, like the wind of the Malaya mountain, kisses sportively the lips of the maidens, red like the pomegranate, seizes them by their beautiful tresses, removes the garments that shine brightly on the high bosoms of the maidens, and easily dries the perspirations occasioned by sport from the brows of the fair.

"28. By whom was not the king Paramârddi Deva esteemed? He was the god with the uneven arrows upon the earth, like a spiritual guide in the mysteries of love. Hundreds of maidens who approached his bed, and hundreds of foes who fell at his feet, were rejected by him.

¹ Bengal Asiatic Society's Journal, 1848, page 313.

"Thou firmament move on, and ye quarters of the world, proceed ; and thou earth enlarge ! Ye who have witnessed the widespread fame of former kings, now behold the rising glory of the fame of king Paramârdi, which, like a pomegranate bursting by the swelling of its seeds, extends over the world. Seeing the gifts of this king, who gives even more than is requested, and hearts of the Divine Jewel (*Vishnu's Chintâmoni*) and the heavenly cow (Kamadhenu, who grants all wishes) would have burst with shame if the former were not a stone, and the latter an animal.

"The king Paramârdi, having conquered his enemies, himself composed with his innate faith this eulogy of Purâri (Siva).

"Oh, ye venerable ones ! although my liberality is great, still my high qualities will not be remembered by vicious persons ; meditate therefore on such works as may satisfy your minds.

"The able Padma, the favourite of the valiant king Paramârdi, the grandson of an eminent artist, the son of Anrina, and superior to all artists, has, in company with Deoka, his younger brother, composed and inscribed this praise of the husband of Girija :—

"'As long as the earth, clad in the garment of the atmosphere, which is adorned with the garland of stars, joining, like two resplendent breasts, the eastern and western mountains ; as long as the earth rests upon the bed of the hood of the serpent-king, so long let this work of the king Paramârdi endure.'"

"Dated Monday ; the 10th of Kârtika Sudi, Samvat 1298. May prosperity and success attend !¹"

It is curious to remember that just 18 months after this bombastic record was composed, king Paramârdi gave up his fort to Kutb-ud-din Aibak. The inscription is dated Monday on the 28th October A.D. 1201, and the surrender took place on Saturday the 27th April A.D. 1203.

F.—Sandstone Slab in Nilakantha.

This inscription is also given by Lieutenant Maisey. It is carved on a soft yellow slab, and is in a very imperfect state, all the right half being missing, so that the translator was not able to make out very much of it. It mentions several of the Chandel kings by name, ending with Vira Varmma, who was the son of Trilokya Varmma, and the grandson of Paramârdi Deva. Its date must therefore be close to A.D. 1250—

¹ Bengal Asiatic Society's Journal, 1848, pp. 316 and 317.

during the period when the Hindus had recovered possession of the fort. The following translation is copied from the Journal of the Bengal Asiatic Society¹ :—

" (The meaning of the first six lines is ambiguous.)

" 7. Was born Bijayapāla. From him sprang Bhūmipāla, who, with his sharp sword, destroyed many kings.

" 8. His son made low the kings, as Agastya made low the mountain (the Vindhya Mountain). Having conquered the southern country, he speedily defeated the immense army of Karna.

" 9. * * * * * which was watered by the flood of tears of the gazelle-eyed females of the king of Mālwa * * *

" 10. His son Jaya Varmma Deva, who was devoted to the worship of Nārāyana (unintelligible).

" 11. Being wearied of government the king made it over to * * Varmma, and proceeded to wash away his sins to the divine river * * *

" 12. They departed their lives, and obtained all their desires in the next world.

" 13. After him Madana Varmma assumed the reins of government * * * (unintelligible).

" 14. He in an instant defeated the king of Gurjara, as Krishna in former times defeated Kansa. He undertook an expedition to conquer the world * * * *

" 15. The younger brother of king Madana was Pratāpa Varmma who was most powerful.

" 16. He was concerned for those * * * * * who were sick, and who were distressed; * * * * * who were lame and weak.

" 17. * * * He had double mouths and double eyes (?). He, the Lord, ever endowed with the eminent qualities of a hero. (The rest unintelligible and obliterated.)

" 18. He made the eyes of the women of * * * warm (with passion) and confounded the hearts of his enemies * * * Kamala (Lakshmi) who was against * * * in the field of battle,

" 19. * he looks as a hero (unintelligible)
* *

" 20. * * (unintelligible).

" 21. * * (unintelligible).

" 22. * * He who delighted the hearts of all the learned

¹ Bengal Asiatic Society's Journal, 1884, pp.319 and 320.

Vira Varmma, disdaining pleasure, subduing all his desires.

"23. * * (unintelligible).

"24. * * (unintelligible).

"25. * * he caused various temples, gardens, ponds and tanks to be made at places * *

"26. * * who was a patron of archers * * * who, like thousands of Sumeru, bestowed gold in Tula * * *

"27. Who established the images of Siva, Kamala, and Kâli in splendid houses * * *

"28. * * (unintelligible).

"29 * * * they, being tired, followed his steps in the order of their ranks. This eulogy was * * * by a person named Valluki Vira."

K.—Plate IX.—In a cell near Nilakantha.

This inscription is older than any of the preceding, but unfortunately the beginning of the first line is lost, and I can find neither date nor king's name. It records the setting up of a symbol of Maheswara. The characters may belong to the 8th century.

L.—Plate IX.—Near the Ganes Gate.

This is a fine inscription of 15 lines. I see the name of *Bhava Nâga* in the 10th line, and in the 1st line there is mention of the *Pânduvânâ-m-kula*. The characters belong to the later Gupta period. It is the oldest long inscription yet found at Kâlanjara.

M.—Outside the Lâl Darwâza.

This is a long inscription of 16 lines, but it is so much injured that very little is readable. I can see *Kâlanjarâdri*, or the "hill of Kâlanjara" in the 4th line, and something like Samvat 1226 at the beginning of the last line.

In the fort there are many other short records of pilgrims who paid their devotions at the shrine of Nilakantha and other places. I got 27 of these records, of which—

1	was dated in Samvat	1366
1	" "	1423
18	between 1500 and	1600
7	between 1600 and	1700

Two of them were found near the north gate, one in the Bhairon cave, two on the pillars of the Nilakantha temple, and twenty on the steps of the Kot Sagar, or Kot Tirath tank.

Outside the walls of the fort on the north face, and about halfway up the hill, there is a small isolated rock some 15 feet long by 10 feet in height. On this rock there is sculptured a famous lingam named Balkandeswara, and, beside it, the figure of a pilgrim carrying Ganges water at the two ends of a banghi-pole. Over the head of this figure there is an old inscription of one line of Gupta characters, 1 inch high, which reads as follows:— (See Plate IX—P.)

Samādhi gata pancha-mahāśabda Sāmanta Sri Vasantah.

There is a similar figure with the same inscription down in the plain below, which will be noticed presently. See Q.

On the back of the rock there is a figure of Mahesasuri Devi.

On the north face of the hill, and about 60 or 70 feet above the plain, there is a fine stone-walled tank called *Gangā Sagar*, 160 feet in length by 120 feet in breadth. It has a continuous flight of steps on three sides, and only a narrow flight in the middle of the fourth side. A long flight of steps leads to the top of the embankment. The whole of the steps and walls are formed of cut stones, including numerous carved pillars, bracket-capitals, and broken statues. On this site there has once been a very fine temple, as shown not only by these remains, but by a colossal figure of Vishnu, 13 feet in length, reclining on the serpent Ananta. There is also a head of a colossal boar, or figure of Varāha, built into the walls. There are no inscriptions; but it seems highly probable that the inscribed figure of a water-carrier, now fixed in a shed a short distance below, must have been taken from this site.

The figure of the water-carrier called *Sarwan Bābā*, is 6½ feet high by 3 feet broad. I suppose that the original name may have been *Saravāha*, or the "water-carrier," but the people are unanimous in calling it Sarwan, which was the

name of the son of Raja Dasaratha's sister. The story is similar to that of the Raja of Benares, as told in the Buddhist legend of the Sāma-Jātaka. The name Sarwan is well known in Northern India, and there are several popular songs founded on his story. His father and mother were blind, and were entirely dependent on him for their food. He is said to have carried them about in a banghi; hence the identification of the water-carrier as Sarwan was very natural. The Brahmanical account is found in the Mahābhārata, where it must certainly be an interpolation. The abstract of it, as given by Wheeler, is as follows¹ :—

“There is a curious episode in the original, in which Dasaratha declared that all his misfortunes had arisen from his having been cursed by a pious recluse whose son he had accidentally slain. The story is told at considerable length; but the main points are comprised in the following extract from the Adhyātma Rāmāyana :—

“Being in his younger days fond of hunting, the Mahārāja went one night to the side of a pond, where the sage Sarwan was procuring water. Sarwan attended on his father and mother with the purest affection. Both parents were blind, and Sarwan was in the habit of placing each of them in a separate basket, and slinging them across his shoulders; and in this fashion he conveyed them to all the places of worship then existing in the world. On the present occasion his parents had complained of thirst, and Sarwan had slung the baskets over the branch of a tree and gone down to the pond with a vessel to procure water. The Mahārāja, hearing the footsteps, thought it must be a deer, and shooting an arrow in the darkness towards the sound, it pierced the breast of Sarwan, who thereupon fell to the ground. The Mahārāja, perceiving he had shot a man, hurried to the spot, and was at once thrown into the deepest affliction. Sarwan, however, said :—¹ Be not distressed, O Mahārāja! I am a Vaisya, and not a Brahman, so that the heinous sin of the murder of a Brahman will not fall upon thy head. My parents, however, have performed sundry religious observances, and should their anger be raised against thee, they would reduce thee to ashes. Give them first a little water to allay their thirst, and then address them with humility and respect.’ The Mahārāja then drew out the arrow, and Sarwan expired. The Mahārāja then did as he was directed, and explained the circumstances to the bereaved parents, and expressed his deep contrition. At the request of the parents he then collected

¹ See Wheeler's Rāmāyana. Note, page 159.

wood for the funeral pile, and they then sat upon it, and directing the Mahâraja to fire it, were consumed with their son. Before this was accomplished, however, the old man uttered the malediction that he, like them, would die out of sorrow for the loss of a son."

The popular account, which is current amongst the people at the present day, is much fuller than Wheeler's abstract. Shortly after his parents became blind, Sarwan married a girl named Sânwâl, who is said to have been of an evil disposition. She had a cooking-pot made with two divisions, in one of which she cooked the rice with milk, making *khîr*, and in the other she cooked the rice with curd (or *chhâch*), making *mâheri*. The former she kept for her husband and herself, and the latter she gave to her husband's parents. After some time the old man complained that ever since his son's marriage their food had become very bad. Sarwan then managed to change plates with his father, and dipping his finger in the coarse food he became aware of his wife's duplicity. Ashamed of his wife's conduct he got a *kânwar*, or bângghi-pole with two baskets, and placing his parents in them, he put the bângghi on his shoulder and started off on a pilgrimage. After passing through several places they reached Ayodhya. As the old people were thirsty, Sarwan hung up the bângghi on a mango tree, and took a vessel to fetch some water. On reaching a tank, surrounded by deer, he stooped down to fill the vessel, when he was suddenly wounded in the side with an arrow, shot by Raja Dasaratha, who mistook him for an antelope. As he fell, Sarwan called out "Râm! Râm!," which attracted Dasaratha's attention. Then Sarwan begged the Raja to take some water to his parents, who were in the bângghi hanging on the mango tree near at hand. Dasaratha took a lota of water to the blind couple, who, hearing a strange voice, demanded who he was. The Raja then told the whole story, and the bereaved parents at once cursed him, saying—

Jas kinâ tum Sarwan sokâ,
Tas hui he tum Râm birogâ.

"Like as you have caused grief through Sarwan,"
"So shall you suffer grief through Râm."

Then the two blind people died, asking the Raja to have their bodies burned along with that of their son.

After a time when Râma was about to leave Ayodhya on his 12 years' exile, the curse of the blind parents came to Dasaratha's mind, and he told the whole story to his wife Kausalya—

Tâpas Andh Sâp sudhi ât,
Kausalâ hi sab kathâ sunât.

The legend is undoubtedly an old one, as it forms the subject of one of the Buddhist Jâtakas. It is not found amongst the existing sculptures of Bharhut; but it is represented on the back of the western gateway of the Sânci stûpa, and on the eighth step of the staircase of the Jamâlgarhi stûpa.¹ In neither of these representations is there any trace of the banghi. On the contrary, the two blind parents are represented seated in the former sculpture in front of their *pansals*, or leaf-roofed huts, and in the latter in a sort of arbour, where they are receiving the pot of water from the hands of the king. In these Buddhist sculptures, however, the king is not Dasaratha, Raja of Ayodhya, but Peliyaka, Raja of Benares. This story, as related by Spence Hardy, is as follows²:—

"When Gotama Bodhisat was born in a former age, as Sâma, son of the hermit Dukhula, he rendered every assistance to his parents, who had become blind when he was sixteen years of age. It happened that, as he one day went for water to the river, the king of Benaras, Peliyaka, entered the forest to hunt, and as Sâma, after ascending from the river, was, as usual, surrounded by deer, the king let fly an arrow, which struck Sâma just as he was placing the vessel to his shoulder. Feeling that he was wounded, he turned his face towards the spot where his parents dwelt, and said, 'I have no enemy in this forest; I bear no enmity to any one;' though, at the same time, he vomited blood from his mouth. Thus he reflected, 'I have omitted the exercise of *maitri-bhawana*, and some one has sent against me an arrow; for what reason it can be I cannot tell, as my flesh is of no use, neither my skin; I must therefore make enquiry.' After saying this to himself, he called out, 'Who is it that

¹ See Fergusson's *Tree and Serpent Worship*. Plate 36, fig. 1, and the 8th step of the staircase, which is now in the British Museum.

² *Eastern Monachison*, p. 275.

has shot me?' and when he learnt that it was the king, he related his history to the monarch, and said that his greatest grief arose from the thought that his blind parents would now have no one to support them, and would perish. But when the king perceived the intensity of his grief, he promised that he would resign his kingdom, and himself become the slave of his parents, rendering unto them all needful assistance in the stead of their son. Soon afterwards Sâma fell down senseless from the loss of blood; but a dewi, who in the seventh birth previous to the present, was his mother, having perceived that if she went to the spot important consequences would ensue from her interposition, left the dewa-loka, and remaining in the air near the king without being visible, entreated him to go to the *pansal* and minister to the wants of the blind parents of Sâma. The king was obedient, and went to the place, where he informed the hermit and his wife that their son was slain. On hearing of his death, they uttered loud lamentations, and requested to be taken to the place where he had fallen. They were, therefore, brought to it, when the mother, in placing her hand upon his breast, perceived that it was warm; at which she rejoiced greatly, as she knew by this token that he was not dead. She therefore resolved upon repeating a *sacha-kiriya* for his restoration, and said, 'If this Sâma has in any previous period obtained *kusula*, by the power of this virtue (*sacha*) may the consequences of this calamity be removed! if from the time of his birth until now he has been continent and true, supported his parents, and excelled in the acquisition of merit; if I have loved him more than my own life; if we, his parents, possess any merit whatever; by the power of these virtues (*sacha*) may the poison pass away from the body of Sâma, as the darkness vanishes at the rising of the sun!' On the utterance of these words, Sâma revived, and sat up; after which the *devi* also said, 'If I have loved Sâma more than any other being, by the power of this *sacha* may the poison or this arrow be destroyed!' Then by the united *sacha-kiriya*s of the *devi* and his parents, Sâma was restored to perfect health. The parents also received their sight, and the *devi* repeated the ten virtues of a king to Peliyaka, by attending to which he was enabled to reign in righteousness, and was afterwards born in the deva-loka, as Sâma and his parents were in the Brahma-loka."

Here, again, in this Buddhist version there is no trace of the Banghi story. At the present day the Banghi is an essential part of the legend; and forms a pictorial frontispiece to the lithographed copies of the "Sângit Raja Sarwannâth."

14.—AJAYGARH FORT.

The fortress of Ajaygarh is situated just 20 miles by road to the south-west of Kālanjar. It stands on a lofty, flat-topped spur of the Vindhya Hills, within sight of the River Kiyān, or Ken, which is only 8 miles distant. It is of about the same height as Kālanjar, or between 700 and 800 feet above the plain. The lower part of the hill, which is of granite, is not very steep, but the upper part, which consists of a reddish sandstone, is very abrupt and quite inaccessible. The size of the fort has been very much under-estimated, as being only about 1 mile in circuit, whereas it is only a very little smaller than Kālanjar, as may be seen at once by a comparison of their plans.¹ The fort is very nearly 1 mile in length from north to south, and only a little less from west to east. It is nearly triangular in shape, and the circuit of its walls is just 3 miles, that of Kālanjar being under 4 miles.

The foundation of Ajaygarh is referred to an unknown raja, Ajay Pāl. But the name of Ajaygarh is not found in any of the inscriptions, the name being invariably given as Jayapura-dûrgga, or the "Fortress of Jayapura."²

The fort has two gates; one to the north being simply called Darwāza; and the other to the south-east, called the Tarhaoni Gate, as it leads directly upon the village of Tarhowan, at the foot of the hill. In the inscriptions I find mention of the Kālanjara-dwāra, or Kalanjar Gate, and this must be the "Darwāza" on the north, as it leads directly towards Kālanjar.

Near the northern gate there are two tanks excavated in the rock, which are known by the name of Gangā-Jamnā. Almost exactly in the middle of the fort there is a large tank cut in the rock called Ajay-Pāl-ka-Talao. It is evidently old; but the black stone figure on its bank, which is called Ajay Pāl, is clearly a statue of the four-armed Vishnu.

Near the southern end of the fort there is another tank called Parmāl Tāl, or the Reservoir of Raja Paramārd.

¹ See Plates VII and XI, which are drawn on the same scale.

² Bengal Asiatic Society's Journal, 1837, p. 887.

Close by there is a ruined temple of the Chandel times, which is also attributed to Raja Parmâl; and at a short distance there are two other temples standing together, which are simply known as Chandeli Mahal. All these temples are in ruins.

The largest of the three temples is 60 feet long by 40 feet broad, with its entrance to the west. The northern portion has fallen down. The walls of the standing portion are very richly ornamented.

The second temple, of the same size, also faces the west. This also was very highly decorated. But all the numerous figures which once adorned its walls are now gone, except that of a single four-armed female.

The third temple near Parmâl's tank is slightly smaller than the others, its dimensions being 54 by 36 feet. The angles of the sanctum seem to have been laid out on the circumference of a circle.

On the rock at the Tarhaoni Gate there is a row of eight goddesses (the Ashta-sakti), of whom seven are sitting and one standing. They are each 3 feet high and 3 feet 10 inches broad, in separate frames. They are roughly executed. Their names are written below them, amongst which I could read *Sri-Chandi*, *Sri-Chamundâ*, *Sri Kâlikâ*, and also the name of *Jayapura-dûrgga*. Both Durgâ and Kâli are amongst the figures.

Close by there is a long inscription cut in the rock, 7 feet by 2 feet 4 inches. It contains several names of the Chandel Rajas, beginning with Kirti Varmma and ending with Bhoja Varmma. The characters are of the square form called *Chitra-varna*, or "Ornamented letters." There are also several rows of small Jain figures sitting with their hands in their laps. Near these there is a cow and calf, and a four-armed goddess sitting with a child in her lap, and with five pigs above one another on her right side, and eight pigs in pairs above one another on her left hand. This is evidently the figure of *Shashti*, the goddess of fecundity.

There is no mention of Ajaygarh by name in any of the Muhammadan histories. I once thought that it might be

the stronghold of the mysterious *Dalki-wa-Malki*, which was captured by Ulugh Khan, the Wazir of Naseruddin Mahmud, in A.H. 644, or A.D. 1246. The fort was certainly in existence some time before, as it is mentioned in the earliest of the Ajaygarh inscriptions as Jayapura-dûrgga, in Samvat 1208, or A.D. 1141, during the reign of Madana Varmma. Now we learn from another Ajaygarh inscription, dated in Samvat 1345, or A.D. 1288, that Nana, the grandson of Malika, was the minister of the Chandratreya kings, that is, of the Chandel Rajas. We learn also that he was a contemporary of Raja Bhoja Varmma, the grandson of Raja Trailokya Varmma, who was therefore a contemporary of Malika. I thought, therefore, that the strange combination of names in Tiloka wa-Malika might represent the joint names of Tilaki (Trailokya) and his minister Malika. It is true that only one raja is spoken of; but the conjunction *wa* "and" would seem to show that there must be two distinct names. That Trailokya Varmma actually possessed Ajaygarh we learn from another inscription dated in Samvat 1269, or A.D. 1212, which was found outside the tank of Pâtâl Sar inside the fort.

The position of the stronghold of Dalaki wa-Malaki is described by Minhâj as being "in the vicinity of the Jumna between Kâlanjar and Karra." But in the position here indicated there are no defiles, and no mountains and no jungles, as described by Minhâj, and I have accordingly given up this identification in favour of another, which will be discussed in my account of Bâghelkhand.

15.—AJAYGARH INSCRIPTIONS.

The inscriptions found in Ajaygarh belong chiefly to the later period of Chandel history after the occupation of Mahoba and Kâlanjar by the Muhammadans. The latest historical records at Kâlanjar belong to the reign of Paramârddi Deva; but at Ajaygarh we have the series continued from Madana Varmma by one inscription of Trailokya Varmma, the son of Paramârddi, followed by three of his grandson Vira Varmma I, two of his great-grandson Bhoja Varmma, and one of his

grandson's grandson Vira Varmma II. The following is a brief account of these inscriptions:—

A.—Plate XII.—On Jamb of Upper Gate.

1. Aum ! Samvat 1208, Mârg-ga badi 15
2. Sanau || Jayapura durggiye sa-
3. mast lokânâm Râût Sri Ve-
4. da Kshatriya-Jâtiya Kortia
5. grâmiya Râût—Sri Jauna Pâ-
6. la putra annena kî dâ bhudye Si-
7. rothayena pralipâdanam atam
8. Bhadranantam Sri Sri Karanika
9. Thakkur Sri Ghal * era, Thakkur Sri
10. Jâlhanam | Thakkur Sri Mahidhara Tha-
11. kkur Sri Pâsala | vareṭha lahaḍaṇḍa bhrâ |
12. tiyana 13, Sankali Ājan 52
13. Patairena ḍiya vettakara 1 Sri Soma
14. marâjasya gramohoddhi * ta ni grâ-
15. niya bhâga pâthâ Widyârddâh Sana
16. sa Kshechâsya dranâh || Râjyena Sri,
17. man Madana Varmmanah || Thâ-Sri-
18. Sutradhâra Suprata-

"In the Samvat year 1208, on Saturday, the 15th day of the waxing moon of Mârgga [Saturday, 10th November 1151 AD.], in the fort of Jayapura, for the use of all people, the Râût Sri Veda, a Kshatriya by caste, of the village of Kortia, the son of Râût Jauna Pâla, built a (*Sirotha* ?)

. Sri Sri Karanika, Thâkkura
Sri Ghala—bera | Thakkur Sri Jâlhana Thakkura
Sri Mahidhara | Thakkura Pâsala

"during the reign of Sriman Madana Varmma, Sculptor, Suprata.

B.—Plate XII.—On Jamb of Upper Gate Samvat 1237.

1. Samvat 1237 Ashâdha
2. Suddhi 2 Some-Jayapura-dûrgi-
3. ya Samast lokânâm Râût
4. Sri Virena Tejlaputra Kshatri-
5. yam Kotia grâmiyam anenu
6. Durbhikshenaiyâ pâdanam mârgha da
7. sutri dhâna dresavo suta prabhriti pra-
8. tipadanakshatam 1 todanamta rava
9. Sri Sri Karana varetho 13— (? varegi)
10. Samkala Ā 12, patairasya
11. nauli cha

"In the Samvat year 1237 (A.D. 1180), on Monday, the second day of the waxing moon of Ashâdha, in the fort of Jayapura, for the use of all people, by the Râût Sri Vera, the son of Tejla, a Kshatriya of the village of Kotiâ, during a time of famine, a *bauli* (well) was built on the road. May his successor preserve it."

(The remainder has not been made out.)

As the week day of Ashâdha Sudi 2 was not Monday, but Wednesday, I conclude that *Some*, or Monday, was a mistake of the writer for *Saumye* or Wednesday.

C.—Plate XII.—On jamb of Upper Gate.

1. Samvat 1243 Jyeshtha Sudi || Budhe
2. Jayapura-dûrggiye Samast lokâ-
3. nâm Râût Sri Sihaḍa, Râût Sâ-
4. tana putra, Kshatriya Jâtiye, ko-
5. tiâ grâmiya anena chautre ni-
6. vâraṇa Sri pratipâdanam kritam ta-
7. danântaramba Sri Sri Karaṇa vare-
8. tha 103 Samkali â 53-swasti.

"In the Samvat year 1243, on Wednesday, the 11th day of the waxing moon of Jyeshtha, for all people the Râût Sri Sinhada, son of the Râût Sântana, of the Kshatriya race, of the village of Kotia, established a Chautra."

(The remainder has not been made out.)

The week day should be *Sunday*, 1st June A.D. 1186, and it is probable that it should be read *Rave*, or Sunday instead of *Budhe*.

D.—Plate XII.—Outside Tank of Patal-Sar.

1. Aum! Samvat 1269, Phâlguna badi (?) Sanaw; Raja Sri Trailokya Va-
2. rmma Devav ijaya râjye.....

(The remainder of this inscription has not been read.)

It is said by a Simla Pandit not to be Sanskrit, but some vernacular dialect. It is the only record yet found of Trailokya's own reign. The day of the month is obliterated, but as the week-day is certain, the date must be either the 2nd or the 9th of Phâlguna badi, equivalent to either Saturday the 9th, or Saturday the 16th February, A.D. 1213. His father Paramârddi was assassinated in A.D. 1203. This is

the only inscription of Trailokya that has yet been found. But his name occurs in several of the Ajaygarh inscriptions as the son and successor of Paramârddi and the father of Vira Varmma I.

E.—Plate XIII.—Rock Inscription.—15 lines.

Eight lines to left of crack in rock ; seven lines to right of crack

This long inscription is engraved on the rock, with a crack dividing it into two portions. The left-hand portion of seven lines is bounded by the crack, and the record is continued by eight more lines on the right hand. The following abstract gives the substance of the inscription, as read by a Simla Pandit :—

“From Chandra sprang the Chandravansa race, in which was born Raja Kirtti Varmma, whose songs the learned still sing for his glory. His son was Sulakshana Varmma, who conquered Malwa. To him was born Jaya Varmma, whose son was Prithvi Varmma, whose son was Madana Varmma. Next came Trailokya Varmma, the destroyer of his enemies, whose sons were Yaso Varmma and Vira Varmma. The latter became Raja, and married the daughter of Raja Govinda, the lord of the earth (*kshitiipati*), named Kalyâni Devi, who was equal to Pârvati. For the increase of her own merit she presented to the Brahmans the *Amrita-Kupa*, or “Pool of Amrita” (now called the Gangâ Jumâ Tank), and also a temple. The record was composed by Ratna Pâla, the son of Hari Pâla. In the year of Vikrama (Vikrama Vatsara) . . . (date in words, apparently Samvat 1312) . . . in the reign of Sri Mad Vira Varmma, on Thursday, the 13th of the waxing moon of Vaisâkha (Thursday, 22nd April 1255 A.D.)”

I have failed in tracing the Govinda Raja mentioned in this inscription. He may, perhaps, have been the Raja of Nalapura, or Narwar, the predecessor of the famous Châhada Deva, the gallant opponent of the Muhammadans.

F.—Plate XIV.—On wall of Temple.

1. Aum 1 Aswavaidya Tha: Bhojakasya putra A-
2. bhaya Deva Iswara nityam pranamati Vi-
3. RA VARMMMA râje, Samvat 1325, Vasta gotrah (? Vatsa).

“Abhaya Deva, son of Thakkur Bhojaka, of the Vatsa gotra, offered his adoration to Iswara during the reign of Vira Varmma in the Samvat year 1325 (A.D. 1268.)”

G.—Plate XIV.—On Rock near figure of Ganes.

This inscription gives the genealogy of the Chandela Rajas from Kirtti Varmma down to Vira Varmma I. It is doubly dated, first in words in lines 19 and 20, as follows:—

“Sāgarānala-vedendu yukte Samvatsare varshe Māghamāsi site pakshe trayadasyam Vidho-dine.”

Here *Sāgara*, the Ocean, stands for 7, or the seven seas; *anala*, or fire, stands for 3; *Veda* stands also for 3; and *Indu*, the moon, for 1. The whole date is therefore 1337, by joining together the oceans with *fire*, the *Vedas*, and the *moon*, in the white half of the month of Māgha, on the 13th Monday (*Vidho-dine*). The date is then repeated more concisely in figures, as “Samvat 1337, Māgha Sudi 13 Some, or Monday, the 13th of the waxing moon of Māgha, in the Samvat year 1337 (Monday, 3rd February, A.D. 1281).

This inscription, as explained by a Simla Pandit, records the setting up of a statue of Vināyaka (Ganesa) by Ganapati, the minister of Vira Varmma.

H.—Slab in Indian Museum, Calcutta.

The slab bearing this long inscription is now in the Indian Museum in Calcutta. The text, with a specimen of the letters, and a translation, was published in the Journal of the Asiatic Society in 1837.¹ It records the genealogy of Nāna, one of the ministers of the Raja Bhoja Varmma in Samvat 1345, or A.D. 1288. (See verse 24, where he is called “Minister of the Chandrātreyā race.” He set up an image of Hari (or Vishnu) in the port of Jayapura (*Jayapura-dūrgge*) in honour of his forefathers.

The inscription was composed by Amarapati and written in *Chitravarṇam*, or “ornamental letters,” which, we thus learn, was the name given to the peculiar square characters in common use throughout the Chandel dominions and the neighbouring countries from about 1115 to 1400 A.D. The inscription is itself of little value.

¹ Bengal Asiatic Society's Journal, Vol. VI of 1837, p. 885.

I.—Two long lines, 7½ feet, large letters.

1. Aum namah Sri Kedaraya Kayastha Vâstavya
 . . Kata *jayapura-durgaya* Thakkur Sri Vidana tatputra
 . . Sri.ja Thakkura Sri devenasansta, Sri
 Kedâra, Pârvati, Vrishabha, Krishna Sri * Kâtâ.
2. Kâyastha vâstavya.

ƒ.—Plate XV.—At the Tirhawan Gate.

This inscription of 15 lines in very large letters is carved on the rock near the Ashta Sakti. It has not yet been translated, but I have noted the following names :—

- Line 4.—Sri Kirtti Varmma.
 „ 5.—Paramârddi.
 „ 13.—Sri Bhoja Varmma.
 „ 14.—Sri Mad Bhoja Mahi Mahendra.

I cannot find any date in it, but, as we have an inscription of himself, dated in Samvat 1345, or A.D. 1288, and another of his son, dated in Samvat 1372, or A.D. 1315, the inscription may be assigned to about A.D. 1300.

K.—Near a female figure—11 lines.

1. Samvat 1346 samaye.
2. Jayapura-dûrgge.
3. . . Mahârâja Sri Bho-Varmma De-

This inscription is too much injured to be readable. Several of the letters are quite clear, but they are all isolated, except towards the end, where I can read *pâla* and *tasya*. The *ja* of Bhoja is omitted in the original.

L.—Over a female figure.

1. Samvat 1349 || Jyeshtha badi 14 Sukre dine
2. Sadhu|| Mana Suta ama Deva putra Arjuna tasya bhâriyâ-
3. Gângo || nityam damaya . . ha Iswara pranamati|| Sri.||

“In the year 349 (A.D. 1292,) on Friday, the 14th of the waxing moon of Jyeshtha, Gângo, the wife of Arjuna, son of Ama Deva, the son of Manu, performed adoration to Iswara.

M.—On upper round step of Temple.

1. Phulahe Raushahne putra Jyarti
2. tranamati . cha|| Sam. 1371.

I cannot satisfactorily read the name of the pilgrim who made this record of his visit to Ajaygarh in Samvat 1371, or A.D. 1314. It looks like Jyaitu, the son of the flower man Raushan.

N.—To west of gateway outside.

This long inscription of 12 lines is too much injured to be easily read. It belongs to the reign of Vira Varmma II, as it is dated in Samvat 1372, or A.D. 1315. It has been so repeatedly whitewashed over that the letters are now filled up.

O.—Plate XIV.—On pillar of gate.

1. Aum! Ganapataye namah|| . . . Jayapurva, &c. &c.

I can make out nothing of this inscription, and a Pandit to whom it has been shown declares that it is not Sanskrit. The name of Vira Nripa occurs in the 12th line, and the date is in the last two lines—"Samvat 1372 Paush badi 10 Sanau," or Saturday, the 22nd November 1315.

P.—On rock outside gate—4 lines.

In 4th line name of Kirtti Varmma.

16.—BACHON, OR BACHAUND.

Bachaund, or Bachon, as it is commonly pronounced, is a large village situated under a hill on the left bank of the Kiyān, or Ken River, 15 miles to the west of Ajaygarh, to which state it now belongs. It contains about 500 houses, and upwards of 2,500 inhabitants. There is a fine large tank called the Bilhariya TAL, faced with boulder stones, and to the north of the village there are many broken sculptures and other remains, which show that Bachon was formerly a place of considerable importance. Amongst these there was—

- 1 figure of the Vāman Avatār.
- 1 group of Hara Gauri.
- 1 figure of Vishnu.
- 2 lingams.

Several old carved pillars of small size.

1 broken slab with the following inscription in 12 lines—

1. (Swas) ti Samvat 143 (3)
2. Sâke 1298 . . .
3. . . nibhi Nâga
4. sahum jatto so râmo.
5. Bhilama Deva râjo.||
6. Vachhiuni-Sthâno
7. . Sri Gopâla Devahya.
8. . namo.

(*The rest not made out.*)

The name of the place is most probably given in the 6th line as *Vachhiuni-Sthâna*, or Bachhiun. The Raja Bhilama Deva, mentioned in the 5th line, must be one of the later Chandels. Unfortunately we do not possess the genealogy of the later Princes, so that it is impossible to identify him. The date of Sake 1298, or A.D. 1376, lies in the middle of the reign of Firoz Shah Tughlak, when the Delhi empire was weak, at which time both Kâlanjar and Ajaygarh were in the possession of the Chandel Rajas.

17.—KHAJURÂHA.

I have already given a long account of Khajurâha, with a detailed description of its principal buildings, which form by far the finest group of Hindu temples now existing in Northern India.¹

Khajurâha, or Kharjurpura, is first mentioned by name by Abu Rihân in A.D. 1031, who calls it the capital of Jajâhuti.² There are no traces of fortifications, but it is probable that Khajurâha may once have been a walled town, as the people refer the name to a pair of gold *khajur* trees (date-palms), which, they say, were fixed on one of the city gates. A more natural derivation would have been from the khajur trees, amongst which the town was originally situated. At present, however, there are not many of these trees in the neighbourhood.

¹ See Archaeological Survey, Vol. II, p. 412, and Vol. X, p. 16.

² Reinand's Fragments, p. 85, Text, and p. 106, Translation. See also Elliott's Muhammadan Historians, by Dowson, Vol. I, p. 57.

The name of the place is found in the inscription of Ganda Deva, dated in Samvat 1056, or A.D. 999. It comes immediately after the date "*Sri Kharjuravâtika Râja Dhanga Deva rājye*," which has been entirely misread by Sutherland as "*Sri Prithvi-pati Râja Sri Banga Deva rājye*."¹ *Kharjuravâtika* would thus appear to have been the original form of the name, which was shortened by dropping the *v*, thus making *Khajurâtika* and *Khajurâha*.

The place is afterwards mentioned by Ibu Batuta, who calls it *Khajurâ*, "at which there is a lake about a mile in length, and round this are temples in which there are idols. At this place resides a tribe of Jogis with long and clotted hair. Their colour inclines to yellow, which arises from their fasting. Many of the Moslems of these parts attend on them, and learn (magic) from them." As Ibn Batuta visited the place about A.D. 1335, I infer from the tolerance of the Hindu ascetics that *Khajurâha* was still in the possession of the Chandel Princes, while the Moslems were in occupation of Kâlanjar and Mahoba. It is almost certain that the Hindus still held Ajaygarh, as there are at least two inscriptions in that fort, dated in Samvat 1372, or A.D. 1315, during the reign of Vira Varmma II.

At the present day *Khajurâha* is only a small village. In 1852 it was said to contain only 162 houses, which would give a population of less than 1,000 persons. But in 1874 I was told that there were 350 inhabited houses, which would give a population of about 2,000 persons. The Brahmans, who form one-sixth, are of two classes, Kanaujiyâ and Jajhotiâ. There are a few Chandel thakurs, or zamindars.

I searched diligently for other ruins, in the hope that some older remains would be found. The oldest was a triangular fragment of a large inscription in Kutila characters, bearing the names of Harsha Deva and Sri Kshiti Pâla Deva Nripati. If it belongs to the time of Harsha Deva, the father of Yaso Varmma, and the grandfather of Dhanga Raja, its date must be about A.D. 900.

¹ Bengal Asiatic Society's Journal, Vol. VIII, p. 175.

The oldest building now standing at Khajurâha is, no doubt, the oblong hypæthral temple of Chaunsat Jogini, or the "sixty-four female goblins," who drink the blood of the slain. As I have described this curious building in a former report, I need only mention here that it is an oblong quadrangle, 102½ feet by 59½ feet, situated on a low rocky hill, 25 feet above the level of the plain. It contains 64 small cells distributed round the sides, and one large cell in the middle of the back wall. It is built entirely of granite, and is therefore, no doubt, older than all the other temples of Khajurâha, which are built of sandstone. In my Report I ventured to assign its age as prior to A.D. 900, and this assignment I am now prepared to verify by two short inscriptions which I found on the pedestals of two small statues of the enshrined Joginis. The cells are small, being only 2 feet 4½ inches broad by 3 feet 9 inches deep. The figures are therefore small. I found only three of them now remaining, the largest of which was 3 feet in height, and the others 2 feet 3 inches in height. The largest with eight arms represents the goddess Bhainsasuri Devi, killing the buffalo demon. On the pedestal is inscribed the name of *Hinghalâj*. On one of the others I found the name of Maheswari. As the characters of these records appear to be older than those of the dated Khajurâha inscriptions, with the single exception of those on the statue of Hanumân, which bears a date in three figures only, I conclude therefore that the Chaunsat Jogini Temple must be older than any of the other temples at Khajurâha, of which one at least dates as far back as Samvat 1011, or A.D. 954. I think therefore that the Chaunsat Jogini may date from the very foundation of the Chandel rule, or from the early part of the 9th century. The temple at Râhilya, near Mahoba, which was built by Râhila Varmma, about A.D. 900, is of sandstone; and I believe that all the granite temples must be older.

The next oldest building is most probably the small square temple of Brahmâ on the bank of the lake. It is built partly of granite and partly of sandstone, and is therefore most probably older than all the remaining temples, which are of sandstone only.

Khajurâha is described by Abu Rihân as the capital of the kingdom of *Fajdhuti*—a name which recalls the Chi-chi-to of the Chinese pilgrim Hwen Thsang. According to him Chi-chi-to was situated at 1,000 *li*, or 167 inches, to the north-east of Ujain, which is considerably under the real distance of about 250 miles. If, however, Hwen Thsang recorded his distances according to the number of *kos* between the two places, he must have allowed only 2 miles to each of the *chaurasi*, or 84 *kos*, distance between the two places. But as the *kos* of Bundelkhand and Malwa varies from 3 to 4 miles, the real distance would have been about 250 miles, which agrees almost exactly with the relative positions of Ujain and Khajurâha.

I have found the name of the province in two different inscriptions, one of the time of Kirtti Varma, and the other of the time of Paramârddi. In the former one, which I discovered at Mahoba, the name is written *Fejâkhyâ* and *Fejabhukti*. The latter form at once recalls the name of *Tirabhukti*, which has long ago been shortened to *Tirhuti* and *Tirhut*. In the same way *Fejakabhuti* would have become *Jejahuti*, exactly as it is written by Abu Rihân. In the second inscription the name is given as *Fejakasukhti-desoyam*, which, by the common change of *s* to *h*, would have become *Fejâkahuti* and *Fejâhuti*, as before.

It is not impossible that the name of the province may be hidden in Ptolemy's *Sandrabatis* or *Sandabatis*, and that Khajurâha or Khajurpur may be hidden in his *Kuraporina*, one of the towns of the district of *Sandrabatis*. The other towns of Empelathra and Nadu-bandagar might then be identified with Mahoba and Narwar or Nalapura, and perhaps *Tamasi*, by a slight change to *Tapasi*, might represent the hill of Kâlanjar, the favourite resort of the *Tapaswis*, or ascetics. Kâlanjar is said by Wilson to be "enumerated in the Vedas amongst the *Tapasiasthânas*, or spots adapted to practices of austere devotion." The name of *Tapasi* was therefore peculiarly appropriate to Kâlanjar.

All the great temples now existing at Khajurâha and other Chandel places would appear to have been built during

the most flourishing period of the Chandel rule, that is, in the three centuries between the accession of Rāhila Varmma about A.D. 900, and the conquest of Kālanjar by the Muhammadans in A.D. 1203, just before the death of Paramārddi Deva.

In my first Report on Khajurāha (Vol. II, Archæological Survey) I gave a list of 24 temples which were still standing at Khajurāha, with a map showing their positions. During my late visit I sought for traces of other temples. I am afraid that most of the materials have been used up in the steps of the palace and tank built during the present century. The entrance to the Raja's garden is formed of the doorway of an old temple of large size, the clear opening being 7 feet 6 inches in height by 4 feet 8 inches in width. On the lintel there is a figure of the *Ardhandri*, or Androgyne Siva, standing in the middle, with a figure of Siva over one jamb, and of Vishnu over the other jamb. At a short distance there is an eight-bracket capital, 2 feet $4\frac{1}{2}$ inches in diameter, and close by there is a colossal statue of Siva. On comparing the size of this bracket capital with those of the largest standing temples, it would appear that some much larger temple must once have stood near the site of the garden. The following are the dimensions of these capitals:—

		ft.	ins.	
Loose bracket capital	.	2	4	diameter. ¹
Khandāriya capital	.	1	10	„
Ghantai capital	.	1	8	„
Chaturbhuj	.	1	5	„

The missing temple was probably an old one, as there are figures of the Ganges and Jumna with their symbols, the crocodile and the tortoise, on the jambs.

For the purpose of obtaining approximate dates for the existing temples I copied all the masons' marks and pilgrims' records on the walls and pillars. The former are presumably of the same dates as the temples themselves, while the latter must be later, although not necessarily much later.

¹ The fellow of this large capital is now lying in the court of the Jain temple.

I take the single names which are found on many of the stones to be those of the masons who prepared them. In a few instances this is absolutely certain, as the names are upside down. Inside the Lakshmanji temple I found three names thus inverted. In the Khandâriya temple I found the word *dâsân*, or "architrave," engraved on the underside of a beam. This also must have been a mason's mark.

In the accompanying plate I have given a few specimens of these short records from all the principal temples. With one or two exceptions they are much more roughly carved than the large formal inscriptions which record the building of the temples. One of the neatest is the name of Nemi Chandra on a pillar of the Ghantai temple. Its letters are quite equal to the best of the great inscription of Dhanga Deva, dated in Samvat 1011, or A.D. 954. The following account of these brief records will be sufficient to show that none of the standing temples are of older date than the great Jain temple of Ghantai.

B.—Ghantai Temple.

1. Nemi Chandra.

2. Swasti Sri Sâdhu Palna.

The second of these short records has already been published by Mr. V. A. Smith in the Journal of the Bengal Asiatic Society for 1879, p. 287 and Plate XIV; but it had not escaped my notice, as it was first brought to light by my clearance of the temple in January 1875. At the same time I found the other name of Nemi Chandra, which is not noticed by Messrs. Smith and Black. I made an excavation completely round the whole temple and cleared out the interior. My account of these operations will be found in Volume X of the Archæological Survey. But, as this volume was not published until 1880, Mr. Smith was not aware of my labours, which must have afterwards facilitated the measurements of his companion Mr. Black. A reference to my Report also will show that I had long before established the correctness of Mr. Fergusson's opinion that the Ghantai was a Jain temple, by the discovery of numerous Jain figures all round it, and of one at least *in situ* inside. As to the

date of the temple I am of opinion that the beautifully formed letters of the name of Nemi Chandra belong to the 10th century, and that the other inscription is not earlier than 1150 A.D., or perhaps even later.

C.—Colossal statue of Śāntināth.

This large statue is enshrined in a common-looking building made of old fragments and covered with whitewash, and very dark inside. I got a copy of its inscription at the time of my first visit in 1852. At my second visit in 1865 not a single letter of the inscription was visible, as the whole statue had been recently whitewashed. In the present year, 1884, however, I have managed to get a fair impression after a long time spent in cleaning the pedestal. The great figure is 14 feet high. I read the date as Samvat 1085, or A.D. 1028. In the accompanying Plate, XX, I have given the portions of this inscription which include the date and the name of the statue. I read the whole line as follows :—

Samvat 1085. Srimat Achārya putra Sri
Thākura Sri Deva dhara suta . Sri Sivi
Sri Chandraya Devah Sri Santināthasya
pratimā kâri.

Here we see that the name of the enshrined statue is *Śāntinātha*, and not *Seṭnāth*, as the people call it.

D.—Statue of Sambhunāth.

This is another single line inscription in small letters, which is engraved on the pedestal of a black stone statue of Shambhunāth, which is now lying in the courtyard of the Jain temples. I have given the opening of the inscription containing the date and the name of the reigning king in Plate XX. I read the whole as follows :—

Aum! Samvat 1215 Māgha Sudi 5 Srimān *Madana*
Varmma Deva pravarddhamāna vijaya rājye ||
Grahapati vāse Sreshthi *Dedu*, tat putra Pāhillah |
Pāhillā . . . pratimā kâri tīta||
tat putrāh Mahāgaṇā, Maha Chandrā, Sani chandra
Jina chandra Udaya chandra, prabhriti, Sam
bhavanātham prapamati nitya|| Mangala
mahâsri|| Râpakâra Râma Deva.||

"In the Samvat year 1215 [A.D. 1158] on the 5th day of the waxing moon of Māgha, during the prosperous and victorious reign of Srimān *Madana Varmma Deva*, the Sreshthi Dedu of the class of householders, together with his son Pāhilla . . . set up this statue. Then the sons, Mahaganā Mahachandrā, Sani chandrā, Udaya-chandrā, offered adoration to Sambhunātha. May it be fortunate ! Sculptor, Rāma Deva."

E.—Khandāriya Temple.

The short inscription marked E 1, which is carved on the under-side of one of the stone beams, is simply the word *dāsān*, or "architrave," and is, no doubt, a mason's mark contemporary with the building. The peculiar form of the attached vowels was common in the 10th century.

The inscription marked E 2, which is carved on one of the pillars, is of a later age, apparently about A.D. 1100. It seems to read as follows :—

Rājam mīda samaye nasu. sama chārma vastrinam.

F.—Chitr-gupt Temple.

These three short records appear to be simply mason's names. They are all in early Kutila characters of the 10th century. No. 1 reads *Gharamvasa* ; No. 2 *Subhavi* ; No. 3 *Nahinā*, or perhaps *Dahina*.

G.—Devi Jagadāmba Temple.

The two records from this temple are also in early Kutila character. No. 1 reads *Jina-Deva*, and No. 2 reads *Devi-Juna*.

H.—Viswanāth Temple.

The single names found on the stones of this temple are very numerous. I noted about 20, but some of them were repetitions. Thus No. 2 I found on four different stones. I read it *Sri Dewān dārgga*. No. 1 reads *Sri ganit*, and No. 3 *Sri Mihirata*. The names in this temple are peculiar in having the honorary prefix *Sri* attached to all of the early Kutila period of the 10th century.

I.—Kunwar Math.

There are two temples on the bank of the Kurar Nala, the large one being called simply *Kunwar Math*, or the

"Princes' Temple," and the smaller one being without name. The plinth, or basement, of the Kunwar Math, 6 feet in height, is of granite blocks, and the superstructure of sandstone. The Mandapa is covered by an overlapping dome, 18½ feet in diameter, without the usual four pillars to support the weight. The name of Vāsālā is found on several stones in both temples. On the wall of the smaller temple there is an inscription in two lines, which is apparently of later date than the temple itself. I read it as follows:—

Samvat 1174 Jyeshṭha badi 3 Ṣanau likhitam ||
Kayastha Jāktura Sri Gotha nityam pranamyati. ||

"In the Samvat year 1174 (A.D. 1117) on the 3rd of the waxing moon of Jyeshṭha, Saturday, this inscription was written. The Kāyastha, of Jāktura Sri Gotha, offered his adoration."

The date corresponds with Saturday, the 21st April 1117 A.D.

As the whole of this temple agrees very closely with that of the old temple at Rāhilya, I think that it may be referred to the same date, that is, to the beginning of the 10th century.

K.—Statue of Shanmukha.

This inscription was found near a ruined temple on the western bank of the Khajur Sāgar. The two lines are engraved on the pedestal of a statue of Shanmukha, or Kārtikeya. I read them as follows:—

Deva Sri Sasa Sinha—Bhaṭārka Sṛf Urddha.
Sivah Achārjasya ||Sarvvpital odharah attambha.
The characters belong to the Kutila alphabet.

18.—KHAJURĀHA INSCRIPTIONS.

The oldest inscriptions yet found at Khajurāha are a single specimen of the Buddhist creed, two short names on statues in the Chaunsat Jogini temple, and a record of three lines on the pedestal of a colossal statue of Hanumān, all of which appear to belong to the 9th century.

The Buddhist creed is very neatly engraved on the pedestal of a large seated statue. The characters are an early form

of Kutila similar to the oldest of the Magadha inscriptions of the Pāla Rajas of the 9th century.

The two Chaunsat Jogini names are given in Plate XX, No. 1. The first reads simply *Sri Maheswari*, and the other *Hinghulāja*, which are the names of the goddess Durgā, on whom the sixty-four Joginis attend.

A.—The inscription on the pedestal of the colossal statue of Hanumān is given in Plate XVI. It is the oldest *dated* record now existing in Khajurāha. The figures of the date are apparently those of the old notation in which each unit, and each ten, has a separate symbol, while the hundreds are formed by attaching a unit on the right side of the letter *s*, which represents *sat*, or one hundred. In the Hanumān inscription the letter *s* has a cypher attached to it, which is the same as that afterwards used for the day of the month, and which I have formerly read as 9, thus making 900. The other figure is similar to the old Gupta numeral for 40, thus making the date Samvat 940, or A.D. 883. But the characters may, perhaps, be one or even two hundred years earlier, making the date either Samvat 840 or 740, or A.D. 783 or 683.

There is a peculiarity about this inscription in the fact that it is divided into two distinct parts by a blank space, and further that the letters of the right half are smaller than those of the left half. I infer, therefore, either that there are two separate records, or that the right-hand half is a continuation of the left-hand half. I accordingly read the inscription as follows:—

- | | |
|----------------------------------|-------------------------------|
| 1. Aum ! Golla Gāhila putrasya, | 4. Gahilasya sutah Sri Mān |
| 2. Samvatsare 940, Māgha sudi 9, | Hanumān Pa- |
| 3. Sri Hanumāntam Gollākah | 5. vanātmaja Sri Lukusaddhar- |
| pranamati. | ma mā- |
| | 6. lokya Gollāko prakritam. |

As the date is uncertain, and no king's name is given, this old record loses much of its importance. I cannot attempt to translate it. But I understand that the statue was set up by Golla, the son of Gāhila, in the Samvat year 940 (?) on the 9th (?) day of the waxing moon of Māgha, when he paid his adoration to the Gollak Hanumān. The name of *Hanumān*

Pavandtmaja in the fourth and fifth lines seems to prove that the inscription consists of distinct parts, as I had supposed.

B.—*Plate XVI.*—The next oldest inscription at Khajurāha is unfortunately only a fragment of 13 imperfect lines. (See Plate XVI.) In the seventh line there is the name of *Sri Harsha Deva*, who was the father of Yaso Varmma, and the grandfather of Dhanga Deva. In the tenth line also there is another royal name, *Sri Kshiti Pāla Deva Nripati*. As his name does not occur in any of the genealogies, it seems probable that he may have been the eldest son of Harsha Deva, and that having died childless, he was succeeded by his younger brother Yaso Varmma; and accordingly his name was omitted in all the genealogical inscriptions. We know that Deva Varmma Deva, the eldest son of Vijaya Pāla, was treated in the same way. He actually succeeded his father, but as he was succeeded by his brother Kirtti Varmma, his name is omitted in all the genealogies.

This fragment was found to the north-east of the village, not far from the temple of Vāmana, to which it may have belonged.

C.—*Plate XVII.*—The oldest inscription at Khajurāha with a certain date is recorded on a very long slab now lying in the temple of Chaturbhūja. It consists of 28 lines of old Kutila characters, and gives the genealogy of the Chandel Rajas from Nannuka Deva down to Yaso Varmma and his son Dhanga Deva. The date is given in words as well as in figures; thus, *Samvatsare dasa-sata ekādasa*.—Samvat 1011, or A.D. 954.

D.—*Plate XVI.*—These four short lines are carved on the pedestal of a statue now lying loose in the temple of Lakshmi Nāth. The characters are early Kutila. That the temple was most probably dedicated to Vishnu we learn, not only from its name of Lakshmi Nāth, or the lord of Lakshmi, but also from the name of *Garuda* in the first line of this inscription. The statue is recorded to have been set up by the sculptor Vena, the son of Bali Atamantai.

E.—*Plate XVI.*—This record is carved on the wall of the temple of Vāmana. The letters are all of the simple Kutila

forms, but I am unable to make out any intelligible meaning from them.

F.—*Plate XVIII.*—The next inscription is that which was discovered by Burt in 1838. It is standing loose in the large temple of Viswanâth. It contains two dates. The earlier one, which I read as 1056, or A.D. 999, belongs to the main inscription which records the building of the temple by Raja Dhanga, his death at upwards of one hundred years of age, and the accession of his son Gaṇḍa Deva. If the date should be read as Samvat 1096, or A.D. 1039, the record would have been put up no less than 85 years after Dhanga's first inscription. This date would, besides, leave only eleven years, or from Samvat 1096 to 1107, between the reign of Gaṇḍa Deva and that of his great-grandson Deva Varmma Deva. As Râja Dhanga, according to other inscriptions, was certainly reigning in A.D. 954 and in 998, it seems almost certain that Gaṇḍa Deva must have succeeded him shortly after the latter date. I would therefore assign Gaṇḍa Deva to the period between A.D. 999 and 1025. We know that he was reigning in A.D. 1020, when he attacked the Raja of Kanauj, and also in the following year 1021, when he was himself attacked by Mahmud of Ghazni.

This inscription was published in the Journal of the Asiatic Society of Bengal for 1839, page 159; but the whole requires careful revision, as it abounds with mistakes, more especially in the names of the Chandel kings.

G.—*Plate XIX.*—The next inscription is on a large slab now standing loose in the entrance-hall of the temple of Viswanâth. It is dated in Samvat 1058, or A.D. 1001, and, so far as I can make it out, it does not mention the name of a single Chandel king, but refers to one Kokkala, who was perhaps a private person. There was, however, a Kalachuri prince of this name, Kokkala II, who, as the father of Gāṅgeya Deva, the contemporary of Abu Rihân, must certainly have been reigning at this very time. I cannot find any royal name in the inscription.

H. This inscription has already been noted in my account of the smaller records given in Plate XVI, fig. C.

J.—*Plate XVI.*—This inscription is carved on the left door jamb of the Jain temple of Jina Nāth. It is dated, but the mason who cut the figures made a mistake in the hundreds, so that the date may be read either as Samvat 1011, or as Samvat 1111, the second figure being compounded of 0 and 1. I formerly read it as 1011, but I have been induced to give up this date for 1111 for the following reason. In Samvat 1011 the week-day of *Vaisākh Sudi 7* was a Friday, and not a Monday. The true date is Samvat 1111, or A.D. 1054, in which year *Vaisākh Sudi 7* did fall on Monday, the 18th April. In the third line there is the name of Raja Dhanga, in whose reign the temple was most probably built. In the fourth line there is the name of the Jaina pontiff Jinanāth, or Jitanāth, to whom the temple was dedicated. Then comes the following list of gifts made to the garden by a member of the Pāhila-vansa during the time of Vāsava Chandra, the Mahārāja Guru or high priest. The following are the names of the gifts :—

1. Pāhila-vātika, or the Pāhila garden.
2. Chandra-vātika, or the Chandra garden.
3. Laghu-Chandra-vātika, or the Little Chandra garden.
4. Sankara-vātika, or the Sankara garden.
5. Pancha Itala-vātika ?
6. Amra-vātika, or the Mango garden.
7. Dhanga-vāri, or the Dhanga garden-house.

L—Is a small inscription of six lines carved on a pillar of one of the smaller corner shrines of the Lakhshmināth temple. The letters are much injured ; and, as no king is mentioned, the record is only valuable as showing that this corner chapel was most probably built in the year noted, or “ Samvat 1161, Māgha badi dwija, 2,” or A.D. 1104. But the great temple of Lakshmināth must be at least a century older, as I found the name of *Sāhilch* in early Kutila letters on one of the square pillars of the Mahā Mandapa, or central hall.

The inscription marked L I read as follows :—

Swa (sti) Sri Bhaṭāraka
 Guṇa Devachāryya Pra-
 bhākara . . . ja.
 Kāritam-Samvat
 1161, Māgha badi
 dwija 2.

From this the builder of the chapel would appear to have been the chief priest, Prabhākara.

M.—*Plate XVIII*.—Last two lines of the great inscription of Ganda Deva. The translation given by Sutherland requires to be amended in the name of the characters used in the inscription. Sutherland reads *Kakuddākārāni*, whereas the inscription has *Kumuddākārāni*, that is, “lotus-like, or beautiful characters.” With this correction the paragraph runs as follows:—

“The king Jaya Varmma Deva (like an elephant supporting the universe) re-wrote in clear letters the above verses, which had before been written in irregular letters (*Kirna*). These letters, in the *Kumudā* form, that Gauda Kayastha, aided by the learned, inscribed by the hand of Jaya Pāla, that Kayastha, of untarnished lustre, the radiant moon of the king’s race, who, the dispeller of gloom, had risen from the ocean of polished literature. Samvat 1173, Vaisākh Sudi 3, Friday.”

The week-day here given does not agree with the calculated day. The name certainly appears to be *Śukre*, or Friday; but as the second letter may be read as *je*, it is possible that the original name was *Kuje* or Tuesday, and that the first letter was incorrectly engraved by the sculptor as *Su*. As the Hindu year Samvat 1173 began on Friday, 17th March 1116 A.D. the 3rd day of Vaisākh sudi would have been the 18th April which was a *Tuesday* (*Kuje*) as proposed, and not Friday (*Śukre*) as appears to be recorded in the inscription.

N.—(See J.) *Plate XVI*.—I have already noticed this inscription in my account of the short temple records in Plate XVI.

O. P. Q. R. S.—These are short inscriptions on the court of the Jain temples.

O is dated in Samvat 1205, or A.D. 1148.

P is dated in Samvat 1212, or A.D. 1155. It is carved on the base of a statue of Viranātha, and bears the name of the sculptor, Kumāra Sinha.

Q is dated in Samvat 1215, or A.D. 1158, during the reign of Madana Varmma. A copy of the date is given in Plate XVI, figure D.

R is dated in Samvat 1220, or A.D. 1163. It is engraved on the base of a statue of Ajitanāth.

S is dated in Samvat 1234, or A.D. 1177. It is engraved on a Jaina pedestal, and is the latest dated inscription found at Khajurāha.

19.—MANIYĀ GARH.

The large ruined fort of Maniyāgarh is situated on the left bank of the Kiyān or Ken River, rising immediately above the town of Rājgarh, on the high road between Chhatrapur and Panna. The hill is from 600 to 800 feet in height above the plain below. The fort derives its name from a small shrine of Manyā Deva.

On the north face of the hill, about 200 feet below the crest, there is a terrace with a lingam of Mahādeo, on which a small jet of water continuously falls from above. This is an object of worship, and an annual fair is held under the hill at Rājgarh on the Siva-rātri.

Mr. V. Smith quotes the bard Chand for a story of the Chandel Raja Kirat Singh having "hunted at Mainyāgarh with Singh, the Gond chieftain of Garha Mandala; and that afterwards, when war broke out, Kirat Singh was taken prisoner by the Gonds—an injury which was revenged by Alha in the reign of Parmāl."

This looks very like an interpolation of late date, as Kirat Singh was the contemporary of Sher Shah, while *Garha* certainly belonged to the powerful Kalachuri king Karna Deva, during the reign of Kirti Varmma Chandel. We know also that Garha still belonged to the Kalachuri princes so late as Chedi Samvat 932, or A.D. 1181, and there seems good reason for believing that the kingdom of Dāhal, of which the capital was Tripura or Tewar, was still in the possession of the Kalachuris for a century later, or until the advent of the Bāghels into Rewa.

There is a shrine of Maniyā Deva at Mahoba. The name is not Hindu, and the worship of Maniya Deva and Maniya Devi is believed to have been a cult of the aboriginal Bhars of Bundelkhand.

20.—MAHOBHA INSCRIPTIONS.

As I have already given a detailed description of Mahoba and its antiquities, I will now confine my remarks to a few notes which were omitted in my previous account.

The Chandela kingdom is universally said to have been founded by Chandra Varmma, the son of Chandrama, or the moon, and the princess Hemâvati, the daughter of the Gahirwâr Râja of Benares or of his purohit Hem Râj. The god informed the princess that her son would be born on the bank of the Karnâvati, or Kiyân River, the present Ken, and directed her to take him to Khajurâha, to offer him as a gift, and to perform the sacrifice of a *Bânda jâg*, to take away the reproach of her having become a mother without marriage.

Chandra Varmma is said to have been born on the 11th day of the waxing moon of Vaisâkh in Samvat 225.¹ When he grew up he built 85 temples,² and founded the fort of Kâlanjara. He then went to Mahoba, the place of Chandrama's "great festival" Mahotsava, and made it his capital.

According to the legend, Chandrama had promised Hemâvati that her posterity should continue to reign so long as they observed the four following conditions:—

1. Not to drink wine.
2. Not to put Brahmans to death.
3. Not to make improper connections.
4. To preserve the name of Varmma.

The unfortunate Raja Paramârddi Deva, who was first conquered by Prithi Râj Chauhân, and afterwards by the Muhammadans, is said to have broken all four of these conditions—

1. He drank wine.
2. He put Brahmans to death.
3. He cohabited with his own sister.
4. He did not bear the name of Varmma.

This account is firmly believed by all the people even at the present day, and the legend is probably as old as the time

¹ Other dates are given by different manuscripts, as Samvat 204, 661, and 662. See Archæological Survey, Vol. II, p. 446.

² These 85 temples are twice mentioned by the bard Chand, Vol. III, p. 85—"Asipânch prâsâd banal," and Vol. III, p. 52—"Pachâsi Math."

of Paramârddi himself, as all his successors bore the name of Varmma. In the bardic accounts his eldest son is named Bramâdit, which I believe to be only a spoken form of *Varmmâ-ditya*, or the "lord of the Varmmas," or Chandels.

Another legend which has also been handed down to the present day tells how Paramârddis' general the Banâphar hero Alha, when he quitted Mahoba, forbade any one from beating a *nakâra* (kettle-drum) in the city for the future. This injunction is still in force after a lapse of seven centuries! The general belief is that the ghosts of the old Chandel Rajas still haunt their old capital, and would resent the beating of a kettle-drum within their hearing. Should any one do so, the horse of the drum-beater would stumble and the rider be killed, while the chief who ordered the drum to be beaten would shortly meet with a violent death. I was myself a witness to the continuance of this old belief. In February 1843, when I was residing at Mahoba, Bâkal Singh, the brother of the Chhatrapur Raja, was obliged to go to Naogaon to celebrate his daughter's marriage, as he did not dare to have a wedding procession with music through the city which the ghosts of the old Chandel Rajas were believed to haunt.

Mahoba was captured by Prithi Raja Chauhân in Samvat 1239, or A.D. 1182, as recorded in his inscription at Madanpur in the Lalitpur district. But it could not have been annexed to the Delhi kingdom, as I found an inscription built into the wall of the Mahoba fort with the name of Paramârddi Deva and the date of Samvat 1240, or A.D. 1183. There are, however, no inscriptions of the Chandel kings of a later date than Samvat 1240, either in Mahoba itself, or in any of the old places in the Mahoba district. At the close of Paramârddis' reign the city was permanently annexed to the Muhammâdan kingdom of Delhi.

The earliest inscription that has yet been found at Mahoba was discovered by myself in 1865, let into the wall of the Dargâh of Pir Muhammad Shah. It was thickly covered with whitewash. I was permitted to take the stone out of the wall on condition that I restored it to its original position after taking an impression of it. I of course replaced it; but

a few years later it was taken to Fatehpur in the Doab by the Magistrate, and eventually found its way to the Allahabad Museum, where I saw it in 1872, and I was thus enabled to get fresh impressions. It is broken both on the right hand and at the bottom, and the date is lost. It is written on a slab of black basalt in the square characters called *Chitra-varna*, or "ornamented letters." It consists of 17 imperfect lines, but the characters are generally in good condition. It gives the genealogy of the Chandel Rajas from Dhanga to Kirtti Varmma. But just before the name of the later King I find the name of the Kalachuri Raja Gānggeya Deva, who was reigning over Tripura, or Chedi, in A.D. 1031, when Mahmud of Ghazni besieged Kālanjar. In the 13th line Kanyākubja is mentioned. But the most interesting part of the record is the mention of the name of the country as *Fejā-bhukti* (line 6). In a short inscription from Madanpur, which I have already published, the name is given as *Fejākasukti*. Both of these forms would naturally be shortened to *Fejā-luti*, just as *Tira-bhukti* has become Tirhuti and Tirhut.

That this was the actual name of the country we learn from two independent authorities of still older date. The first is the Chinese pilgrim Hwen Thsang, who visited *Chichi-to* in A.D. The second is Abu Rihān, the contemporary of Mahmud of Ghazni. He calls it Jajahuti, which is the form still preserved in the names of the Jajhaotya Brahmans and Jajhaotiya Baniyas. Its application to both of these classes shows that it was a geographical designation.

The second large inscription from Mahoba I found in 1843 in the fort wall placed upside down as a common building stone. It is broken at top and at both ends, but the bottom line is in good order, and contains the date of *Samvat 1240, Ashādhā badi 9 Some* (A.D. 1183). It refers to the building of a temple (*prāsāda*). The sculptor was Deva Raja, the son of Soma Raja. I cannot find any king's name, but the reigning Raja in Samvat 1240 was Paramārddi Deva.

A third broken inscription in the same square characters consists of the remains of 16 lines. It seems to be nearly perfect on the left hand and at bottom; but both the top and

the right-hand portion are gone. The only part of the date now remaining is in the last line, where I read *Tāksha Samvatsara*, which can only be *Raktāksha*, which was the 58th year of the 60-year cycle of Jupiter. This may be either A.D. 1141 or 1200. The stone-cutter was Deva Raja, the son of Soma Raja; but I do not see any trace of a Raja's name. As Mahoba was lost to the Chandel princes after 1200 A.D., the most probable date of the inscription is A.D. 1200, as will be seen from the next inscription, which was engraved by the same stone-cutter, named Deva Raja, the son of Soma Raja, in 1183 A.D. It certainly refers to the building of a temple, as I find that the word *prāsāda* occurs twice (see lines 10 and 15).

I found also several short inscriptions on the pedestals of broken Jaina statues. Some of these are valuable, as they give both the date and the name of the reigning king at the time when the statue was set up. Some omit the king's name, but record the date, whilst others omit both.

The earliest of these short records that I have noted at Mahoba contains only a few words—

Samvat 1169, Phālguna Sudi 8 (A.D. 1112).

It most probably belongs to the time of Jaya Varmma Deva, who, we know, was reigning only four years later, in Samvat 1173.

A second fragment, dated in Samvat 1203, gives the name of the sculptor Lākhana.

A third inscription on the pedestal of a figure with a shell symbol (*Nemināth*) consists of two lines, of which the lower one reads as follows :—

Sri Mān Madana Varmma Deva rājye,
Sam 1211, Ashādha Sudi 3, Sanau (*shell*),
Deva Sri Neminātha—Rupākāra Lākhana.

A fourth inscription with a goose symbol (*Sumatināth*) consists of one long line only. It opens with the date—

“ Samvat 1213, Māgha Sudi 5 Guran.”

No king is mentioned, and it ends with the name of the sculptor Rūkara (for Rupākāra) Lākhana.

A fifth inscription with the elephant symbol (*Ajitanāth*) consists of two lines, giving the date and the name of the worshipper—

“Samvat 1220, Jyeshtha sudi 8 Ravau : Sadhu Deva Ga natasya putra Ratna Pāla pranamati nityam ||”

A sixth inscription gives the name of the same worshipper together with those of his wife and his four sons—

1. Sāṅgamya samā tat putra sādhu Sri Ratna Pāla |
tasya Bhārya Sādhā | putra Kirtti Pāla |
2. tatha Ajaya Pāla | tatha Vasta Pāla | tatha Tribhuvana Pāla |
pranamati nityam |
3. jita nāthayah ||

A seventh incomplete inscription belonging to the reign of Paramārddi Deva, consists of one long line—

Samvat 1224 Ashādha sudi 2 Ravan || (Kāla njarādhipoti Sri Mat Parāmārddi Devapād—nām pravardhamān a Kalyāna nijaya rajye.

21.—DAHI COPPER-PLATE.

About 1848 a copper-plate was obtained by Colonel Ellis from Dāhi, $4\frac{1}{2}$ miles to the east of Bijāwar in Bundelkhand. I have not seen the plate itself, but Colonel Ellis kindly furnished me with the following account of it, in which two out of the four Rajas' names have certainly been misread. The first, which his Pandit reads as *Sri Kando Barm Deo*, must be *Sri Madana Varmma Deva*, as he was the father of Trailokya Deva, and the last, whose name was read *Sri Sandin Barm Deo*, must be *Srimat Vira Varmma*, as he was the son of the third king Bhoja Varmma, and was actually reigning in the very year in which the copper-plate grant was made.

The “abstract translation” which I received from Colonel Ellis is as follows :—

“Substance of a grant of land dated *Rab-din Bysākh Sudi puno, Sambat 1337* (Sunday, A.D. 1280), written by Sri Harnām Pandit, inscribed on copper, from Dāhi, a village 3 kos east of Bijāwar in Bundelkhand.

“Kando Barm Deo, a descendant of the line of Atri, was a great prince, mighty, like a second Chandrama. His son, Parmārd Deo, had issue Trilok Barm Deo, whose son, Sandin Barm Deo, was Raja of Kālanjar. He was just, well versed in the Veds, and protected his people with the most tender anxiety.

"He assembled the Brahmans, Kayeths, Harkâras, cow-herds, goat-herds, orchard-keepers, and all other classes, high and low, and said, 'I have this day granted the lands and waters of the village Dahi, with its live and dead stock, rights and privileges, and everything belonging to it, past, future, and present, to the great grandson of Magana Brâhman, the grandson of Sava, the son of Chaonde, by name Balbhadra Mallaya, an illustrious chief of distinguished bravery, who has conquered the Rajas of Nalpur, Gopal-Madhuban, Hatta, Hâr-raj, Gopagiri, Sardhi, the Turks, and rulers from Kashmir. After bathing in water brought from sacred places of pilgrimage and performing worship to Bhagwân, Mahadeo, Suraj, and Bhovâni, holding the kus and Ganges water in hand, I make this grant for the benefit (s) to be accrued (? to accrue) to my mother's, my father's, and my own manes. My servants henceforward must have nothing to do with the village. The jangals, forests, graves, ponds, rivers, mines, hidden treasures, together with all privileges and rights of seignorage over the matmakers, banyas, siklegars, and other inhabitants within its boundaries, are included in the grant. Enjoy the gift without fear of molestation.' This is followed by the usual imprecations against the resumers of land and the advisers of resumption, &c."

Some time afterwards, in 1848, I saw an impression of the copper-plate inscription, from which I made a transliteration in Roman characters. The plate contained 30 lines of about 30 letters in each line. I then read the two doubtful names as Sri Yâdava Varmma Deva and Sri Sandhîra Varmma Deva. The change from Sandin of the Pandit's reading to Sandhîra shows that the last name was Vîra, as I have now suggested.

I cannot follow in my transcript all the names read by the Pandit. According to my reading the gift was made to one Mallâya of the Kâsyapa gotra, the great-grandson of Bhaṭṭa Mahattama Sinha, the grandson of Sîvâhada, and the son of Sri Chanda. This hero is said to have conquered the lord of Narwar ("Samarayugâparâjîtâ Nalapurapati") and the ruler of Mathura (*Gopâla Madhuvankâdhipa*), and Hariraja of Gwâlior (*Gopagiri*).

I copied the date as *Samvat 1337, Samayâ Vaisâkha Sudi 15 Ravi-dine*, which agrees with the Pandit's reading of "*Rab-din Bysâkh Sudi puno Samvat 1337*." But the 15th of Vaisâkh Sudi in Samvat 1337, or A.D. 1280, was *Tuesday* the 16th of April, and not Sunday.

In A.D. 1280 the fort of Gwālior was in the possession of Balban, the Muhammadan king of Delhi.

I purpose to make enquiries for this copper-plate during the ensuing winter on my tour through Bundelkhand.

22.—GOBARI.

Gobari is a small village in the petty state of Mahiyar, 9 miles to the north-east of that town and 7 miles to the east-south-east of Uchahara. It possesses an inscribed slab, 27 inches high by 13 inches broad, with an inscription in large letters, containing a date and a king's name. I read portions of it as follows :—

1. Aum ! Swasti ! Samvat 1407,
2. Samaye Jyestha Su-
3. di panchami Bhaume Go-
4. bari grāme Mahārā-
5. jādhirājā Sri Vīra
6. Rāja Deva rājye pratha-
7. ma pañcha 11 māna
8. Pañ : Devadhara gra.
9. me.

(The remainder is too much broken to be read.)

On the left side there is a single line, as follows :—

likhitam Sutradhāra Gopāla (?).

The date corresponds with Wednesday, 12th May A.D. 1350. The Raja may possibly be the same as the Chandel king Vira Varmma II; but I think it much more probable that he may be the Baghel Raja Bhairava, who was reigning from A.D. 1335 to 1355.

23.—RAYPUR.

Raypur is a large village in the petty state of Kothi, about 20 miles to the north of the Satna railway station, and about 30 miles to the south-east of Kālanjar. Here Colonel Ellis found a large black slab, with a long inscription, dated in Samvat 1408 and Sāke 1273, on Wednesday, the 11th Vaisākh Sudi, during the reign of Sri Vira Deva Nripate. The date

corresponds with Wednesday, 6th July 1351 A.D. It is within one year of that of the Gobari inscription last mentioned, and bears the name of the same Raja Vira Deva. From the proximity of Raypur to Kālanjar one would expect to find the name of one of the Chandel princes in this record. But there is a barren and difficult range of hills between Kālanjar and Raypur, whereas to the eastward the country is quite open to the valley of the Tons River, which flows through the heart of Rewa, or Baghelkhand. The existence also of another inscription of the same date, and bearing the same king's name at Gobari, which is within the Rewa territory, is very strongly in favour of both inscriptions to one of the Baghel Rajas. There is, however, no Vira in the Baghel list, while there are two Rajas of that name amongst the Chandel kings. There are two inscriptions of Vira II Chandel in Ajaygarh Fort, both dated in Samvat 1372. or A.D. 1315. It is therefore quite possible that he may have been reigning in A.D. 1350-51. I have, accordingly, placed both the Gobari and Raypur inscriptions in the Chandel list for the present. I may note also that the Ajaygarh prince is called simply Vira Nripa, and not Vira Varmma. But if the Chandel dominions still extended to Gobari so late as A.D. 1350, the Bāghel rule must have been confined to the country to the south of the Son River with its capital at Bāndhogarh.

24.—THE CHANDELA KINGDOM.

In two previous Reports I have given an account of the Chandela dynasty from all the materials then available. But later discoveries, including the inscriptions found during my late visit to Kālanjar and Ajaygarh, the two great strongholds of the kingdom, now enable me to offer a much fuller and more complete abstract of their history. I feel conscious also that the wider reading and the more matured judgment which I now possess will justify me in making public all the information that I have now acquired.

The country held by the Chandel princes may be described as lying between the Dhasân River on the west and the Vindhya Mountains on the east, and extending from the Jumna

on the north to the sources of the Kiyân, or Ken River, on the south. The Kiyân River runs through the country from south to north, dividing it into two nearly equal portions, with the capital cities of Mahoba and Khajurâha in the western half and the great forts of Kâlanjar and Ajaygarh in the eastern half. Within these limits it had an average length of about 120 miles with a breadth of 100 miles, and an area of more than 12,000 square miles. It, therefore, comprised about one-half of the two British districts of Hamirpur and Banda, with the whole of the Native States of Chirkhâri, Chhatarpur, and Bijâwar to the west, and Jaitpur, Ajaygarh, and Panna on the east. In their most palmy days the Chandels pushed their conquests to the Betwa River on the west, which added to their dominions about 5,000 square miles more.¹

The revenue of the first tract of 12,000 square miles is now just 50 lakhs of rupees, while that of the second tract is about 20 lakhs, the whole being about 70 lakhs. During the rule of the Chandels the revenue must certainly have been less or, say, not more than 40 or 50 lakhs, or about half a million pounds sterling. But this was only during the most prosperous period of the Chandel rule, when their dominions attained their greatest extension.

It was at this time that Raja Ganda Chandel invaded Kanauj to punish the Rahtor king for submitting to Mahmud of Ghazni. When Mahmud afterwards invaded his territory the Chandel king is said to have brought into the field no less than 36,000 cavalry and 45,000 infantry, supported by 640 elephants. The numbers are, no doubt, much exaggerated; but even if we reduced them by more than one-half, there will still remain a force of 40,000 men, with 300 elephants, which is just two-thirds of the strength of the Sikh army, as it was left by Ranjit Singh, and greater than that of the Gwalior army which opposed Lord Ellenborough.

According to the universal tradition of the country, which is supported by all the chroniclers, the Chandels derive their

¹ Chanderi is generally supposed to have belonged to the Chandels from the belief that it derived its name from them. But the true derivation of the name appears to have been from Chandragiri.

origin from Hemâvati, daughter of Hemrâj, the Brahman Purohit, or family-priest, of Indrajit, the Gahirwâr Raja of Benares¹—

“ Hemâvati was very beautiful, and one day when she went to bathe in the Râti Tâlâb, she was seen and embraced by *Chandramâ*, the god of the moon, as he was preparing to return to the skies. Hemâvati cursed him. ‘ Why do you curse me ? ’ said *Chandramâ*. ‘ Your son will be lord of the earth, and from him will spring a thousand branches.’ Hemâvati enquired—‘ How shall my dishonor be effaced when I am without a husband ? ’ ‘ Fear not,’ replied *Chandramâ*. ‘ Your son will be born on the bank of the Karnâvati River ; then take him to Khajurâya, and offer him as a gift and perform a sacrifice. In Mahoba he will reign, and will become a great king. He will possess the philosopher’s stone, and will turn iron into gold. On the hill of Kâlanjar he will build a fort. When your son is 16 years of age you must perform a Bhânda Jag to wipe away your disgrace, and then leave Benares to live at Kâlanjar.’ ”

According to this prophecy, Hemâvati’s child, like another *Chandramâ*, was born on Monday, the 11th of the waxing moon of Vaisâkh, on the bank of the Karnâvati, the modern Kiyân, or Kane, River of the maps, and the Kainas of the Greeks. Then *Chandramâ*, attended by all the gods, performed a “ great festival ” (Mahotsava), when Vrihaspati wrote his horoscope, and the child was named Chandra Varmma. At 16 years of age he killed a tiger, when *Chandramâ* appeared again to him and presented him with the philosopher’s stone, and taught him polity (*râjnit*). Then he built the Fort of Kâlanjar, after which he went to *Kharjûrpur*, where he performed a sacrifice (*jag* or *yajnya*) to do away with his mother’s shame, and built 85 temples. Then *Chandravati* Râni and all the other queens sat at the feet of Hemâvati, and her disgrace was wiped away. Lastly, he went to Mahotsava, or Mahoba, the place of *Chandramâ*’s “ great festival,” which he made his capital.

But this popular tradition receives no support from the inscriptions. In the copper-plate record of Raja Dhanga Deva, the founder is said to be “ of the great family of Sri Brahmendra Muni.” In the stone inscription of Raja Ganda

¹ Archæological Survey Reports, Vol. II, pages 445 and 446.

Deva the kings are said to be of the Chandrâtreyâ line, which agrees with the other statement, as Atri and Chandra were the son and grandson of Brahmâ or Brahmendra. But there is no allusion whatever to Hemâvati, the Brahman maiden, whose story is probably a pure fiction, invented to cover the equivocal origin of the ancestors of the Chandels.

In the two long inscriptions at Khajurâha the earliest name mentioned is that of Nannuka. In Dhanga Deva's copper-plate the earliest name is that of his own grandfather, Harsha Deva, while in that of Deva Varmma Deva the earliest name is that of Vidyâdhara Deva, the grandson of Dhanga. The following is the genealogy as derived from all sources:—

Chandela Rajas.

No.	Date.		Names.	
	Vik. S.	A.D.		
1	857	800	Nannuka Deva
2	882	825	Vâkpati
3	...	850	Vijaya
4	...	875	Râhila
5	...	900	Harsha Deva
6	982	925	Yaso Varmma Deva
7	1010	953	Dhanga Deva	Inscription, S. 1011 and 1055.
8	1056	999	Ganda Deva	Inscription, S. 1056.
9	1082	1025	Vidyâdhara Deva
10	1097	1040	Vijaya Pâla Deva
11	1107	1050	Deva Varmma Deva	Copper-plate, S. 1107.
12	1120	1063	Kirtti Varmma Deva	Deogarh Rock, S. 11.
13	1155	1097	Hallakshana Varmma Deva
14	1 67	1100	Jaya Varmma Deva	Inscription, S. 1173.
15	1177	1120	Hallakshana Varmma Deva
16	1179	1122	Prithvi Varmma Deva
17	1186	1129	Madana Varmma Deva	Inscription, S. 1186 to 1220.
18	1222	1165	Paramârddi Deva	Inscription, S. 1224. Killed A.D. 1203.
19	1259	1203	Trailokya Varmma Deva	Inscription, S. 1269-1297.
20	1297	1240	Vira Varmma I.	Do. S. 1312 to 1337.
21	1309	1282?	Bhoja Varmma	Do. S. 1345.
22	1357	1300	Vira Varmma II.	Do. S. 1372.
23	1387	1330	Sasângka (bhupa)
24	1403	1360	Bhilama Deva
25	1447	1390	Paramârddi
26	...	1420
27	...	1445
28	...	1470
29	...	1495
30	1577	1520	Kirat Singh
...	1602	1545
...	1627	1570

I now give a list of all the Chandel inscriptions at present known, as they form the authorities on which the above genealogy has been compiled—

Chandel Inscriptions.

No.	Place.	Letter.	DATE.		King.		Lines.
			Vik.S.	A. D.			
1	Kālanjar . .	P	...	400	? . . .	Gupta character . .	3
2	Do. . .	Q	...	400	? . . .	Ditto	1
3	Do. . .	L	...	600	? . . .	At the Ganes Gate . .	16
4	Do. . .	K	...	800	? . . .	Cell near Nilkanth . .	4
5	Khajurāha	800	? . . .	Buddhist creed
6	Do. . .	A	940	883	? . . .	Colossal statue of Hanumān	3
7	Do. . .	B	...	900	Harsha Deva .	Broken slab	13
8	Do. . .	C	1011	954	Dhanga Deva .	Loose slab in temple .	28
9	Do. . .	D
10	Do. . .	E
11	Nanyaura	1055	998	Dhanga Deva .	Copper-plate, Bengal Asiatic Society's Journal, 1878	14
12	Khajurāh .	F	1056	999	Ganda Deva .	Loose slab in temple .	32
13	Do. . .	G	1058	1001	...	Sri Kokala—loose slab .	22
14	Do. . .	H	1085	1028	...	Colossal figure of Śāntināth	1
15	Nanyaura	1107	1050	Deva Varmma Deva	Copper-plate, Bengal Asiatic Society's Journal, 1878	19
16	Khajurāha .	J	1111	1054	...	Left-door jamb, Jain Temple	11
17	Do. . .	K	1142	1085	...	Bull-symbol statue of Adināth
18	Deogarh	1154	1097	Kirtti Varmma .	On rock	8
19	Khajurāha .	L	1161	1104	...	Corner temple of Lakshmināth
20	Mahoba . .	A	Kirtti Varmma .	Idgāh wall—incomplete .	17
21	Ajaygarh . .	P	Ditto . .	Rock outside gate . .	4
22	Mahoba . .	B	1169	1112	...	Fragment	1
23	Khajurāha .	M	1173	1116	Jaya Varmma .	Under Ganda's inscription No. 12	2
24	Do. . .	N	1174	1117	...	Kunwar Math, on Kurar Nala	2
25	Kālanjar . .	A	1186	1129	Madana Varmma	8

Chandel Inscriptions—contd.

No.	Place.	Letter.	DATE.		King.		Lines.
			Vik. S.	A.D.			
26	Kálanjar . .	B	1187	1130	4
27	Do. . .	C	1188	1131	9
28	Augási	1188	1131	Madana Varmma	Copper-plate, Bengal Asiatic Society's Journal, 1878	19
29	Kálanjar . .	D	1192	1135	...	Thakur Narsingh, statue of Narsingh . . .	8
30	Do. . .	E	1194	1137	.	Cave near Nilkanth .	7
31	Do. . .	F	1195	1138	.	Rock to north of Nilkanth	21
32	Mahoba . .	C	1203	1146
33	Khajuráha .	O	1205	1148
34	Bárigarh	1207	1150	.	Pedestal of naked standing figure
35	Ajaygarh . .	A	1208	1151	18
36	Mahoba . .	D	1211	1154	..	Statue of Nemináth . .	2
37	Khajuráha .	P	1212	1155	...	Viranáth-Sculptor Kumār Singh
38	Mahoba . .	E	1213	1156	Madana Varmma	Figure of Sumatináth
39	Khajuráha .	Q	1215	1158	Ditto . .	Figure of Sambhunáth .	..
40	Do. . .	R	1220	1163		Statue of Ajitanáth
41	Mahoba . .	F	1222	1165
42	Kálanjar . .	G	1222	1165	...	Pavement of Nilkanth Temple . . .	2
43	Mhau	Madana Varmma	Asiatic Researches, Vol. XII
44	Mahoba . .	G	1224	1167	Paramáreddi Deva	On pedestal with figures .	1
45	Khajuráha .	S	1234	1177	..	Jain figure
46	Ajaygarh . .	B	1237	1180		..	.
47	Madanpur	1239	1182	Paramáreddi Deva	Small temple
48	Mahoba . .	H	1240	1183	Ditto . .	Wall of fort
49	Do. . .	J	Nearly square fragment
50	Ajaygarh . .	C	1243	1186	8
51	Kálanjar . .	H	1258	1201	Paramáreddi Deva	Bengal Asiatic Society's Journal, Vol. XVII, p. 316	32
52	Bagrári	Ditto . .	In 2 pieces, bank of lake .	24
53	Ajaygarh . .	D	1269	1212	Trailokya Varmma	...	6
54	Do. . .	E	1312	1255	Vira Varmma	55

Chandel Inscriptions—contd.

No.	Place.	Letter.	DATE.		King.		Lines.
			Vik.S.	A.D.			
55	Kālanjar . . .	J	Vira Varmma .	Yellow slab-circa, A.D. 1250	31
56	Ajaygarh . . .	F	1325	1268
57	Do.	G	1337	1280	Vira Varmma	21
58	Dāhi	1337	1280	Ditto . . .	Copper-plate, Colonel Ellis	30
59	Ajaygarh . . .	H	1345	1288	Bhoja Varmma .	Bengal Asiatic Society's Journal, 1837, page 885
60	Do.	I	Without date, long lines .	2
61	Do.	J	Bhoja Varmma .	Large letters, long inscription	15
62	Do.	K	1346	1289	Ditto	11
63	Do.	L	1349	1292	.	Over a female figure .	3
64	Do.	M	1311	1314	...	Upper round step of temple	2
65	Do.	N	1372	1315	...	Almost illegible from white-wash	12
66	Do.	O	1372	1315	Vira Nripa .	Pillar of gateway . . .	15
67	Kālanjar	1372	1315
68	Gobari	1407	1350	Vira Raja Deva
69	Raypur	1408	1351	Ditto . . .	and Sasāngka Bhūpa .	..
70	Bachon	1433	1376	Bhilama Deva
71	Rāsin	1466	1409	Paramārdi
72	Kālanjar		Outside the Lal Darwāza .	16

Of the first three kings in the list, nothing whatever is related save the fact of their reigns.

To No. 4 *Rāhila*, the chronicles assign the erection of a very fine temple, now in ruins, at the village of Rāhilya, 2 miles to the south-west of Mahoba. As he was the great-grandfather of Dhanga Deva, his reign cannot be placed later than 75 years (or three generations) prior to the accession of Dhanga, or from 875 to 900 A.D.

Of No. 5, *Harsha Deva*, we learn that his wife was named Kaneshuka, and that their son was .

No. 6, *Yaso Varmma Deva*, whose wife was Narmma Deva.—A great part of the earliest and longest of the Khajurāha

inscriptions, dated in Samvat 1011, or A.D. 954, is taken up with an account of his reign. His son, Dhanga, is mentioned in line 25, and the date is given, both in words and in figures, in the 28th or last line.

No. 7.—Dhanga Deva is celebrated as the builder of a temple of Siva, in which was enshrined an emerald lingam, and also a stone image of the god. He is recorded to have lived more than 100 years (*jīvitwa saraddm satam samadhikam*), when he drowned himself at the junction of the Ganges and Jumna Rivers. His copper-plate is dated in Samvat 1055, or A.D. 998; and as the great stone inscription at Khajurāha, which records his death, is dated in the following year, his son's accession may be placed in Samvat 1056, or A.D. 999.

No. 8.—Ganda Deva, the son of Dhanga, was the conqueror of Kanauj in A.D. 1020, and the opponent of Mahmud of Ghazni in 1021. He is called Nanda Deva and Beda Deva by the Muhammadan historians, both easy corruptions of Ganda in Persian characters. The mere omission of the *markaz*, or the substitution of a point, would have changed *Ganda* into *Nanda*, or even into *Beda*. The beginning of Ganda's reign would appear to have been disturbed by an invasion of the Kalachuri King Kokkala, as there is an inscription of Sri Kokkala in one of the temples, dated in Samvat 1058, or A.D. 1001. It seems more probable, however, that Kokkala was only a private individual, as the inscription does not give him the title of king, but calls him simply *Srimat Kokkala*.

Nos. 9 and 10.—Of these two nothing is recorded.

No. 11.—Deva Varmma Deva is known only from a copper-plate inscription, translated by Mr. V. Smith.¹ It is dated in Samvat 1107, or A.D. 1050. He is called Kālanjarādhipati, or "Lord of Kālanjar," and is expressly stated to be the son of No. 11, or Vijaya Pāla Deva. We learn also that his mother was named Bhuvana Devi.

No. 12.—Kirtti Varmma Deva was the brother of Deva Varmma. His reign was probably a long one, as we have his inscription from Deogarh dated in Samvat 1154, or A.D. 1097,

¹ See Bengal Asiatic Society's Journal, 1878, page 82.

just 47 years later than his brother's copper-plate.¹ To him is attributed the construction of the Kirat Sāgar at Mahoba, and there are several broken inscriptions which bear his name, but they are unfortunately without date. There are also gold coins inscribed with his name *Srimad Kirtti Varmma Deva*. Apparently Kirtti Varmma was one of the most powerful of the Chandel kings. His territory extended to the south, down to the great fort of Deogarh on the Betwa, to the south-west of Lalitpur. At his court was performed the curious drama, named *Prabodha Chandrodaya*, or "Rise of the Moon of Intellect," composed by Krishna Misra. In the prologue to this work he is represented as having been at war with the powerful Karna (the Kalachuri Prince of Chedi); but the enemies of the king having been destroyed, the administration of government is entrusted to his celebrated ministers, and having entered on the road of peace, he commanded the manager to act the "Rise of the Moon of Intellect." Kirtti Varmma was the contemporary of Bhoja of Malwa and of Bhima Deva of Gujarât, as well as of Karna Kalachuri of Dâhal or Chedi.

No. 13.—Hallakshana, or Sallakshana Varmma Deva, was the son of Kirtti Varmma. In one inscription he is called Sulakshana. To him is ascribed a great victory in Antarbéd, or the Doab of the Ganges and Jumna. He is called Hallakshana on his coins, of which I have specimens both in gold and in copper.

No. 14, Jaya Varmma Deva.—The British Museum has a silver coin of this prince from the Prinsep collection, and I possess seven of his copper coins. He restored the long inscription in the temple of Siva, in which the emerald lingam had been enshrined by Raja Dhanga. The original inscription, which had been written in *Kirnakshara* characters, or "bent letters," he restored in *Kumardâkarâni*, or "beautiful characters," in the Samvat year 1173, or A.D. 1116.

No. 15, Jaya, was succeeded by his brother *Hallakshana*, or Sallakshana II., who could not have reigned for more than a year or two.

¹ See Archaeological Survey, Vol. X. p. 103.

No. 16, Prithvi Varmma.—Of him nothing is recorded ; but I possess four of his copper coins. He was succeeded by his son,

No. 17, Madana Varmma Deva.—His reign was a long one, as we possess inscriptions of various dates, beginning with Samvat 1186, or A.D. 1129, down to 1220, or A.D. 1163. He made the beautiful lake of Madan Sâgar at Mahoba with its two temples. Of his coins I possess two large and four small specimens in gold, and one in copper. In one of the inscriptions it is said that “ he in an instant defeated the King of Gurjara, as Krishna in former times defeated Kansa.¹” During his reign the Chandel kingdom probably attained its greatest extent and prosperity.

No. 18, Paramârddi Deva, or Parmâl.—The annalists interpose a second Kirtti Varmma as the son and successor of Madana ; but as I have found no other trace of him, I doubt their accuracy. Paramârddi, or Parmâl, or Parmâlik, was certainly on the throne in Samvat 1224, or A.D. 1116, or only four years later than the last of Madana Varmma’s inscriptions. Paramârddi had a long and eventful reign. According to the annalists, he lost his kingdom because he was not a Varmma, as his predecessors had been. But the title of Varmma is first found in the inscriptions with Deva Varmma, the 12th Raja ; and we now know that at least four of Paramârddi’s successors bore the name of Varmma, so that the title did not die with him.

Early in his reign, or in Samvat 1239=A.D. 1172, Paramârddi was attacked and conquered by the famous Chauhân Prince Prithivi Raja, whose inscriptions at Madanpur I have already made known.² After his defeat the dominions of Paramârddi were limited by the Dhasân River on the west, and by the Bijâwar and Panna Hills on the south. But he still held Mahoba and Khajurâha to the west of the Kiyân or Ken River, and Kâlanjar and Ajaygarh to the east. A copper-plate inscription at Rewa, dated in Samvat 1297=A.D. 1240, with the name of Trailokya Varmma Deva, would seem to show

¹ Bengal Asiatic Society’s Journal, 1848, page 319.

² Archæological Survey Reports, Vol. IX.

that the Chandel kingdom had been extended to the eastward by the defeat of the Kalachuris. His earliest inscription is dated in Samvat 1224, or A.D. 1167, and his latest in Samvat 1240, or A.D. 1183. But we know that his reign continued for 20 years longer, down to A.D. 1203, when he was besieged in Kālanjar by Kutb-ud-din Aibak. He made arrangements for surrendering the fort, but was murdered by his minister, who, after a few days' further defence, was obliged to surrender by the failure of the water, on 27th April, A.D. 1203. The minister was killed and the fortress was occupied by the Muhammadans, who desecrated the temples and raised mosques in their places. But the fortress was soon recovered by the Hindus, and probably remained in their possession for some time.

No. 19.—Trailokya Varmma Deva was the son and successor of Paramārdi. There is an inscription of this Raja in the fort of Ajaygarh, dated in Samvat 1269, or A.D. 1212. When or how he recovered Kālanjar is not known; but he was in full possession in A.H. 631, or A.D. 1233, when the troops of Iltutmish, King of Delhi, under the command of Nusrat-ud-din Tāyasi, invaded the territory of Kālanjar for the purpose of plunder. The country must have been rich, as the invader returned with one hundred and twenty-five lakhs of some coin unnamed, but which was probably *dirhems*.

No. 20.—Vira Varmma Deva I. was the son and successor of Trailokya. Of his reign there are three stone inscriptions, dated respectively in Samvat 1313, 1325, and 1337, or A.D. 1256, 1268, and 1280. There was also a copperplate of his time, dated in Samvat 1337, which was in the possession of Colonel R. R. Ellis, and which was lost in the mutiny. His name was read as Sri Sandin Barm Deo by Colonel Ellis' pandit, for which I guessed Sri Sandhira Varmma Deva;¹ but which I now see must have been Sri Mad Vira Varmma Deva.

No. 21.—Vira was succeeded by his son Bhoja Varmma Deva, of whom we possess a notice in a long inscription dated

¹ Archæological Survey, Vol. II, p. 455.

in Samvat 1345, or A.D. 1288. This inscription records the genealogy of Nāna, the minister of the *Chandrātreyā* line, that is, of the Chandel princes. He sent his horse to Bhoja Varmma, who is apparently "the newly-appointed royal Lakshmi," whom Nāna's father had supplicated (verse 27). The inscription itself is now in the Indian Museum in Calcutta. It is written in the well-known square characters of the later Chandel princes, which in this record are called *chitra-varna*, or ornamented letters.

There is a long inscription of Bhoja Varmma himself near the *Ashta Sakti* figures at the Terhauni Gate of the Ajaygarh Fort. It is cut in the rock, and measures 7 feet by 2 feet 4 inches. It contains 15 lines in large *chitra-varna* characters. The genealogy of the prince is given, beginning with Kirtti Varmma.

No. 22.—The successor of Bhoja Varmma was apparently a second Vira Varmma. There are two inscriptions, dated in Samvat 1372, or A.D. 1315, in one of which I find the name Vira Nripa, and in a third inscription of apparently the same date a Vira Varmma is mentioned.

No. 23.—The name of Sasāngka-bhūpa is found in an inscription near Raypur, in the Koti District, 24 miles to the south-east of Kālanjar. The inscription has 23 lines, but it is much injured in the middle. I have not seen it; but my information is derived from an impression taken by one of Colonel Ellis' servants. In the 10th line I find the name of Sri Vira Raja Nripa, and in the 21st line the name of Sāsangka-bhūpa. The date is given very fully as Samvat 1408 varshe Sake 1273, Ashadha sudi 11 Budhavāsare divasa, or Wednesday, 6th July, A.D. 1351. The absence of the name of Varmma might be supposed to show that Sasāngka was not a Chandel. But in this very inscription the name of Vira Raja occurs without Varmma. We know, also, that the name of Varmma was certainly discarded by the later Chandel princes, as the Raja of Kālanjar who opposed Sher Shah was named Kirat Singh.

No. 24.—The name of Bhilama Deva Rāja is found in a short inscription at Bachon, near the left bank of the Kiyān or

Ken River, 15 miles from Ajaygarh. There is no direct proof that he was a Chandel prince, but the near vicinity of Bachon to the great Chandel stronghold of Ajaygarh makes it almost certain that it must have formed part of the Chandel dominions. The inscription is dated in Samvat 1433 and Sake 1298, both equivalent to A.D. 1376.

No. 25.—The name of Paramârddi-mahîpateh is found in an inscription at Râsin, which is dated in Samvat 1466, or A.D. 1409, on Saturday, the 7th of the waxing moon of Chaitra, or Saturday, the 23rd March 1409. The reign of Paramârddi II. may be assigned to the year 1390 to 1420 A.D.

Nos. 26, 27, 28, 29.—I have found no trace of the names of the Râjas who must have reigned from A.D. 1420 to 1520. During this period there would have been only four generations, but there may have been as many as six or eight reigns.

No. 30.—Kirat Singh was the last actual Raja of Kâlanjar. He was besieged by Sher Shah, and was put to death by Islâm Shâh after the capture of the fort in A.D. 1545. He was almost certainly the father of the famous Princess Durgâvati, the Queen of Dalapati, the Gond Raja of Garha Mandala, who reigned from A.D. 1530 to 1548. With Raja Kirat Singh and his heroic daughter Durgâvati the Chandel sovereignty came to an end, after a brilliant career of seven centuries and a half, from A.D. 800 to 1545 and 1563.

The fort of Kâlanjar was acquired by Akbar in A.H. 977, or A.D. 1569, and it remained in the hands of the Mughals until the time of the great Bundela Chief Chhatra Sâl. It was held by his descendants until A.D. 1812, when it was surrendered to the British Government.

The latest Khajurâha inscription is of Paramârddi Deva, with the date of Samvat 1234, or A.D. 1177, in the early part of his reign. When the Muhammadans invaded the country of the Chandels, they at first made their head-quarters at Kâlanjar; but after the Hindus had recovered the fortress the Muhammadans retained Mahoba and the plain country to the west of the Kiyân or Ken River, which included the old

religious capital of Khajurâha. It is no doubt on this account that no Hindu inscriptions are to be found either in Khajurâha, or Mahoba, after the Muhammadan conquest. There is a masjid in Mahoba, with an inscription of Tughlak Shah of Delhi; and Khajurâha (or Kajarrâ) was visited by Ibu Batuta in A.H. 743, or A.D. 1342 during the reign of Muhammad. He mentions the temples and the jogis with matted hair, who were attended by numbers of Musalmans who were desirous to learn their secrets.

From the above abstract we learn that the Chandel rajas were in possession of the fortress of Kâlanjar for about four centuries, or from A.D. 800 to 1203, when the place was captured by Kutb-ud-din Aibak. It was soon re-captured by the Hindus, and must have remained in their possession for some time, as several attempts were shortly after made by the Muhammadans to re-take it. But the power of the Chandels was broken, and many of them left their country to seek safety and independence beyond the reach of the Moslem domination. Thus the present Chandel Rajas of Handur and Kahalur (near Simla) trace their descent from emigrants from Mahoba in the beginning of the 13th century of the Christian era. A large body also marched eastwards and sought refuge in the wild country near Bardhi, where the Son River breaks through the Kaimur and Vindhya ranges of hills. But the great body of the people still remained in their native country of Jejahuti with their capital of Ajaygarh. Their power seems to have gradually declined until the province was finally annexed to the Mughal empire by Akbar in A.H. 977, or A.D. 1569.

25.—MAP OF N.-W. INDIA BY PTOLEMY.

In attempting to identify the cities and peoples of ancient India mentioned by Pliny and Ptolemy, it is startling to find how very few names have been preserved to the present day. The names of the rivers have mostly remained unchanged, as the Ganges and the Jomanes (or Gangâ and Jamunâ), and even smaller streams at the Tamasis (Tamasa or Tons), the Cainas (Ken or Kiyân) and the Sonus (or Son). The great

provinces of Indo-Scythia and the Kaspiræi were, no doubt, occupied by the Sakas and Kushâns. The territory of the latter, according to Ptolemy, included Modura, or Mathura, and their coins and inscriptions are still found there in considerable numbers. But to the east of the Kaspiræi we find the territories of Sandrabatis, the Bolingæ, and the Poruari, between the Ganges and *Vindius Mons*, or the Vindhya Mountains, with the Son River on the east; while to the south are the Phullitæ, the Kondali, the Bettigi, the Adisathri, and the Soræ *Nomades*—not one of whom has yet been identified. I will now examine these names in succession, in the hope that I may be able to throw a few rays of light on this dark quarter of Indian geography.¹

Sandrabatis.—This district is bounded on the west by the Kaspiræi, whose territory included Modura, or the holy city of Mathura of the present day. To the south lay the Vindhya Mountains, and to the east the Tamasis, or Tons River. With these landmarks I venture to guess that the province of Sandrabatis derived its name from the *Charmanvati*, or Chambal River, and that it comprised the whole of the country lying between the Chambal and the Tons Rivers, thus including the northern half of the present Gwalior territory, with the whole of Bundelkhand and a strip of Rewa.

The towns of Sandrabatis mentioned by Ptolemy are—1, Tamasis; 2, Kuraporina; 3, Empalathra; and 4, Nadubandagar.

The first of these may, I think, be identified with the famous hill of Kâlanjar, which, before it was fortified, was well known as the favourite abode of *Tapaswis*, or “Ascetics.” H. H. Wilson says that it is mentioned in the Vedas, and that it was one of the *Tapasya-sthânas*, or “spots adapted to practices of austere devotion.” By a very slight change the Greek *Tamasis* may be read as *Tapasis*.

The second name, *Kuraporina*, as I have already suggested, may possibly be a corruption of Khajurapura by the simple elision of the letter j-, thus making Khurapura.² It was the

¹ See Plate XXIV for Ptolemy's Map of India, south of the Jumna.

² According to Vararuchi, the letter j might be elided.

capital of the country in the time of Abu-Rihân, and it still possesses the largest and finest collection of rich and stately temples in Northern India.

The third name, *Empalathra*, is a difficult one. I think that it may be Mahoba, of which the full name is Mahotsavanagara.

The fourth name, *Nadubandagar*, is even more difficult. I think that it may be intended for Nalapura-dûrgga, or Narwar, as it stood on the high road leading from Modura to Kurapornia, which agrees exactly with the position of Narwar. The fort is said to be as old as the time of Raja Nala, from whom it derived its name.

The district of the *Bolingæ* is placed to the east of Sandrabatis, and to the north of the Vindhya Mountains. It corresponds generally with the present state of Rewa, of which the earliest inhabitants are said to have been the Bâlands, or Bâlandas. They were first driven northward by the Kalachuris and afterwards by the Chandels, until they reached the Ganges. They have left their name in the town of Balwaniya, 35 miles to the south-south-east of Mirzapur. Mr. Carlleyle also suggests that Ptolemy's fort of Balanti-purgon, which I have identified with Bandho-garh, may have derived its name from the Bâlands. Bâlandi-garh would be the natural name for their capital, and Bândhōgarh would be a natural abbreviation of the name.

Only two towns are mentioned as belonging to the Bolingæ. They are named—1, Sagabaza, and 2, Bardaotis. The first seems to suit the position of Nâgodh, an old town belonging to the Parihâr Raja of Uchahara.

The second place, Bardaotis, I have already identified with Bharhut, where I discovered the remains of a grand Stûpa, surrounded with a richly carved railing representing many of the principal events in the life of Buddha, as well as a large number of the Jâtakas, or former births of Buddha. These sculptures are known to belong to the 2nd century before the Christian era, from the style of the characters used in their descriptive titles.¹

¹ See my Stûpa of Bharhut for a discussion on the date.

To the south of the Bolingæ, Ptolemy places the *Poruari* with their three towns, named *Bridama*, *Tholobana*, and *Malaita*. The people I take to be the *Parihâr* Rājputs, who have occupied this part of the country from a very early date. I have already mentioned the *Parihâr* Raja of Uchahara, who traces his lineage up to a remote period. As the *Parihârs* are said to have been subjected by the *Kalachuris*, they were probably in possession of the country before the *Kalachuri* conquest of *Kālanjar*, and the establishment of the *Chedi*, or *Kalachuri* era, in 249 A.D.

The first town, *Bridama*, I would identify with *Bilahari*, an old town which possesses many ruins of the early *Kalachuri* princes. The second town, *Tholobona*, I would identify with *Bahuriband*, a very old town, with a number of *Gupta* temples in its neighbourhood. Perhaps the name may have been altered from *Bolobana*, which would be a very close approach to *Bahuriband*, or *Boriband*, as it is quickly pronounced.

The third town, *Malaita*, I would identify with *Multai*, an old town 30 miles to the north-east of *Jabalpur*, where some old copper-plate inscriptions have been found.

Still further to the south Ptolemy places the *Phullitæ* and the *Kondali*, whose country is described as *Pars Phullitarum*. *Phullitæ* I take to be a Greek name descriptive of the *Parna Savaras*, or "leaf-clad *Savaras*," one of the most powerful of the aboriginal races in the early centuries of the Christian era. Their only town was *Agara*, which may perhaps be identified with *Sâgar*.

To the west of the *Phullitæ* were the *Parapiotæ*, with a single town, *Adisathra*, which I would identify with *Bidisa*, or *Besnagar*, one of the oldest towns to the north of the *Narbadâ*. It is happily situated in the fork at the junction of the *Besali* and *Betwa* Rivers.

To the east of the *Phullitæ* and to the south of the *Poruari*, Ptolemy places the country of the *Adisathri* with their capital, named *Sageda Metropolis*. The *Adisathri* I would identify with the people of *Chattisgarh*. If this be correct, their capital must be looked for at *Sirpur* on the

Mahânadi River. Their other town, named *Balanti-purgon*, is, most probably, the curious hill city described by the Chinese pilgrims Fa Hian and Hwen Thsang. The latter calls it *Po-lo-mo-lo-ki-li*, or *Paramala-giri*, and says that its name meant the "black peak." *Kili* or *giri* is certainly a hill, but the only word resembling *Polomolo*, with reference to blackness, is *bhramara*, or the great "black bee." Another Chinese writer says that the word meant "coral beads," which would be *Palâ-mâlâ*, or coral necklace, in Sanscrit. A third Chinese author says that the city was named *Pa-lai*, or "situated on a height." This would point to *bala*, or *balla*, which is the *Korku*, or *Kolian*, term for a hill: *male* also means a hill in several of the aboriginal dialects. Any of these names might be identified with Ptolemy's *Balanti-purgon*, supposing that the term meant "a hill fort." The position of the city described by the Chinese writers from hearsay has not yet been ascertained.

To the south of all these were the *Bettigi* on the west, and the *Sora Nomades* on the east. The former I would identify with the people of *Vâkâtaka*, or *Bândak*, and the latter with the Savaras of South Chattisgarh. The Rajas of *Vâkâtaka* were contemporary with the Guptas, and I have lately found an inscription of Prithivi Sena, one of their early kings, showing that their power once extended to Khutara, only 20 miles to the south-west of Nâgodh.

The *Soræ Nomades* I take to be the pure aboriginal race of *Savaras* or *Sauras*, and their chief town *Sora Arcati regia* must have been named after them. They still extend from the Mahânadi down to the sea-coast of Ganjam. I think that *Sora* may be identified with Savari-Nârâyan on the Mahânadi River. It is a famous place of pilgrimage, and lies on the high road from Bilâspur to Jagannâth. It is about 35 miles to the south-west of Bilâspur and 75 miles to the north-east of Raypur. The people of the present day refer its name to the woman Savari, who is connected with the legendary history of Râma. The term *Arcati regia* may perhaps refer to the temple of the sun (*arka*), which is apparently the oldest building now existing at Savari-Nârâyan. The temple now holds a figure of Vishnu, but its original dedication to the Sun god

is attested by a figure of the god being placed over the middle of the entrance doorway. There is a ruined site close to Ghâzipur, which is still called Suîri-ka-râj, which is said to have received its name from the Suîrs or Savaras, and which at once recalls the Savari or Suari-Nârâyan on the Mahânadi.

26.—NACHNA, OR KUTHARA.

The small village of Nachna is situated 2 miles to the west of the town of Ganj, which is 25 miles to the south-east of Panna, and 15 miles to the south-west of Nâgodh. The place lies in the southern extremity of the Ajaygarh territory, and it was from the Raja himself that I first heard of the ruined temples near Ganj. The little village of Nâchna stands on a clearing made by a party of twenty families of Kols in the beginning of the present century. The spot is covered with bricks, and there are many remains of brick buildings on the road from Ganj to Nâchna. The people say that Kûthara was a great city in former times, and that it was the capital of the king of the country. The site of Nâchna is still called Khâs Kûthara. In the early history of the Bundelas it is recorded that Sohan Pâl, the fourth in descent from Pancham, the founder of the family, captured *Kûtharagarh* about the middle of the 15th century.

Lakhura is the name of the ground outside the fort of Kûthara. It was called Lakhura, or Lakhâwara, because the Raja had planted there one lakh of mango trees, and had also fed one lakh of Brahmans. There is said to be a tunnel from the fort of Kûthara to the Satna or Gorena Nala, which flows past Nâchna, and joins the Kiyân or Ken River, 11 miles to the south-west of Ganj.

In the Atlas map of India the name of the village is erroneously written as *Narhwa*, instead of Nâchna. The whole way from Ganj lies through jungle, chiefly of dhâk trees, from which the Kols collect gum for sale. There are many *pân* gardens near Ganj, which is a sure sign of an old Hindu city. The position in the entrance of a valley had the great advantage of offering a safe retreat into the recesses of the Vindhya Hills on the east, west, and south, in case of attack.

There are two temples still standing at Nâchna, one named after the goddess Pârvati, although at present it possesses no statue; the other named Chaturmukh Mahâdeva, after the colossal four-faced lingam, which is still enshrined inside.

The temple of Pârvati is one of the most curious and interesting shrines that I have seen. It is curious from the conventional imitation of rock-work on all the outer faces of its walls. It is especially interesting, as it seems to preserve the old fashion of the temples cut in the rock. The figures on the outer walls and on the doorway are all in the Gupta style of sculpture. The entrance doorway has the figures of the Ganges and Jumna standing on their respective symbols, the crocodile and tortoise. And, lastly, all the roofs are flat, like those of known Gupta temples at Sânci, Eran, and Tigowa.

The Pârvati Temple is a building of two storeys. It is nearly square, 15 feet 9 inches by 15 inches in plan, with plain perpendicular walls. The lower storey is surrounded by a roofed cloister upwards of 5 feet wide, which is closed, except in front of the entrance door, by a wall, 3 feet thick. In front of the entrance there is an open, unroofed court, nearly 12 feet square, which is reached by a flight of steps, $4\frac{1}{2}$ feet in height.

The upper storey is quite plain both inside and outside. It was covered by a flat roof of apparently three slabs. These are still on the top of the walls, but are much tilted and out of position. The joints were covered as in the known Gupta temples. The doorway is on the west, and the chamber is lighted by two trellises, one in each side wall. These are formed simply by two plain loop holes, one on each side.

The doorway of the lower storey is very richly carved with human figures in pairs on each jamb, ending with small statues of the Ganges and Jumna. The figures are all of the Gupta period, and are much superior to all mediæval sculpture, both in the ease and gracefulness of their attitudes, as well as in the real beauty of the forms. The hair of the male figures is arranged in the same fashion as that of the Gupta kings on their coins, with rows of curls, like the wig of a judge. There are no obscene figures.

The sanctum is dimly lighted on each side by a stout trellis of simple square holes, which receives its light from another trellis in the cloister wall opposite. In the middle of each of the outer faces there is a large trellis, with two horned lions and two men. On one side the trellis has four small pillars, with three openings, each pillar being ornamented with a human figure.

The outer faces of the walls (excepting only the upper room) are carved to imitate rock-work. A few figures are introduced, as well as a few lions or bears lying in holes or caves in the rock-work.

Inside there is a pedestal with a mortice hole for the reception of the tenon of a statue. This has been pushed to one side by some treasure hunter who dug up the floor.

In the accompanying plates¹ I have given a plan and elevation of this curious temple, with a sketch of one of the pilasters, and two of the peculiar ornaments on the lintel of the doorway. All these belong to the Gupta style, as shown in the temples at Eran and Udayagiri. There is no inscription, and not even a single letter or mason's mark could be found on any of the stones. But the Gupta style of the figures, the returns at the ends of the door lintel for the reception² of statues, the prominence given to the figures of the Ganges and Jumna, all point to a very early period. There is an inscription on a loose slab lying at Lakhuria which also certainly belongs to the Gupta period; and as Lakhuria forms part of the old capital of *Kūthara*, the record most probably belongs to some one of the old buildings. The inscription is written in the peculiar box-headed characters of the Vākātaka copper-plates, which is also found in the Eran inscription of Samudra Gupta, and in the Udayagiri inscription of Chandra Gupta II. This peculiar character was, therefore, in use during the 3rd century of the Christian era. But the inscription itself gives the name of one of the Vākātaka princes, Prithivi Sena, as suzerain, in conjunction with that of Vyāghra Deva, the local sovereign. Now Vyāghra was the father of Jayanāth, whose inscriptions are dated in the years 174 and 177 of the Gupta

era. Vyāghra therefore must have been reigning about 140 and 150 of the Gupta era, or about A.D. 300 according to my reckoning. He was, accordingly, a contemporary of Skanda Gupta. The temple may not be so old as the inscription; but, as it is undoubtedly of the Gupta period, it may perhaps be referred to about A.D. 400 with some degree of certainty.

The inscription, which is irregularly cut on a rough slab, consists of four lines on the face of the stone and two lines on the side or edge. But these two side lines are only a repetition of the inscription on the face. In the middle of the face there is a record as follows¹:—

1. Vākātakaṇam Mahārāja Sri
2. Prithivi Sena pādānudyāto
3. Vyāghra Deva mātā pitro punyabhi (?)
4. Kritam-iti.

The side inscription is incomplete; but it was certainly only a repetition of the record on the face. The work which it refers to was done by Vyāghra Deva, the tributary of Sri Prithivi Sena, Mahārāja of Vākātaka.

The other temple, called Chaturmukh Mahādeva, is quite different in style, although its doorway is similar to that of the Pārvati Temple. It is a square building, $11\frac{3}{4}$ feet inside and $16\frac{1}{2}$ feet outside. It has a tall spire, with slightly curved sides, and is now about 40 feet high. It stands on a raised platform, like that of the old temple at Deogarh. There are four broken figures of lions lying outside, each trampling on a bear. They probably flanked the staircases of the platform. In the middle of each side there is a stout stone lattice, surmounted by a couple of niches holding figures. There are also side niches; but these are now empty, with the exception of a standing figure of Brahmā with four arms. All the figures are draped. Inside, there is a colossal lingam, 4 feet 8 inches in height, with a large head, with a most elaborate head-dress on each of the four faces. The heads are all perfect; and this is sufficient evidence to prove that the temple could never have been seen by the idol-breaking Muhammadans. In fact, the two temples occupy such a secluded position in a jungly

¹ See Plate XXVII.

valley, far from any main road, that they have hitherto escaped the notice of English travellers. The Chaturmukh Temple must be considerably later than the other, and is probably not older than 600 to 700 A.D.

27.—JASSO.

The town of Jasso is situated about half-way between Ganj and Nāgodh, being 9 miles to the north-east of the former, and 10 miles to the south-west of the latter. It is now a small independent state, with a yearly revenue of ₹30,000. Jasso is said to have been called Hardi in former days, and to have been a great city of the Jains. It must certainly have been a place of some consequence, as there are numerous broken statues lying about, both Brahmanical and Jain, but chiefly the latter. At Dareda, to the south-west of Jasso, there is a large stone set up under a pipal tree, which is now worshipped as a lingam. It is, in fact, a natural lingam, 5 feet in height, and slightly bent and pointed towards the top. On one face there is a wheel, with the word *vāṅkātu* engraved above in old Gupta letters.¹ The wheel is similar to that on the old inscription slab at Lakhuria, near Nachna, and may perhaps be the cognizance of the old local chiefs of this district.

There is a very fine sheet of water at Jasso, with several Sati pillars on its bank. One of these, dated in Samvat 1396 [A.D. 1339], Jyeth badi 6, Thursday, bears several names of a Thakur's family.

In Jasso itself there is a pretty little lingam temple, called Kumhāra-math, or "Potter's Temple," because it was built by a *kumhār*, or potter. It is 27 feet square outside, with an entrance portico on the east, supported on four pillars. On the inner door step there is a single line of inscription of the 8th or 9th century, and in another place a part of the same inscription is repeated. It reads simply *Nehalasya Khaṇḍah*. In another place, in modern Nāgari, there is a record of three short lines, as follows:—

Rāma Rāma likhita-
sya Sri Paṇḍita Mā-
dhava Dāsa 96.

¹ See Plate XXVII.

This record cannot be more than two or three hundred years old.

28.—CHHOTA DEORI.

At different places, near the sources of the Kiyān or Ken River, there are some small ruined temples, which were once much frequented, but are now rarely visited. The best known of these ruined buildings is at Chhota Deori, or the "Little Temple," where there is a famous pillar with an old inscription. This pillar is held in great veneration, and even awe, by the people of the neighbouring villages, who do not like to go near it.

The pillar is 7 feet 2 inches high and 1 foot square. The inscription of 11 lines is near the top; in the middle there are two seated figures, male and female; and below there is a standing male figure. The inscription is in old characters of the 6th or 7th century. In the 1st line there is something like a date in three figures, preceded by a word which *may be* read as Samvat. The unit figure of 6 seems certain. At the end of the 1st line I read the name of Sangkaragaṇa, and in the latter half of the 5th and beginning of the 6th line I read without any doubt words¹—

Śrī Śangkaragaṇa Deva rājya.

"During the reign of the fortunate Śangkaragaṇa Deva."

This is, no doubt, the name of the reigning king. As the name is peculiar to the family of the Kalachuris of Chedi, I conclude that it must belong to one of them. There is mention of a Budha Raja, the son of Śangkaragaṇa, who was defeated by Mangalisa Chalukya about A.D. 550. This date is, perhaps, too early for the characters of the inscription.

Chhota Deori is 16 miles to the west of the Jokahi railway station.

29.—MARHIA.

At a few miles to the west of Chhota Deori, near the village of Marhia, there is a small ruined temple only 7½ feet

¹ See Plate XXVIII.

square inside, and $12\frac{1}{2}$ feet square outside. The lower walls are still standing, but there is no inscription.

30.—BARGAON.

Bargaon is a large village to the north of the high road, and just half-way between Damoh and the Jokahi station of the Jabalpur Railway, or 26 miles to the west of Jokahi. It is an old site of the Jainas, as shown by the remains of their temples and sculptures. One temple is still standing to a height of 21 feet above its basement. It is 13 feet square inside, and 31 feet long by $26\frac{1}{2}$ feet broad outside. The walls are plain. It possesses a weather-worn inscription, 3 feet in length by 13 inches in height, containing 12 lines of mediæval characters. It is too much weather-worn to be readable. In the 10th line I find the words *Kalachuri-nripa*, or "the Kalachuri King;" but this fact is only valuable as showing that the district of Bargaon belonged to the Kalachuris of Chedi, and not to the Chandels of Mahoba.

31.—SIMRA.

The village of Simra is situated 3 miles to the south of the Jokahi and Damoh road. It stands 15 miles to the west of Jokahi, and nearly opposite Marhia. On the bank of a tank there is a slab with two lines of inscription as follows :—

Samvat 1355, Sake 1220.

Rau Daosat Singh * Patnika Nanna Devi.

"In the Samvat year 1355, and Sake year 1220 [or A.D. 1298], Nanna Devi, the wife of Rau Daosat Singh (became Sati)."

During my long sojourn in India I have observed that nearly all the Sati monuments are placed on the western bank either of a stream or of a reservoir, with the face towards the east.

32.—BESÂNI.

Besâni is situated on the old line of road leading down from Kâlanjar and Ajaygarh, through Ganj and Kûthara and

Khopa to Bilhari and Jabalpur. It is 13 miles to the north-west of Jokahi.

On a loose broken slab, near the ruins of a temple, there is an incomplete inscription of six lines, which I read as follows:—

1. Samvat 958 prathama Ashâdha Sudi 3
2. Sutradhâra Jama De grihita dramâ 30 ta Sri
3. *Nitad (r) amâ 10, Suja grihita dramâ 100
4. Prithiva vasiṇi grihita dra (mâ) 10 Râu (t).
5. *Kâ grihita dra (mâ) 1,000.
6. * * * * * *

From the style of the characters the record cannot be nearly so old as Vikramâditya Samvat 958, or A.D. 901. I conclude, therefore, that the era must be that of Kalachuri or Chedi, which dates from A.D. 249. This is confirmed by the name of the month Prathama Ashâdha, which shows that there was an intercalary month of that name in the year when the slab was inscribed. Now, this was actually the case in the year 958 of the Chedi era, or $958 + 249 = 1207$ A.D. The mention of the intercalary month in this year is particularly valuable, as it proves that the tables of Hindu years with their intercalary months, which I have prepared for publication, are absolutely correct for the long period of nearly 700 years.¹ But my tables of intercalation are certainly correct for even a longer period, as I find that the month of Srâvana is recorded in an inscription as having been intercalary in the Sake year 1091, or A.D. 1169.²

I have not yet made out this inscription satisfactorily. The substance seems to record certain gifts of money (*dramâs*) by different individuals for some purpose not made out. The work was most probably connected with the temple near which the stone now lies. But the sum of money must have been small, as the *dramâ* (S. *dramya*) was a silver coin, the representative of the Greek drachma, and weighed a little

¹ Book of Indian Eras. Thacker & Co., Calcutta, 1884.

² Rice: Mysore Inscriptions, page 23.

over 60 grains. If the whole sum reached 300 dramās, it would not have amounted to more than 100 rupees.

33.—BAGHELKHAND, OR REWA.

How or when the Bāghels obtained possession of the upper valleys of the Son and the Tons, they themselves know nothing. They say that they came from Gujarāt, under Vyāghra Deva, either in Samvat 580 according to the Rewa chroniclers, or in Samvat 683 according to the Bāra chroniclers. Their first settlement was at Marpha, a large fort, 15 miles to the north-east of Kālanjar. This statement receives some support from the existence of two large villages, named Bāghelwāri and Bagholan, within 12 or 13 miles of Marpha to the north and south. He is also said to have married the daughter of the Raja of Tirhāwan on the Paisuni River, 15 miles to the east-north-east of Marpha, and a few miles to the north of Chitrkut. The Bāghel chroniclers assert that Vyāghra succeeded in making himself master of most of the country lying between Kālpi and Chunār. His son, Karna Deva, added the valley of the Tons River, or Rewa proper, and at last obtained possession of the famous Fort of Bāndhogarh by marrying the daughter of the Raja of Mandala.

The tract of country thus obtained forms the present state of Bāghelkhand. Previous to the conquest it is said to have been held by the Chandels, the Kalachuris (or Karchulis), the Chauhāns, the Sengars, and the Gonds. All these clans are still represented in Bāghelkhand by the Chandels of Bardi, the Karchulis of Raypur, the Chauhāns of Sidi, and the Sengars of Mhau and Naigarhi, while the Gonds have holdings in Singhwāra and other parts of the Rāmnaḡar Tahsil.

From inscriptions discovered in the northern hills at Piāwan and Alha Ghāt, we learn that the whole of the country above described formed part of the dominions of Gāṅggeya Deva, the Kalachuri Rāja of Dāhal, in the beginning of the 11th century, and that it was still in the possession of his descendant, the Dahaliya Raja Nara Sinha Deva so late as Samvat 1216, or A.D. 1159—and Vijaya Sinha, his nephew,

was certainly in possession of the southern half of the territory, or the valley of the Son, so late as A.D. 1181.¹

According to Tod, the Bāghels derive their name from Bāgh Rao, the son of Sidh Rai Jay Sinh. Bāgh Rao, or Vyāghra Deva, therefore dates from the death of his father in A.D. 1150. He was a contemporary of the Kalachuri Prince Nara Sinha Deva, and his son Karna may have married his daughter, as Nara Sinha must have been the ruler of Mandala, as well as of Tripura or Tewar. As it is quite certain that the Bāghela Chief would not have married a daughter of any Gond family, the Raja of Mandala could not have been a Gond at that time.

Nara Sinha Deva was succeeded by his brother Jaya Sinha Deva, who, according to the inscriptions, was a great warrior. He was followed by his son Vijaya Sinha Deva, of whom we have an inscription, dated in 932 of the Chedi Samvat, or A.D. 1181, at which time there was an heir apparent named Ajaya Sinha Deva. As no later inscriptions of the Kalachuri Prince have yet been found,² it seems probable that their rule may have come to an untimely end somewhere about A.D. 1200. We know that the great fort of Kālanjar was captured by the Muhammadans under Kutb-ud-din Aibek on 27th April 1203 A.D., when all the temples were destroyed and mosques built on their sites. As the fort was then occupied by the Muhammadans, I think it almost certain that either they or the displaced Chandels must have pushed their arms into the neighbouring territory of the Kalachuris. During the struggle for empire, and the consequent weakness of the Delhi state, which followed the death of Kutb-ud-din Aibek, the Chandel Raja of Kālanjar recovered possession of his fort, and with it the rule of most of his former territory. But the Delhi King towards the end of his reign, when his authority had become firmly established, col-

¹ Since the above was written, I have obtained later inscriptions on copper, which show that Vijaya Sinha Kalachuri was in possession in A.D. 1196, and Trailokya Varmma in A.D. 1240. Vyāghra's conquest must, therefore, be later than A.D. 1240. If the Bāra chroniclers' date of Samvat 683 be referred to the era of Harsha Vardhana, the date will be $683 \times 606 = 1289$ A.D.

² Except that of A.D. 1196, mentioned in the previous note.

lected a large force from Bāyāna, Kanauj, Gwalior, and other places, for a campaign against Kālanjar and Jamu. This was in A.H. 632, or A.D. 1234.

"The army marched on 50 days from Gwalior, and great booty fell into its hands, so much that the imperial fifth amounted to nearly 22 lakhs.¹"

The situation of Jamu has not been identified, and the name is very probably corrupt, but the distance of 50 days' march from Gwalior would tally with the position of the famous fort of Bāndhogarh.

At a later date, in A.H. 645 or A.D. 1247, a second campaign against Kālanjar was organized under the command of Ulugh Khan (afterwards the Emperor Balban). On this occasion the army advanced beyond Kālanjar against a Rāna, "over whom the Rais of Kālanjar and Mālwa had no authority." He bore the strange name of Dalaki-wa-malaki.

"He had numerous followers and ample wealth; he ruled wisely; his fortresses were strong and secure; in his territories the defiles were arduous, the mountains rugged, and the jungles many. No Muhammadan army had ever penetrated to his dwelling-place. When Ulugh Khan reached his abode, the Rāna took such care for the safety of himself and his family that he kept quiet from the dawn till the time of evening prayer, and when it grew dark he fled to some more secure place. At day-break the Muhammadan army entered his abode, and then pursued him, but the accursed infidel had escaped into the lofty mountains to an inaccessible spot impossible to reach except by stratagem and the use of ropes and ladders. Ulugh Khan incited his soldiers to the attempt, and, under his able direction, they succeeded in taking the place. All the infidels' wives, dependants, and children, fell into the hands of the victors, with much cattle, many horses, and slaves. Indeed, the spoil that was secured exceeded all computation.¹"

At first I thought that this powerful chief, who was independent of the Rajas of Kālanjar and Mālwa, must have been the Kalachuri Raja of Chedi or Dahal. The latter name also seemed to offer some similarity with Dalaki. But I have since found, amongst the early Bāghels, two Rajas in succession, named *Dalakeswar* and *Malakeswar*. These two names I take to be the originals of the Muhammadan author's

¹ H. M. Elliott's *Muhammadan Historians*, Vol. II, p. 366.

Dalaki-wa-Malaki. If this identification be admitted, then the Bāghel dominion had already been firmly established as early as A.D. 1247, and the "inaccessible" place in which the Raja took refuge must have been the famous fort of Bāndhogarh.

Ballār Deo, the 12th prince and the 2nd Rāja in succession after Dalakeswar and Malakeswar, is said by the chroniclers to have been a contemporary of Timur Shah, Emperor of Delhi, and to have given him assistance when he was hard-pressed, in return for which he received many honorary distinctions, along with the gift of the fort of Kālanjar. As the date of 1096 Samvat, or A.D. 1039, is assigned for this astounding event, we have a good test of the utter worthlessness of the dates given by the chroniclers. Birbhān Deo, the 9th Rāja, is said to have been a contemporary of Humāyun, whose family received shelter in Bāndhogarh, when he was obliged to fly before Sher Shah. The chroniclers, in fact, know nothing of the real history of their country. For instance, they attribute the foundation of Rewa, the present capital, to Rāja Vikramaditya, in A.D. 1618. But Rewa was in the possession of Jalāl Khan, at the time of Sher Shah's death, in A.D. 1545. The list of Rājas preserved by the chroniclers is most probably correct, as the names of the later princes have stood the test of comparison with the numerous notices of Muhammadan authors. For the following list I am indebted to the kindness of Major Barr, the Political Agent, now in charge of the Rewa State during the minority of the Raja. I am also indebted to the Raja of Bāra for a list of his ancestors from the foundation of the family under Vyāghra Deva, the common progenitor of the two dynasties of Rewa and Bāra. Each family gives a list of 31 princes, from the death of Vyāghra in about A.D. 1150 to the present time. In the Rewa list the 31st prince has passed away. In the Bāra list the 31st Prince is still living. These figures allow about 24 years to each generation, which is close to the usual average of Eastern families.

I have restored the spelling of most of the names in the following list, but a few still remain, of which I cannot even guess the original form.

BAGHEL RAJAS.

No.	DATE.		Names.	
	Samvat.	A. D.		
1	Siddh Rai Jay Sinh.	
2	Vyāghra Deva.	
3	Karna Deva . .	(Kandhāra Deva in Bāra).
4	Sohāga Deva . .	Founded Sohāgpur.
5	Sāranga Deva.	
6	Bishāl Deva.	
7	Bhanāh Deva.	
8	Anik Deva.	
9	Bālān Deva.	
10	1297	1240	Dalakesar Deva	{ Dalaki-wa-Malaki, A. D. 1246,
11	Malakesar Deva	{ of Minhāj (Tabakāt-i-Nasiri).
12	1357	1300	Bariār Deva.	
13	1387	1330	Ballār Deva.	
14	1417	1360	Singh Deoji Sidhi.	
15	1447	1390	Bhairava Deva.	
16	1447	1420	Narhar Deva.	
17	1497	1450	Bhīra Deva . .	Bhid, invaded by Sikander Lodi, A.D. 1494.
18	1552	1495	Sālivāhana Deva.	
19	1577	1520	Vīra Sinha Deva . .	— ? Founded Birsinghpur in N. Rewa.
20	1597	1540	Virabhāna . .	— Humāyun's family received shelter.
21	1611	1554	Rāja Rāma Deva . .	Copper-plate Rāja Rāma Chandra, S. 965 = A.D. 1557.
22	1648	1591	Virabhadra.	
23	1649	1592	Vikramāditya . .	Founded city of Rewa.
24	1658	1601	Duryodhana.	
25	1677	1620	Amara Sinha . .	Reigning in 1625 and 1634.
26	1702	1645	Anūpa Sinha . .	Attacked by Pahār Singh Bundela in A.D. 1650.
27	1727	1670	Bhana Sinha.	
28	1752	1695	Anirudha Sinha.	
29	1782	1725	Abdhut Singh . .	Six months old at father's death.
30	1832	1775	Ajta Sinha.	
31	1866	1809	Jaya Sinha Deva.	
32	1882	1825	Bishnāth Singh.	
33	1911	1854	Raghurāj Singh.	
34	1937	1880	Bankatesh Raman.	

I have already quoted the Muhammadan account of the invasion of the territories of Dalaki-wa-Malaki by Ulugh Khan in A.D. 1247, during the reign 'of Nāsir-ud-din Mahmud I. This was followed, about 50 years later, by a second attack under Ala-ud-din Muhammad Khalji, who, according to Abul Fazl, besieged Bāndhogarh in vain.¹

Our first detailed notice of Bāghel history is in the early part of the reign of Sikandar Lodi, A.H. 897 = A.D. 1492,

¹ Ain-i-Akbari, p. 367, note.

when Rai Bhid (or Bhira of the list), Rāja of Bhata, whose territories extended to Kantit on the Ganges near Mirzapur, had seized Mubarak Khan, Governor of Jaunpur. Mubarak was soon after released, and the king proceeded to Kantit, when "Rai Bhid came out to meet him and proffered his allegiance, for which the Sultan confirmed him in the possession of Kantit.¹" But the Rai, being suspicious of treachery, afterwards fled; and in A.H. 900 = 1494-95 A.D. Sikandar invaded his country for the purpose of chastising him. At *Khān Ghāti*, or *Gungauni*, he was opposed by Bir Singh Deo, one of the Raja's sons. The name of the place seems corrupt, and I think that it should be *Kathauli*, which is still the principal ghāt leading over the Vindhyan Range from Allahabad to the south. Bir Singh was defeated, and the king advanced against Bāndhogarh. "Raja *Bhid* fled towards Sirguja, but died on the road."² The king penetrated as far as Phāphund (20 miles to the north of Bāndhogarh), and then retired under the plea of want of provisions. As the new Raja shortly afterwards supported Sikandar against Husen Shah of Jaunpur, it seems probable that the king may have bought his assistance by his withdrawal of the besieging army.

A few years later (Ferishta says A.H. 904, A.D. 1498-99), Sikandar again invaded Bhata in person to revenge himself on Sālivāhan for the refusal of his daughter in marriage.

"He destroyed all signs of cultivation. His most valiant soldiers showed their courage at the fort of Bāndhu, the strongest castle of that district, and Sultān Sikandar having utterly devastated and ruined the whole of that territory, went back to Jaunpur."³

The successor of Sālivāhan was Bir Singh Deo, or Vira Sinha Deva, who may have been the son of Bhira Deva, who opposed Sikandar on his first invasion of Bhata. Bir Singh

¹ See Niāmatullah in H.M. Elliott's *Muhammadan Historians*, Vol. V p. 94. Sikandar then marched to Arail and *Bayāk*—according to Dowson, or *Biak* according to Dorn. For both of these names read *Payāg*, the common Hindu form of Prayāg, the modern Allahabad. Its position near Arail should have led to its identification.

² H. M. Elliott's *Muhammadan Historians*, by Dowson, Vol. V, p. 95.

³ H. M. Elliott's *Muhammadan Historians*, by Dowson, Vol. IV, p. 469.

Deo was followed by Birbhân, who, according to the chroniclers, gave asylum to the family of Humâyûn, when he was chased out of India by Sher Shâh. I first heard of this story at Asni on the Ganges just two years ago, as I have related in my account of that place, as follows¹ :—

“The people of Asni also have a strange story about Akbar. They say that, when Sher Shâh defeated Humâyûn, the latter fled to the west, leaving a Begam named Choli in Delhi, who was captured by the conqueror. Shortly afterwards Sher Shâh, being pleased with some verses of a bard named Narhar, told him to ask a boon. The bard accordingly asked that Choli Begam might be given to him, which the king granted. Narhar carried off Choli to Bândhogarh, in Rewa, where, soon after, she gave birth to Akbar. When he was twelve years of age, the boy Akbar asked Birbhân, the Bâghel Raja of Rewa, to let him have some soldiers, so that he might go up to Delhi and recover his kingdom from Sher Shâh. The Raja gave the troops, and Akbar advanced against Delhi, while Humâyûn returned from Ghazni. Sher Shâh was then dead and Islâm Shâh was defeated by Akbar, who thus recovered the kingdom of his father.”

This story has found general acceptance amongst the people, in spite of the explicit statement of the Muhammadan historians that Sher Shâh treated Humâyûn's queen in the most chivalrous manner. Thus Abbâs Khan, the author of the *Târikh-i-Sher Shâhi*, says :—

“Masnad Ali Haibat Khan told me, Abbâs Khan, the author of this book, that he was at Sher Khan's side, when the Emperor Humâyûn's queen, with other noble ladies and a crowd of women, came out from behind the *parda*. As soon as Sher Khan's eyes fell upon them, he alighted off his horse, and showed them every respect, and consoled them.”

The popular story, however, is likely to survive, as it has been related in a *kabîr* by *Ajbes*, the Bhat of the Raja of Rewa. Some, indeed, say that the verse finds favour owing to the wretched pun on the name of Akbar, to whom Raja Birbhân of Rewa is said to have been an *Akhe-bar* or *Akshaya-bar*, “the imperishable banian tree,” which is the name of the famous tree of Prayâg.

¹ See Archæological Survey, Vol. XVII, p. 101.

These are the verses—

“ Dilli kê jîtêk Sardâr, Mansabdâr,
Raja Rao, Umrao, sabhi ko nipât bhao
Begam bichâri bahi kitahu na pâlî thâh,
Bândhogarh, gâro gûr tâko pachh pât bhao,
Sher Shâh salil praleye ko baṛo Ajbes.
Bûrat Humâyûn kê mahâ hi utpât bhao,
Balhîn bâlak, Akabar bachâi-ve ko,
Birbhân bhûpati, Akhebar ko pât bhao.”

“ In Delhi all the Sardârs and the Mansabdârs,
‘ The Rajas, the Raos, and the Umraos, were distracted :
‘ The Begam, helpless, found no place of refuge,
‘ Till the stronghold of Bândhogarh became her protector.
‘ Then Sher Shâh’s power prevailed, says Ajbes.
‘ Though Humâyûn escaped drowning, he was in great distress,
‘ And the boy Akbar was saved solely
‘ Through Birbhân becoming his *Akhebar*.”

No. 20.—The son and successor of Birbhân was Raja Râma Chandra Deva, of whom we have numerous notices in the reign of Akbar. He is generally called Râm Chand by the Muhammadan authors ; but he is named Râma Chandra Deva in the lists, and also in a copper-plate inscription which I saw at Karra on the Ganges two years ago. The record is dated in “ Samvat 965,” which can only be intended for the Hijra reckoning. The date will, therefore, be A.D. 1557-58, or the third year of the reign of “ *Akbar Sâh Gâji*.”

Râma Chandra had already succeeded to the throne before Akbar, as he is mentioned as having given asylum to Ibrahim, the son of Sikandar Sur, in A.H. 962, or A.D. 1555. As he died in the 37th year of Akbar = A.H. 1000, or A.D. 1592, his reign may be fixed at about 37 years, or from A.D. 1555 to 1592. The following is Blochmann’s brief account of the career of Râm Chand and his successors as gathered from the Muhammadan historians¹ :—

“ Râm Chand was Raja of Bhat’h (or Bhattah, as the *Maâsir* spells it). Among the three great Rajas of Hindustân whom Bâbar mentions in his memoir, the Raja of Bhat’h is third.

“ Râm Chand was the patron of the renowned musician and singer Tânsen. His fame had reached Akbar ; and in the 7th year, the

¹ *Ain Akbari*, by Blochmann, p. 406.

Emperor sent Jalâluddin Qûrchi to Bhat'h to induce Tânsen to come to Agra. Râm Chand, feeling himself powerless to refuse Akbar's request, sent his favourite with his musical instruments and many presents to Agra, and the first time that Tânsen performed at Court, the Emperor made him a present of two lakhs of rupees. Tânsen remained with Akbar. Most of his compositions are written in Akbar's name, and his melodies are even now a-days everywhere repeated by the people of Hindustân.

"When Aḡaf Khân led his expedition to Gaḡha, he came in contact with Râm Chand; but by timely submission the Raja became 'a servant' of Akbar. In the 14th year, Râm Chand lost Fort Kâlanjar. He sent his son, Bîrbhadr, to court, but from distrust would not pay his respects personally. In the 28th year, therefore, when Akbar was at Shâhâbad, he ordered a corps to march to Bhat'h; but Bîrbhadr, through the influence of several courtiers, prevailed upon the Emperor to send a grandeé to his father and to convey him to court. Raja Bîrbhadr and Zain Kokah were selected for this office, and Râm Chand came at last to court, where he was well received.

"Râma Chandra was succeeded by Virabhadra or Bîrbhadr, who on his way from court to Bhath fell from his palanquin and died soon after, in the 38th year, or A.H. 1001 = 1593 A.D.

"Bîrbhadr had married a daughter of Rai Singh, son of Kalyân Mall, the Rathor Raja of Bikaner. Akbar interceded for their young children and prevented the widow from burning herself.

"Virabhadra's sudden death led to disturbances in Bândhu, of which Bikramâjit, a young relative of Râm Chand, had taken possession.¹ The history of the family is thus continued by Blochmann—Akbar therefore sent Ismâil Qulikhân to Bândhu, to convey Bikramâjit to court (41st year), their intentions being to prevent Bândhu from being conquered. But Akbar would not yield; he dismissed Bikramâjit, and after a siege of eight months and several days Bândhu was conquered (42nd year).¹

"In the 47th year, Duryodhan, a grandson of Râm Chand, was made Raja of Bândhu. In the 21st year of Jahangir's reign, Amar Singh, another grandson of Ram Chand, acknowledged himself a vassal of Delhi. In the 8th year of Shahjahân, when Abdula Khan Bahâdur marched against the refractory Zamindâr of Ratanpur, Amar Singh brought about a peaceful submission. Amar Singh was succeeded by his son Anûp Singh. In the 24th year, when Raja Pahâr Singh Bandela, Jagîrdâr of Chauragadh, attacked Anûp Singh, because he had afforded shelter to Dairâm, a zamindâr of Chauragadh, Anûp Singh, with his whole family, withdrew from Rewa (which, after the

¹ Ain Akbari; by Blochmann, p. 407.

destruction of Bāndhu, had been family seat) to the hills. In the 30th year, however, Sayyed Calābat Khan, Governor of Ilahābād, conducted him to court, where Anūp turned Muhammadan. He was made commander of 3,000 infantry, 2,000 horse, and was appointed to Bāndhu and the surrounding districts."

With Anūp Singh our Muhammadan authors fail us, and we are reduced to the scanty records of the chroniclers. According to them, Abdut Singh, the 28th Raja, was only six months old at his father's death, about A.D. 1725. His country was accordingly soon after invaded by Hridaya, or Hirde Sāh, the Raja of Panna, who succeeded his father Chhatr Sāl in 1718 A.D. The invasion probably took place about A.D. 1730, when the capital was occupied by Hirde Sāh, while the Raja fled to Partābgarh. His reign was a long one, probably from 1725 to 1775 A.D.

He was succeeded by his son Ajit Singh, who was followed in A.D. 1809 by Jaya Sinha Deva. "It was during his rule that British influence was established in Bāghelkhāṇḍ, and the first formal treaty between the British Government and Rewa was made with Jaya Sinha Deva in 1812 A.D."

Jayanāth was succeeded by his son Bishen Nāth, who abdicated in 1854 in favour of his son the late Raja Raghurāj Singh, who died in 1880.

34.—PIĀWAN.

The Tons River, with its tributaries, has long been known for the number of its water-falls and the wild beauty of its scenery. The falls are found from 20 to 30 miles to the north and north-east of Rewa, where the river rushes down the Vindhya Hills to join the Ganges near Panāsa. All the principal falls are considered holy by the Hindus, and pilgrimages are still made to them by devout people. One of these holy spots lies in a small valley, called Piāwan, 6 miles to the south-east of Kathaula, and 25 miles to the north-north-east of Rewa.

Piāwan, or Payāwan, means simply the "drinking-place." The spot is a small valley about 800 feet wide and half a mile in length, with precipitous rocks on both sides, about

200 feet high. At the western end a small stream falls over the cliff, and the rock below, on which the water falls, has been formed into an *Argha* for the reception of a lingam, or phallic symbol of Siva. A view of this Argha has been given by my assistant, Mr. Garrick, who first discovered the place. He has described it under the name of *Ḥhirna*, or the "water-fall." The name given to me was received from the people, who grazed their herds in the neighbouring hills, and who knew it only as the *Piāwan*, or "watering-place." The Argha is 14 inches in diameter.

On the upper face of the Argha there is an inscription of six lines in boldly carved letters, which are unfortunately much weather-worn. Mr. Garrick made a large photograph of the inscription, and my servants made several impressions of it on paper. The inscription is a valuable one, as it is the only record yet found of the Kalachuri Prince Gānggeya Deva, the contemporary of Mahmud of "Ghazni. He is mentioned by name by Abu Rihān, as *Gāngeo*, of *Dāhal*, of which the capital was *Pituri*, or, more correctly, Gānggeya Deva of Dāhal, of which the capital was Tripuri, now Tewar, near Jabalpur.¹ The inscription is especially valuable, as showing that the dominions of the Kalachuri kings of Chedi extended so far north as the Vindhya Hills, only 50 miles from Allahabad. The letters are much defaced, as people are constantly walking over the face of the rock. I read the text as follows:—

1. Sri mad Gānggeya Deva Mahārajadhirā—
- 2.—ja parameswara bha * maha mandale—
3. ṣwara * naka Sri Dhāhala mahābha * * *
4. sahitam Maheswara De * *
5. Asangga pranamati.
6. Samvat 789—* * Sri Dhāhalamiti.

The date consists of three figures, which I read as above, 789, of the Chedi era, equivalent to $249 + 789 = 1038$ A.D. The name of Dāhala is twice given, but both times as Dhāhala.

¹ Reinand; Fragments, pp. 85—106, and Elliott's Muhammadan Historians, Vol. I, page 56.

35.—ALHA GHAT.

Alha Ghât is one of the natural passes of the Vindhya Hills, by which the Tons River finds its way from the tableland of Rewa to the plain of the Ganges. From Allahabad to Chaukhandi at the foot of the Ginja Hill the distance is only 45 miles to the south-west. From Chaukhandi there is a clear view of the open valley of the Tons between the hills to Koni and Rupaoli on the left bank of the river. At Rupaoli the road crosses to the right bank, from whence begins the ascent by the Alha Ghât to Simol on the tableland, 22 miles to the north of Rewa. The distance is called 12 kos.

About one mile-and-a-half from the river there is a large cave, 110 feet in length, with a breadth of from 8 to 10 feet, and a height varying from 22 to 50 feet in the middle. At the main entrance it is 10 feet broad; but it has two other entrances on the right hand, each about 30 feet long, one by a passage varying from 3 feet to 2 feet in width, and the other varying from 6 feet to 3 feet. In the further corner of the cave there is a small pool into which water is constantly dripping. The cave has, of course, been in frequent use by ascetics; but no traces, either of inscriptions or of paintings, could be found on the walls.

About 100 yards from the cave there is a very large block of stone on which there are three inscriptions. The best preserved of these consists of seven lines, and contains the name of the Dâhaliya Raja Narasinha Deva with the Samvat date of 1216, or A.D. 1159. The second inscription has fourteen lines, but it is too much injured to be deciphered. I can read the following words:—

- | | |
|-----------------------------|---------------------|
| 1. Srimukho nâma Samvatsara | . (Srava)— |
| 2. na sudi | . Mahârajadhira— |
| 3. ja | . Brahmâ Deva râjye |
| 4. Ran. | |

As *Srimukha* is the name of the 7th year of the 60-year cycle of Jupiter, the exact date of the inscription might easily be obtained, if we only knew something about Brahmâ

Deva Raja. One of the sons of Paramârddi Deva Chandel, named Brahmâditya, is said to have fallen in the defence of Mahoba. If the inscription belonged to him the date might be A.D. 1209, which was the *Śrīmukha* Samvatsar, or the 7th year of the Jovian cycle in Northern India. There may have been a Kalachuri prince of this name, but we know nothing of the Kalachuris after Vijaya Sinha Deva in A.D. 1197. The presence of Nara Sinha Deva's inscription makes it highly probable that the other records on the same stone belong to the Kalachuri kings.

The third inscription consists of only four lines in bad order. There is no date and no Raja's name. The first line reads—

Rajâputra Sri Sosharma Devah Râ Râma Deva.

"The king's son Sri Sosharma Deva, (and) the Râ(ut) Râm Deva."

Râ is the conventional abbreviation for Râüt, just as Thâ is for Thâkur.

Near the foot of the Ghât there is a Sati Pillar with an inscription in large letters dated in Samvat (13)72 and Sake 1237, Aswina Sudi 10 Budha dine (A.D. 1315).

I now return to the first inscription of Nara Sinha Deva, of which nearly every letter is certain—see Plate XXVIII. I read the text as follows:—

1. Samvat 1216 Bhâdra sudi pratipada Ravau|| Dâhâliyan Mahârâjâ
2. dhiraja Sri Nara Singha Deva Vijaya râjye|| Pipala—mahâ—
3. rânak Sri Jalhana putra rânak Sri kkihulasya Kali-juga
4. Dharmmârtha khata Khandika Ghâta bandhan Margratetika Deva Karâ
5. pita iti|| Dharmmartha kâma moksha sadhana|| Kausâmbi nikâsa Ran—
6. ti Anâmajâti udharitah|| Thakur Sri Kamalâdhara likhita
7. sutradhâra Kamalâ Sinhah some | Kokâsam|| Pâlhana Jalhana.

36.—KEVATI-KUND.

Kevati-kûnd is a famous pool near the junction of the Mahâ River, with the Tons, 22 miles to the north-north-east

of Rewa, 9 miles to the south-east of the Alha Ghât, and 12 miles to the north-west of the junction of the two high roads leading from Allahabad and Mirzapur to Rewa. Kewati-sthâna is one of the holy places of the Tons circle. In the Atlas map, No. 89, the name is written *Keonti*, but it is always pronounced *Kevati*, and it is so spelt in the oldest of the four Sati inscriptions found on the spot. The Kûnd is a small pool into which the waters of the Mahânadi fall from a cliff 336 feet in height. The Kûnd is well known throughout Northern India, and is much frequented by pilgrims. Mr. Macaulay Markham describes it as "almost quite circular," and as hemmed in by perfectly perpendicular rocks on each side.¹ The water then flows "from over 2 miles through a canon of perpendicular rocks," keeping the full height almost the whole way. "On one side of the beetling crag is a fine old native fort, and on projecting crags, on the edge of the fall, are picturesque Hindu temples. Altogether it is a lovely spot."

In a cave close by Mr. Markham discovered an old Pali inscription of about 200 B.C. It has been read as follows by Dr. Hoernle—

Hâritîputenam Sonakena kâritâ pukharinî.

"The pool (cave) caused to be made by Sonaka, the son of Hâriti."

The slabs on which the Sati inscriptions are engraved are simple monumental pillars, as each of them has the figure of a soldier armed with sword and shield in the attitude of fighting.

The oldest of the four inscriptions marked A consists of five short lines, and is dated in the Samvat year 1390, on *Bhadra badi 4*, *Sanau dine*, or Saturday, the 31st July, A.D. 1333. The text reads as follows:—²

- A. 1. Aum ! Kevati-sthâna râje Si=
2. dhi kâritam yogai sataji Dadhi=
3. gauni milam Jujhitam-Samvat.
4. Samvat 1390 Samaye, Bhadra
5. sya badi 4, sanau dine.

¹ Journal of Bengal Asiatic Society, 1880, p. 121.

² See Plate XXIX—A.

Fujhitam is a term generally used for soldiers who have fallen in battle. This confirms the conclusion drawn from the figure of the fighting soldier.

The inscription marked B consists of six lines which I read as follows (see Plate XXIX):—

1. Aum ! Samvat 1397 Samaye Mâgha sudi 4 Soma dine||
tasmin Kâleva=
2. rattammâne Samvatsara|| Lukasthâne Mahârāja Sri
HAMIRA DEVA râjye|| Baori grâme Râ (u)
3. Sri Jai Singha Deva bhula mane|| tasya mânya Rau
Lohareswa Ran Drona para|| Kathau=
4. li-sthâna Mahârajadhirâja Sri Mahârāja *Devakasya* Pâdi-
mayura grâmati=
5. â got|| tasya judyanevarstiti|| asya vantwâri-hetita||
Sutradhâri Holi . . .
6. rupakâra Gâdhita|| Shangharo likhiti.

“ In the Samvat year 1397, on Monday, the 4th of the waxing moon of Mâgha (Monday, 22nd January 1341), in that year, during the reign of Mahârāja *Hamira Deva* of Lukasthâna, . . . Rau Jai Singh Deva of Baorigrâma, . . . Ram Lohareswa, Rau Drona . . . of Kathaulisthana Maharâjadhirâja Sri Maharâja Devaka, &c.”?

The date falls in the reign of Muhammad Tughlak of Delhi. Neither of the Rajas' names occurs in the list of the Bâghel kings of Rewa. Hamira Deva might have been a petty Raja of Lukasthâna; but the higher title given to the second Chief Devaka certainly denotes a king of higher rank than an ordinary raja.

The inscription marked C consists of seven lines, which I read as follows:—

1. Aum ! Samvat 1397 Samaye, Mâgha sudi 4, soma dine||
tasmin Kaleva-
2. rattammâne Samvatsara || Lukasthâne Mahârāja Sri Ha-
mira Devarâ
3. jye Baori grâme Ra (u) Jaya—Singha Deva râjya | taza-
manyâ.
4. Rau Loharasura | Rau Râmpâr Kathaulisthâna Mahâ-
rāja Sri .
5. Mahârāja Dendakasya Ghâdi Mayura Grâmahî âgat tasya
6. judhana varttini | asya sutra . . mâjara sâhita 3 ma sutra-
7. dhâ(ra) Nudi Devam hetitâ || Suvakâra Hâli, Rupakâra,
Phitam.

Here the fight is referred to distinctly in the beginning of the 6th line by the word *judhan*.

The inscription marked D consists of six lines, which I read as follows :—

1. Samvat 1397 varshe Māgha sudi 4 somadine tasmin
Kale-
2. varttamāna Samvatsara || Lukasthāne Mahārāja Sri Hamira De-
3. va rājye || Baorigrāma Rau Sri Jai Singh Deva . māna
ta-
4. sya manya Rau Vijaidhara sute Rau Yaso Kathaulisthāna
Mahā-
5. rājādhirāja Sri Mahārāja Devakasya Ghādikapura grāma-
6. hi agat | tasya judhya . ve tritā || Rau Duleharita

In the three inscriptions marked B, C, and D, we have the names of one Mahārājādhirāja Sri Mahārāja Devaka, of one Mahārāja Sri Hamira Deva, and of several Rājās. There are also three holy places mentioned as Kevati-sthāna, Kathaula-sthāna, and Luka-sthāna.

The names of two villages, Baodigrama and Mayuragrāma, occur in all three ; but I have not been able to identify them. The three holy places, or *sthānas*, still exist. Kevati-sthāna is now known as Kevati-kund ; Kathaula-sthāna is now the large village of Kathaula, near the Mamani Ghāt ; and Luka-sthāna is the large village of Lûk, on a low hill on the right bank of the Tons River near its exit from the hills.

Of the two Rajas I can find nothing certain. The foundation of Hamirpur on the Jumna is attributed to a Raja Hamira ; but his date is uncertain. From the date of Samvat 1397 = A.D. 1340, I should be inclined to conclude that the great fight, in which the Rājās fell, must have been between the Chandels and the Bāghels. In A.D. 1240 the Chandels were in possession of the country, and, so late as A.D. 1315, it seems probable that they still held the north-western portion of the Rewa territory under their King Vira Varmma II. I hope to have an opportunity of examining these inscriptions more leisurely during the ensuing cold season.

37.—GINJA HILL.

The Ginja Hill is an isolated mountain, about 800 feet in height, which stands out prominently in the plain close to the exit of the Tons River from the Vindhya Hills. It is 11 miles to the south of the Bargarh railway station, and 40 miles to the south-west of Allahabad. It is 1,326 feet in total height above the sea; and is similar in appearance to many of the hills about Kālanjar and Ajaygarh. The hill is said to be 3 kos, or 9 miles, in circumference at the base. The top of it is a narrow ridge of perpendicular rock about 200 feet in height, while the lower part is a steep slope all round, thickly covered with jungle. It is said to belong to the Bāra Pargana of the Allahabad District; but in all our maps it is assigned to the Native State of Rewa.

At rather more than half-way up the ascent there is a large reservoir of water about 200 feet round. Up to this point the ascent is tolerably easy, but above the tank it becomes very steep and difficult, and is much impeded by thorny jungle. On the south face of the top the scarped rock overhangs very considerably, and forms a large open hall, or rock shelter, about 100 feet long by 40 or 50 feet broad, and of irregular height, varying from 20 to 25 feet. It is closed at both ends by rough walls; but the whole of the front is open. In the middle of the rock at the back there is an inscription in red paint with some rude drawings of men and animals. The characters of the inscription are of the earliest Gupta forms; but the opening is worded in the well-known style of all the shorter Indo-Scythian inscriptions.

The letters were traced on oiled paper, and the accompanying plate gives a very faithful copy of all the better preserved portion of the inscription. I read it as follows:—

1. Mahārājasya Sri Bhimasenasya sam (vatsare) . 52 Gimha
pakshe 4 divasa 12 etaya-

2. purvayam Siddhi Sri triṣe ṣatasya puna *Gija ka* lika bhāta.

“(In the reign) ” of Mahārāja Sri Bhima Sena in the Samvat year (52), in the 4th fortnight of the hot season, the 12th day, on that date

The date may be explained in two different ways, either with reference to the era of the Seleukidæ, which would appear to have been in use with the Indo-Scythians, or with reference to the era of the Guptas. In the former case it must be taken as the year 452 of the era, the hundreds being omitted, and would correspond with 140 A.D., in the middle of the reign of the Indo-Scythian King Huvishka. In the latter case it would correspond with the year $166 + 52 =$ A.D. 221, according to my reckoning of the Gupta era. The Indo-Scythian style of the inscription, with its fortnights and seasons, is in favour of the earlier date. But the forms of the letters seem to me to be more in accordance with those of Samudra Gupta's inscriptions. The difference in date of 81 years is not great. But the style of recording the date agrees so exactly with that used by the Indo-Scythian Princes, Kanishka, Huvishka, and Vasu Deva, that I feel constrained to assign the record to the earlier period.

To the right and left of the inscription there are several very rudely drawn figures of men and animals sketched in outline in red paint. Their age is doubtful, as they have no connection with the inscription.

38.—KATKĀ OBELISK

On the west bank of the Tons River, opposite the village of Katkā, and close to the railway bridge, there is a very curious sculptured obelisk. From its position on the west bank of the river, and facing the east, it may be a Sati monument; but there is nothing about the sculptures on the four faces that is peculiar to the known Sati pillars of later times. The obelisk is $3\frac{1}{2}$ feet high, with two long faces of 20 inches and two short faces of 12 inches. The upper part above the four sculptures slopes backwards like the roof of a Dravidian temple, with three knobs on the top of the ridge.

The principal sculpture represents a Raja on horseback with his umbrella-bearer behind him, very much after the fashion of the Gupta gold coins. On the opposite face there is a four-armed figure of Bhainsāsuri Devi; with one hand she holds a leg of the buffalo, and in two other hands a sword

and shield. On one of the short sides there is a seated figure holding a cup in his right hand; and on the fourth side there is figure of Ganeṣa.

There is no inscription on the obelisk; but the sculptures and ornaments have so much in common with those of the Gupta period that I have no hesitation in assigning this curious monument to a very early date, not later than the 3rd or 4th century of the Christian era.

39.—HALIYA.

The town of Haliya is situated on the north or right bank of the Adh, or Adhwa River, as it is more usually called, 31 miles to the south-west of Mirzapur and 13 miles to the south of Lalganj. On the bank of the river, on a high point above the road, there is a large flat slab, 7 feet 8 inches high by 4 feet 6 inches broad, with two long inscriptions in English and Hindi, describing the capture of the fort of Bhopâri on the Son River on 18th April, A.D. 1811, by a regiment of Native Infantry. Both inscriptions are rather roughly cut.

The English inscription is as follows:—

“Under the auspices
of Lord Minto, Governor
General of India, and General Hewett,
Commander-in-Chief and Vice-President,
a passage was made through the *Kirahe Pass*,
of vast height, 2 miles in extent,
into *Burdee* for 18-pounders, &c., &c.,
by Lieutenant-Colonel James Tetley, Commanding
the 2nd Battalion, 21st Regiment, Native Infantry,
aided by the great exertions
of his gallant and willing corps,
the following of whom fell courageously
assaulting *Babarrah Ghurry in Burdee*,
April A.D. 1811:—

Which is now destroyed,
and levelled with the ground—
Golaub Sing Naick, Sepoys Cassce Deen,
Pheeroo Sing, Jysook, Deenah, Boodie,
Incha, Byjenaut, Goorange Sing, Poornu,
Bahâder Cawn, Golundauze,
Panchoo, Gun Lascar,

Soane, Head Bullockman.

Tilloock Sing, Sepoy of the same corps, killed at *Bissore Gaut*.
February 18th.—1 Jemadar, 2 Havildars, 2 Naicks, &c. 30
 Sepoys defending the post against 300 Banditti, beating
 them off."

The Hindi inscription, which consists of 25 lines, is rather fuller than the English one, as it mentions that no batteries were made, and that the guns were brought up close to the gate, but that the fort did not fall then, as the *kiladar*, or governor, made his escape. The Hindi text is given in the accompanying plate.¹ The following is an English transcript of this curious record, which, from its homely language, I judge to have been the composition of some of the sepoy themselves :—

1. Batâl 2 Rejmant 21 Karnal Tetali Sâheb Bahâdu-
2. 1 *Kidri ka* Ghâtâ banwayâ, Lât Manda (Minto)
3. Sâheb ke hukum se, Jarnai Hêwaṭ Sâheb ke
4. hukum se, path kaṭâi ke bagali patâi ke, wâ pâ-
5. thar se wâ mati se, bhar Ghâta dui kos ka tha au (?)
6. Sipâhi apañi khusi se, au kuchh log Mirjâpur se
7. mangâyâ thâ, Ghâta dui kos ka lambâ thâ athâ-
8. ra panî ke lejâne mâphak bana, au (?) Ghâta bahut
9. uchâ thâ, Sipâhi apañi khusi se banâya bari mehan-
10. t se, au BARDI ke rasta . au Tarikh 18 Sani 1811
11. mahina Abarel *Garhi Bhopâri* mâ larâi huâ, leken
12. murchâ nahi lagâ thâ, au Top chhapani dui thâ kilâ
13. te, pandarâ kadam par darwâja ke sâmane, au Dîwâl
14. nagich thâ au(r) Sipâhi kilâ ke nagich pahuncha, le-
15. kan kilâ us wakht nahi chhuṭa Sâm ke kilâdâr bhâ-
16. gi gayâ Bhopâri garhi Ghâti ke girâi ke barâbar kiyâ bâgi-
17. cha katâi ke bâhar phenk diâ indârâ (*wells*) girâ diâ. Jûjhâ
18. Nâik Gulab Singh; Sipâhi Jaisukh, wa Pheru, wa Kâsi din,
19. wa Dina Singh, wa Budhaï, wa Ichha Râm, wa Gajrâj Singh,
 wa Baij-
20. nâth, wa Puran, Nâik 1, Sipâhi 9; Golandâz Bahâdur Khan
21. Khalasi Pâncu wa Bulakmân ka Chaudhari Sôn *Garhi*
Bhopâri wa Ta
22. duâ, wa joki, tino Gaḍi me gadahâ kahar phirâ. Bhoswal ke thâ
23. na Lochan Singh ke sâth gârd thâ jemadâr I.H. 2., S. 30 târi-
24. k 18 larâi huâ || Dâke par larâi mârâ jot tin so log Dâka
25. ayâ thâ, so bhâgi ga (yâ) Sipâhi Tilok Singh *Ghâṭa Bhaiswal*.

¹ See Plate XXXI.

The following translation will show the differences between the two versions—

"The 2nd Battalion of the 21st Regiment, under Colonel Tetley Sâheb Bahâdur, made the Kiâri-ka-Ghât, by order of Lord Minto (and) by order of General Hewett Sâheb. They cut a road and built up the side with stones and with earth, making the Ghât for two kos in length. The sepoy worked of their own accord, and some workmen were got from Mirzapur. The Ghât, 2 kos in length, was made passable for 18-pounders. The Ghât was very lofty, and the sepoy made it of their own free-will with great labour towards Bardi. On the 18th day in the year 1811, in the month of April, the fort of Bhopâr was attacked; but batteries were not made, and two 6-pounders were taken up in front of the gate within 15 paces, and the sipahis went up to the wall, but the fort did not then surrender. In the evening the kiladâr fled. The walls of Fort Bhopârî were thrown down and levelled, the trees were cut and thrown outside, and the wells were destroyed. Killed—Naick Golâb Singh; Sepoys Jai Sukh, Pheru, Kâsi Din, Dina Singh, Budhai, Ichha Râm, Gajrâj Singh, Baijnâth and Puran; Naick 1, Sepoys 9, Artilleryman Bahâdur Khan, Khalâsi Pân-chu; Head Bullockman Son.

"The forts of Bhopârî, Tadu, and Joki, were all three levelled by ploughs drawn by asses.¹

"In Bhosâwal Thana with Lochan Singh there was a guard of 1 Jemadar, 2 Havildars, 2 Naicks, and 30 Sepoys. The Dâkas (*dakots*) were beaten off, and all the 300 who came there ran away. Killed Tilok Singh at Ghâta Bhaisâwal."

Both inscriptions conclude with a list of the names of the sepoy who were killed. Mention is made at the end of the defence of Bissore Ghât by a party of 35 sepoy against 300 banditti (in Hindi *Dâka*), in which one sepoy was killed.

As I was unable to find any account of this gallant exploit in our histories, I applied to Major Barr, the Political Agent, now in charge of the Rewa State, who kindly furnished me with the following note on the subject:—

"The story of the capture by assault of the Bobarry ghurri in Burdec is well known at Rewa. Bobarry, or Bhopârî, was a stronghold of the Chandels of Bardi, who in 1811 were not entirely under

¹ The position of *Joki* is shown in the map, 4 miles to the west of *Bhopari*.

The third fort, named Tadu, is most probably *Tendua*, to the south of the Son River, only 5 miles to the south-south-east of Bhopari. The Rani is still living there.

the Rewa Rāj. Their subjection was afterwards completed. Foujdār Singh was the Thākur of the clan, and lived in the fort, where he harboured an offender from the neighbouring British district of Mirzapur. Our demand for his surrender was refused, and a regiment of Native Infantry was therefore sent against the place. Foujdār Singh opened fire on the troops, and, in consequence, the fort was taken by assault after a very tough fight. Foujdār Singh seems to have escaped from the fort, as the Chauhāns afterwards gave him the village of Rāmdit, where his descendants, Siwai Lāl Singh and Hira Lāl Singh, are now living."

Haliya has lost most of its importance since the new road by the Katra Pass from Mirzapur to Rewa was completed. The old road to the south passed through Haliya *viâ* Dibhor and the Kerahi Pass. In the Gazetteer of the Mirzapur District, the following account of the erection of the inscription slabs is given by the compiler¹:—

"This monument was erected to commemorate a little expedition undertaken at the instance of Lallu Nāik, a well-known merchant of Mirzapur, to punish the marauders of Rewa, who used to plunder the rich convoys of merchandise which passed between Mirzapur and the Dakhin. This was before the construction of the Dakhin road and the Katra Pass, when the route lay *viâ* Hallia and the Kerāi and Dibhor Ghāts. This same Lallu Nāik constructed along the latter route a number of fine masonry tanks, which still, in their ruin, testify to the importance of the trade it once possessed. He was a powerful and wealthy man, and seems to have used his riches well. His house has decayed along with the city, and only the name remains. His grandson, Rāi Durga Prasād, died in comparative obscurity some years ago, and only a few female relatives remain to represent the family—a striking example, if one were needed, of the instability of oriental fortunes."

Lallu Nāik is the same person who is mentioned in my account of Dibhor as Lalla Mor. His name was Mor, and he was the Nāik or Chief of the Banjāra community of Mirzapur.

40.—DIBHOR.

In reply to my repeated enquiries about ancient buildings, I had often been told of a temple and large tank at Dibhor,

¹ North-Western Provinces Gazetteer, Art. Mirzapur, Vol. XIV, p. 194.

in a narrow valley of the Vindhya Hills, 12 miles to the south of Haliya and 43 miles to the south-south-west of Mirzapur. I accordingly visited the place, and was much disappointed to find a small temple of the modern Mirzâpur type, only 10 feet 9 inches square. The tank, however, is a very fine one, being 430 feet in length from north to south and 352 feet in breadth, with steps all round.

There is a long inscription of 22 lines of raised letters in the verandah of the temple, describing its erection by Srimân Nayak Mân Mor in the Samvat year 1881, on Wednesday, the 5th of the waxing moon of Phâlgun, or Wednesday, the 23rd February 1825 A.D. Mân Mor was the head of the Banjâra merchants of Mirzâpur. The date is also given in the year *Manmatha*, of the 60-year cycle of Jupiter, which corresponds with 1881 Samvat.

Dibhor itself is a small hamlet of a few houses belonging to the attendants of the temple. There is a pathway through a gap in the hills to the east, which joins the road running southward to Bardi on the Son River. The place is a regular *cul-de-sac*, and is extremely hot. I suppose that the vagrant instinct of the old Banjâra preferred a jungle site. No doubt he got the ground cheap; and from this vantage point he was able to supply Mirzâpur with both wood and charcoal. This trade still continues; but, as no young trees are ever planted, the jungle is gradually being cleared away, and both wood and charcoal are becoming dearer.

41.—ADESAR HILL.

Adesar is a lofty, flat-topped hill, some 700 or 800 feet in height. It stands on the left, or east, side of the road leading from Mirzâpur through Haliya and Dibhor into Rewa. It is said that there are several caves in the precipitous sandstone cliff near the top of the hill, but the lower slopes are so densely covered with jungle that none of the Kol population ever attempt to ascend it. It is believed, however, that one of the Bijaypur Rajas managed to reach one of the caves by means of ladders, and that he found an image of the goddess Devi.

The Adesar Hill seems to be similar in its formation to the hill forts of Kālanjar and Ajaygarh, the lower three-fourths being comparatively easy slopes of granite, thickly covered with jungle, and the upper fourth being a bare bluff of sandstone. The hill itself is an isolated offshoot of the Kaimur Range, immediately facing the most easterly peaks of the Vindhya Range on the opposite bank of the Adhwâ River. It is possible that there may have been some connection originally between the name of the river and that of the hill. The latter was probably named after the former, as the "hill of the Adhwâ River," which, after the adoption of the lingam stone by the Brahmans, would naturally have been changed to the Hill of Adesar.

42.—TURA.

Tura is the name of a perennial spring near the top of the hill, $2\frac{1}{2}$ miles to the north-east of Dibhor, and close to the Rewa village of South Lohâri. Close by the spring there is a rude stone cell that was formerly occupied by a *Sādhu*, or holy man. There are several fine trees near the cell, which are visible from Dibhor. The people call the cell a cave, but it is simply an irregularly shaped room built of rough stones. It is only 6 feet long by 4 feet broad, covered with a flat roof. Formerly there was a second room, 6 feet square on the east side, but it has now fallen in. The cave, or cell, is approached by a flight of steps on the east side. The spring flows out from beneath the cave, and its course is marked by a green track right down to the foot of the hill. There was no inscription in the cave.

43.—AHUGI.

Ahugi is an old village situated on the road between Haliya and Dibhor, at the point where it divides into two branches, one going direct to Dibhor and Bhopâri, and the other to the east of the Adesar Hill, to Bardi on the Son River. The houses of the village are scattered along both banks of the Adh, or Adhwâ River, which here flows in a deep channel with plenty of water. In the Atlas sheet, No. 89, of

the map of India the name is written once as Onji (apparently a mistake for Ougi), and again as Ahogee Kd., the abbreviation standing for the Persian word *Khurd*, or "Little."¹

Its favourable situation amongst fine old trees on the banks of a running stream must have led at an early date to the selection of Ahugi as a halting-ground for the Banjāra merchants, and afterwards to its occupation by the Brahmans as a pleasant site for their temples. There are, however, no temples now standing, but there are many ruins of stone temples both to the north and to the west of the village, besides numerous statues.

On a low mound to the west of the village, there are the ruins of a temple of Siva, of which the sill, one jamb, and the lintel of the entrance to the sanctum still remain on the ground. The lintel has a figure of Siva, four-armed, seated in the middle, with Brahma to his right and Vishnu to his left. There is a single pilaster, 5 feet 5 inches in height, and a standing statue of Surya, 3 feet 2 inches high, with Aruna on the pedestal, and five horses.

To the north of the village there are the remains of at least three different temples.

No. 1 is a small lingam temple facing the west, the interior being only 3 feet 9 inches by 3 feet, while the walls are formed of single upright slabs only $4\frac{1}{2}$ inches thick.

No. 2 is also a small lingam temple, but its entrance is to the east. The interior is only $4\frac{1}{2}$ feet by $4\frac{1}{4}$ feet, and the walls are formed of single slabs containing figures in panels. I recognized Ganesa, Bhainsāsuri Devi, and a four-armed female, who was probably intended for Durgā.

No. 3 is similar to the east, but it is much more broken.

On a long, flat slab of No. 2 temple I found a few letters, which were sufficient to show that the temples belonged to the mediæval period of about 1000 A.D.

¹ This is one of the absurdities which still disfigure the sheets of the Atlas of India. Thus, we find everywhere the scarcely known Persian terms *Kalān* and *Busurg*, for "great," and *Khurd*, for "small," instead of the universally known vernacular terms *barā* and *chota*, for "big and little."

44.—BARDI AND BHOPÂRI.

The fort of Bardi is situated on a rocky ridge to the south or right bank of the Gopat River, just above its junction with the Son. It is 213 feet long and 138 feet broad, with walls 4 feet thick at top, and octagonal towers at the four angles. The entrance gate on the north side is 10 feet 8 inches high, but only 3 feet 4 inches wide.

Bardi was captured by the Rewa Raja in Samvat 1876, or A.D. 1819. Before that time the Chandel chiefs who held the fort are said to have sacrificed a man, or some human being, every year to the goddess of Bardi.

Bhopâri is on the northern bank of the Son River, 10 miles to the west of Bardi, and the same distance south-south-west from Dibhor in a direct line. By the Kirâhi Pass the actual road distance is nearly double, and the descent from the top of the Kaimur Range towards the Son is both steep and bad.

45.—DURGA-KHO.

In a former report I have given a short notice of the inscriptions engraved on the face of the wall in the cave of Durga-kho, near Chunar. Durgâ kund is a perennial pool, or reservoir, situated about half a mile up a narrow ravine to the south-south-west of the Railway Station at Chunar. The mouth of the ravine is 1 mile from the station. On the north side of the ravine stands the temple of Kamâksha Devi, and just below it a small old temple without name. The ravine, or Jhima Nala, is spanned by a bridge which leads to a row of three *dâlâns*, or cloisters, formed by building against the face of the rock. Against the back wall there is a low platform or seat, 15 inches high and 16 inches broad, which was probably intended for the reception of statues.

Sculptured on the rock there are several figures of lions, horses, and elephants in outline. The face of the rock is 5 feet 3 inches high, above which the required height was obtained by building up. The beams and pillars of the present arcade are quite new. The whole back wall is literally covered with short inscriptions of all ages from the Gupta period down-

wards. Several of these I have already published; but, as my last visit was a more leisurely one, I was able to examine the writings with more attention. I have accordingly given in the accompanying plate¹ some of the previous ones over again, along with several new ones. I read them as follows:—

1. Vishnu.
2. Iṣāna Shatapasa (a mistake for Khatapasa).
3. Samavidaivikāntā.
4. Praṣṭa satadhinarchilaka Chandra.
5. Jaya Samudra.
6. Śrī Bharkarasta.
7. Bhagwaloka chirnattakudra.
8. Garga datta.
9. Prachanḍa Prithivekah.
10. Jambu Dāsa.
11. Yaṣalokacha.
12. Sujam bhara
13. Ujala.
14. Uja.
15. Heṇṇa ha . . va, or Meṇṇa ma . . toa
16. Bhārosaviniya.
17. Sri Bhoja Deva.
18. Sri Bhoja Devabhavira.
19. Bhadra Viloka.
20. Vashana Chilaka.
21. Dhāra kāhṇada.
22. Govinda.
23. Chhedī Bhagat kā dwari.

There is nothing amongst these records of any interest, except perhaps the juxtaposition of the names of Chandra and Samudra in Nos. 4 and 5. As they are in old Gupta characters, similar to those used upon the coins, it is possible that the names may refer to the two kings, Chandra Gupta and his son Samudra Gupta.

Most of the names appear to be those of the quarrymen or stone-cutters who occupied the rock shelter, which has been turned into a long arcade.

¹ See Plate XXXII.

46.—BHULLI.

In a former report I have described the remains at Bhulli, and I only visited it on the present occasion, because it happened to be in my way from Durgâ-kho. A few new objects were discovered, of which the only one of any interest was an old Muhammadan inscription of 5 double lines let into the lower wall of a masjid in Dakhin Tola. Unfortunately it is much injured, but I was able to read in the 2nd line—

Sultân bin Sultân Shah Muhârak Ânâ Kutbi.

and in the 5th line *Sabamiah* (or 700).

The inscription therefore belongs to the time of Kutb-ud-din Muhârak Khilji, who reigned from A.H. 716 to 720.

At the same place also there were three Hindu pillars and a bracket capital.

In the hill to the south there is a cave dargâh of *Makhdum Sâhib Chirâgh Hind*. It is whitewashed inside, and no inscriptions were visible. It is only a small room of 8 feet by 6 feet, and 6 feet high.

There is also a rock shelter called *Chilam marfa*, 15 feet by 12 feet, and $6\frac{1}{4}$ feet high. Near it there is a curious natural monolith, $5\frac{1}{2}$ feet in height, or with its base and pinnacle $9\frac{1}{2}$ feet. It is reckoned a curiosity, as the shaft is considerably curved.

47.—SEOPUR.

Seopur is $1\frac{1}{2}$ mile to the west of Kantî near Mirzapur. In former days it possessed a very large temple, of which the ruins now lie scattered about. The present temple of Râmeswar Nâth contains many large capitals, and there are numerous broken sculptures and other remains in the neighbourhood. The most striking thing is a life-size female figure seated on a throne with a child in her lap. The sculpture is 5 feet 2 inches high by 3 feet 8 inches broad, and 1 foot 8 inches deep. The face is gone, but a small figure of Buddha still remains on the top of the head. The right arm is broken at the elbow, and the left arm supports the child. The left knee is bent, and the leg is resting on the ground at

the foot of the throne. At the back of the figure there is a large tree with foliage and flowers. At the foot of the throne under the left leg there is a lion. I believe the statue to be a representation of Shashti, the goddess of Fecundity. There are 7 attendants on each side, 2 flying, and 5 standing. The statue is now called *Sangkaṭa Devi*, very probably for *Sangkaṭa-haraṇi Devi*, "the remover of misfortune."

48.—KÂLPI.

The old town of Kâlpi stands on a bluff cliff of clay overhanging the Jumna. The fort occupies the highest position, and commands the passage of the river. It has walls only on the three land sides, the river front being inaccessible. To the westward there are many old tombs and mosques, now in ruins. There are no inscriptions on any of them, and only a few names are now remembered. At the north-west corner there is a piece of ground called *Prabhâvati Mandi*, or the "splendid market-place," where old coins are found in the rainy season. It is said that *ata* (or flour) mixed with water cannot be cooked on this spot, and that dead bodies cannot be burned there.

Kâlpi was the birth-place of Mohes-dâs, a poor Brahman, who afterwards became famous as Raja Bir-bar, or Bir-bal, the companion of Akbar.

Kâlpi also was the residence of the holy Shekh Burhân, who died at 100 years of age in A.H. 970, or A.D. 1562-63. He is said to have lived on milk and sweetmeats only. He was buried in his cell, the site of which is not now known.

According to Ferishia the fort of Kâlpi was built by Vasu Deva, Raja of Kanauj, the contemporary of Bahrâm Gor. But the people of the place know nothing of this doubtful chief, and attribute the building of Kâlpi to an ancient Raja, named Kalib Deva. The earliest mention that I have found of Kâlpi is the notice of its capture by Kutb-ud-din Aibeq in A.H. 593 = A.D. 1196. It was afterwards joined to Mahoba and placed under an imperial governor from Delhi. During the troubled times which followed the invasion of Timur, Kâlpi and Mahoba became independent under Muhammad Khan, the son of Malikzâda Firoz, who took the title of king. In

A.H. 937 Kālpi was attacked by Ibrāhim Shah of Jaunpur, who retired on the advance of Mubārak Shah of Delhi, to whom the governor, Kadir Khan, had made urgent appeals for aid. In the following year, A.H. 938 or A.D. 1434-35, during the war between Delhi and Jaunpur, Kālpi fell into the hands of Hushang Shah of Malwa. Before A.H. 847 or A.D. 1443 the new governor of Kālpi, named Nasir Khan, the son of Kādir Khan, still acknowledged fealty to Malwa. But the place was shortly afterwards attacked by Mahmud of Jaunpur, who sacked the town, and compelled Nasir Khan to fly to Chanderi.

After the conquest of Jaunpur, Kālpi fell into the hands of Bahlol Lodi of Delhi, who appointed Kutb Khan Lodi to be the governor. During the reign of Sikandar Lodi, his son Jalāl Khan became ruler of the eastern provinces, including Kālpi and Jaunpur. He was afterwards dispossessed by his brother Ibrahim Lodi, who put him to death.

Kālpi was successively occupied by Bāber and his son Humāyun, by Sher Shah and his relatives, Ibrāhim Sur, Sikandar Sur, and Muhammad Adil; and, lastly, by Akbar, by whom it was permanently attached to the Mughal empire of Delhi. Here he had a mint for copper coins.

The principal remains at Kālpi are the tombs of Madār Sāhib, of Ghafūr Zanjāni, of Chol Bibi (a square enclosed by trellises), of Bahādur Shāhid, and the great enclosure called Chaurāsi Gumbaz, or "eighty-four domes." There is a large statue of a lion at another tomb, which is assigned to a barber. The lion is said to have been turned into stone when struck by the holy saint Madār Sāhib.

The only remarkable building at Kālpi is the Chaurāsi Gumbaz. It is said to be the tomb of Lodi Shāh Bādshāh, and some people even assign to it Sikandar Lodi. But we know that he died near Agra, and that his body was carried to Delhi to be buried. The Chaurāsi Gumbaz is built of blocks of kankar laid in lime mortar. All the ornamentation is in stucco, with flowered borders and bands. Altogether, the style corresponds very closely with that of the Lodi period, and I think, therefore, that the people are right in their attribution of it to a Lodi prince.

The building itself is only remarkable for its size, being 125 feet square outside, and about 80 feet high—seven narrow arched openings, divided by thick square piers. The whole building is divided, something like a chess-board, into eight lines of piers, and seven lines of open spaces, thus forming 64 piers, all connected by twice 49 arches, with the 49 intervening spaces covered by flat roofs. In the middle there are four piers omitted, and the square space thus obtained is covered by a lofty dome which rises about 60 feet above the flat-terraced roof of the main body of the building. There are four small domes covering the four corner intersections, and there is a small domed turret over each of the sloping towers at the outer corners. But the appearance of the great central dome rising for about 40 feet or more cylindrical neck above the terraced roof is extremely bold and imposing. The meagre appearance of this domed tower might easily have been softened by the addition of a second storey rising from the next inner line of piers to within a few feet of the spring of the dome.

The piers vary from 6 feet 2 inches to 8 feet 8 inches square, and the arches from $6\frac{1}{2}$ feet to $9\frac{1}{2}$ feet span. Altogether the building is very solid, and is likely to last for a long time. No one could explain why the tomb was called Chaurāsi Gumbaz, or “the eighty-four domes.” There are only 40 intersecting spaces in the roof, after deducting intersections in the middle which are covered by the main dome. These, with the four corner turrets and the great dome, make only 45 possible domes, so that the name of *Chaurāsi Gumbaz* is decidedly incorrect. The original name may have been *Chālisi Gumbaz*, or the “forty domes,” which would have been strictly correct, as well as in accordance with a favourite Hindu number.

The present town of Kālpi occupies a site to the south-east of the original old town and the great mass of ruined tombs and masjids.

49.—SULTĀNPUR.

I have given a description of Sultānpur, in the Jālandhar Doāb, in my report of my last tour in the Panjāb (see

Archæological Survey, Vol. XIV, p. 55), where I have shown that it corresponds in position with the Tamasa-vana monastery of Hwen Thsang. The people of the place, however, say that it was named after Sultân Khân Pathân, a brother of Haibat Khân, in the time of the Pathân kings. There was a Haibat Khân in the time of Sikandar Lodi, who gave his name to the old town of Patti, to the west of the Biâs River, nearly opposite to Sultânpur. Since my visit a short inscription has been found outside the serai, dated in A.H. 970 (*Sabain-wa-tisamiah*), which records the building of a mosque by Abdullah, son of Shamsuddin, son of Jamâl Ansâri, the humblest of mankind.

50.—CHINI.

I have described the lofty mound of Chini in my last Panjâb Report, Volume XIV, page 53, of the Archæological Survey. I then identified it with the *Chinapati* of the pilgrim Hwen Thsang, who notes that the Chinese hostages were kept there by Kanishka during the winter months.

During the present year the mound has been dug into by a contractor for bricks. During the excavations a very old statue of Vishnu was brought to light. The contractor claimed it as part of his property, but the villagers put in a counter-claim for the figure as that of their village deity. I have hitherto failed in getting a photograph of this interesting piece of sculpture.

51.—CHAMBA.

The small Hindu state of Chamba is situated in the alpine Panjâb, and embraces all the country lying on the River Râvi and its tributaries, from their sources to the point where their collected waters pierce the outer range of hills. About one-third of the territory forming the Chamba District of Lâhul lies on the Chenâb River and its tributary the Bhâga. But this is a poor country with a very small population.

The capital, named Champapuri, or Chamba, stands on the northern bank of the river, in the south-western corner of the territory, at an elevation of rather more than 3,000 feet above the sea. On all sides it is surrounded by lofty ranges

of mountains, rising to 16,000 feet in height on the south, towards Kangra, and 18,000 and 20,000 feet in the north-east, towards the valley of the Upper Chenāb. On the north-west side the mountain range is less lofty, although several of the peaks reach 16,000 feet.

The original capital of the country was at Barmāwar, on the Budhil River, about 60 miles nearly due east from the town of Chamba by the road, but only 32 miles distant in a direct line. Barmāwar is upwards of 7,000 feet above the sea, and possesses several old temples, both of stone and wood. These I have already described in a previous volume.¹ All the earlier Rajas bore the name of Varmma, and the inscriptions on the pedestals of the statues give the names of Meru Varmma, and his three predecessors with the same title.

The change of capital from Barmāwar to Chamba is assigned to Śāla Varmma, who was defeated and killed by Ananta Varmma of Kashmir in A.D. 1060. In the inscriptions this Chamba King is called Śālivāhana, of which Śāla is only a common contraction. He built the famous temple of Lakshmi Narāyan, which is by far the most popular of all the temples now standing at Chamba. His son was Soma Varmma Deva, of whom there is a copper-plate grant now existing at Chamba. This document is attested both by his own signature and by that of his son Asata Deva. Kalasa, the son of Ananta of Kashmir, married Asata's sister, named Vappikā, who became the mother of Harsha Deva, the next king of Kashmir.

There are four inscriptions now existing at Chamba, of which three are engraved on copper-plates, and one on a stone slab.

The oldest is that mentioned above. The copper-plate is 17 $\frac{1}{4}$ inches long and 12 inches broad. There are 29 lines written direct, with 1 line to right, and another at top upside down, and a third on the left hand, or altogether 32 lines. There are two dates noted in it, namely, the first year, *Samvat-sare prathame*, on Friday of the 3rd of the waxing moon, Vaisākh. The second date is Samvat 11 Bhādrapada, Sudi

¹ Archaeological Survey, Vol. XIV, p. 109.

13th, on Some, or Monday. These dates correspond with the Christian years A.D. 1060 and 1070. In the former year Raja Sâla was killed by Ananta, and was succeeded by his son Soma Varmma Deva. In the latter year Raja Soma was still reigning, but his son Asata had then grown up, and the grant was accordingly attested by him as heir apparent, as well as by his father. Raja Kalasa, of Kashmir, married Asata's sister.

The second inscription is also on copper. It has 17 lines quite perfect, but I can find no date. The Raja's name is Bhata Varmma, son of Mânikyā Varmma Deva. Both names are found in the list of the Rajas of Chamba; the latter being spelt Bodha.

The third inscription is engraved on a stone slab, which is now lying under a very large Toon tree, on the side wall of a Chabutara, or platform, besides a tank. It consists of 10 lines, but is only remarkable for the precise way in which its date is recorded. The words are Śrī Mân nripati Vikramāditya Samvatsara 1717, Śrī Sâlivahara Saka 1583, Śrī Sâstri Samvatsare 37, that is—

in the Vikrama Samvat year	1717 = A.D. 1660
in the Sâlivâhana Saka „	1583 = „ 1661
in the Sâstri Samvatsara „	37 = „ [16]61

Here we meet with the Lok-Kâl, or Sapt Rishi-Kâl, under the name of Sâstri Samvatsara, or *Sâstri era*. The week-day *Budhavâsare*, or Wednesday, shows that the year corresponded with A.D. 1661. The era of the seven Rishis might appropriately be called the holy Samvat, or divine era.

The fourth inscription is engraved in 23 lines on a copper-plate. It is quite modern; but, as it gives the Sâstri Samvatsara, it is of some value. It bears two different dates as follows:—

line 7, Vikramāditya Samvat	1917, Sâstri Samvatsare	. 36
line 8, do. do.	1915, do.	. 34
lines 18-19, do. do.	1917, do.	. 36

Here the Vikramāditya dates are correct, as they give A.D. 1858 and 1860; while the Sâstri Samvat gives the same, *viz.*,

$1824+34 = 1858$, and $1824+36 = 1860$ A.D. The seal also bears the two dates of "Samvat 34 and 36," but without the corresponding years of the Vikramāditya, I have given a full account of the Sapt Rishi-Kāl or Lok-Kāl in my "Book of Indian Eras."

PART II.

REPORT OF A TOUR IN REWA, BUNDELKHAND,
MALWA, AND GWALIOR,

IN

1884-85.

REPORT OF A TOUR IN REWA, BUNDELKHAND, MALWA, AND GWALIOR, IN 1884-85.

PART II.

I.—KEVATI-KUND, OR KEONTI.

The falls of the Tamasa, or Tons River, have long been famous. The river rises in the small state of Mahiyar, 50 miles to the south-west of Rewa, and, after a course of 130 miles, measured in a direct line, falls into the Ganges, between Allahabad and Benares. None of the falls are on the main stream, but on its larger tributaries just above their junction with it. The following are the names of the principal falls:—

Fall.	Stream.	Height	Distance from Rewa.
		Feet.	
1 Piāwan . .	Piāwan Nala . .	115	23 miles N.
2 Damdo . .	Damdo Nala . .	?	24 „ N.
3 Pūrwa . .	Small stream . .	240	17 „ N.
4 Chachai . .	Behar Nadi . .	368	20 „ N. N.-E.
5 Kevati . .	Mahā Nadi . .	331	21 „ N.-E.
6 Bilohi . .	Odda Nadi . .	464	36 „ E. N.-E.

The *Piāwan fall* has been described by both Mr. Garrick and myself. It possesses an inscription of Gānggeya Deva, the Kalachuri Raja of Chedi or Dāhal, dated in the Chedi Samvat 789, or A.D. 1030. The inscription is carved on the Argha of a lingam.

The *Kevati-Kund* is the most famous of all the Tons waterfalls, partly perhaps for its easier accessibility, but

chiefly, I believe, for the romantic beauty of its scenery. The Mahâ Nadi River pours over the sheer rock in one unbroken fall of 331 feet into a deep blue pool, and continues its course for some miles between the beetling cliffs of the narrow ravine. On the east the cliff is crowned by a fort and some small temples, below which, at 130 paces, there are two long ledges, protected by the overhanging rocks, which form the shelters now known as caves. The larger one is 200 feet long and 43 feet broad, but only 3 feet in height at the back, and it appears to have been partly quarried out. The other shelter, now known as the Mahâdeva cave, is partly artificial, being closed on the outer side by built walls, 7 feet in height. It is $36\frac{1}{2}$ feet long by 33 feet broad, and 7 feet high, diminishing to 3 feet at the back. Inside there are a few lingams, from which it derives its name of the Mahâdeva cave. On the rock outside there are two Buddhist stûpas carved in outline. These prove the Buddhist origin of the cave, which is confirmed by the following inscription on the roof of the cave, carved in letters of the 2nd century B.C. The inscription was found by Mr. Macaulay Markham, and the following reading of it has been published by Dr. Höernle:—

Hariti putenam Sonakena kâritâ pukharinî.

"The pool (cave) caused to be made by Saunaka, the son of Hariti."¹

The cave is rather difficult of access, but one is well repaid for the trouble by the fine view of the waterfall and of the blue pool below which the cave commands.

In the open rock-shelter there are numerous figures of animals sketched in red ochre, such as antelopes, bāra-singhas, and elephants, with floriated letters in white. One man told me that the proper name of the pool was *Dhar-mâtma*, but the place is named in all the inscriptions as *Kevati-sthân*, and is more generally known as *Keönti-Kund*.

One mile from the waterfall, on the high ground near the village of Keönti, there is a row of four Sati pillars called *Panch Bhaya*, or "the Five Brothers." Only four are now

¹ Indian Antiquary, Vol. IX, p. 121.

standing ; but there is a gap showing where the missing pillar once stood. Two other pillars, standing a little way off, are called *Nand-bhanu*. All bear representations of armed soldiers in the act of fighting, with inscriptions beneath. The northern pillar is dated in Samvat 1390, but all the others are seven years later, and bear the same date of Samvat 1397, on Monday, the 4th day of the waxing moon of Māgha (Monday, the 22nd January, A.D. 1341). The people say that these were five brothers who all fell on the same day. From the existing inscriptions it is certain that three of them fell on the same day ; but one of them fell upwards of seven years earlier, on Saturday the 31st July A.D. 1333 ; or, if the Samvat date be read as 1340, he must have fallen fifty-seven years earlier.

In the three later inscriptions, dated in Samvat 1397, there is mention of Mahārāja Hamira Deva, of Luka-sthān, and of Mahārājādhirāja Devaka, of Kathauli-sthān. I conclude, therefore, in spite of their royal titles, that these two Rajas were only the petty chiefs of the two neighbouring towns of Luka-sthān and Kathauli-sthān, which still exist ; and that the fight commemorated by the pillars was only a quarrel about their contiguous boundaries. The men who fell are all designated as Raus, or zamindars. Both Luka and Kathauli will be found in the accompanying map, Plate I. Of Baorigrām, which is mentioned in all these inscriptions, I could not get any information. Kathauli is a large village on the tableland near the Mamani pass, 30 miles to the west of north from Rewa. Lûk is a large village on the right bank of the Tons River, near where it leaves the hills, 27 miles to the east of north from Rewa. The distance between the two places is not more than 12 miles in a direct line.

2.—REWA, OR BAGHELKHAND.

The city of Rewa, the present capital of Bāghelkhand, is of comparatively modern date, as it was founded by Raja Vikramāditya Baghel, after the fort of Bandhogarh had fallen into the hands of the Muhammadans during the reign of Akbar, about 1595 A.D. The only objects of any interest about the city are a very fine Toran gateway, and some

sculptures, all of which were brought very recently from the ruins of the old city of Gûrgi Masâun, 12 miles to the east of Rewa.

The Toran gateway has been set up in front of the palace. A view of it has been given by my assistant Mr. Garrick.¹ The clear span between the bases of the two pillars is 10½ feet, and between the shafts 1 foot more. It is one of the richest and largest temple gateways that I have seen. Its original position at Gûrgi is still pointed out by the people.

Of the four sculptures which were brought from Gûrgi, one is undoubtedly Buddhist, and the others Brahmanical.

I.—The Buddhist sculpture is a seated figure of Padma-pâni, half life-size. One hand rests on the knee, which is raised up, while the other, holding a lotus flower, lies in the lap. On the back is engraved the Buddhist creed in three lines of well-cut characters of about the 10th century.

Ye dharma hetu prabhavâ hetun teshân Tathâgato
hyavâdatteshân cha yo nirodha evam vâdi
Mahâsramanah.

II.—A standing figure of Vishnu.

III.—A seated figure of a four-armed goddess, on the pedestal of which is engraved her name in an inscription of two lines.

Sri Hasti-vâhini Devih||
Sâhâraṇa pâda pankaja—

The statue derives its name from a small figure of an elephant, *hasti*, which forms the end of the pedestal.²

IV.—A bas-relief, 4 feet high, Siva and Pârvati, seated at top, his foot resting on a bull, and her foot on a lion. In the middle are two male figures seated and attended by women. Below, there are two tall swordsmen with shields, fighting two small men, armed with bows and arrows. I have a suspicion that this may be a Sati monument.³ But I cannot even guess why the two swordsmen on the left are

¹ Archaeological Survey of India, Vol. XIX, p. 80, and Plate XIX.

² See Plate XXXVI, for a picture of this Goddess from a photograph.

³ See Plate XXXVII, for this battle-scene, taken from a photograph.

represented as giants of just twice the height of all the other figures. It is possible that they may be intended for fabulous monsters, as one of them has been shot through the body with an arrow, and I think also through the left thigh. Under this view the scene might represent the fight between Râma-chandra and the giant Kûmbhakarna.

The Rewa Durbar is in possession of several copper-plate inscriptions, of which only four are old. These I will refer to as A, B, C, and D.

A is engraved on a single plate, and is dated in Samvat 926, on Thursday, in Bhâdrapada, the 4th of the waxing moon, or A.D. 1175, as I take the Samvat date to be recorded in the Kalachuri era of Chedi, which starts from A.D. 249-50. The week-day, however, according to this reckoning does not agree with the day stated in the inscription. The characters of the inscription are of much too late a date for the Vikrama Samvat 926, or A.D. 869, and, as the Raja Jaya Sinha Deva Kalachuri is known to have been living in A.D. 1177, when the Rewa territory actually belonged to his family, I have no hesitation in assigning the inscription to him. But there is another difficulty in this record which begins with the name and titles of—

Parama bhaṭāraka Mahārājādhirāja Parameswara
Sri Vāma Deva—

followed by the term *pādānudhyāto*, or “bowing to whose feet,” after which we have the name and titles of the reigning king as follows:—

Parama bhaṭāraka Mahārājādhirāja parameswara parama
Māheswara Trikalīṅgādhipati nij bhujo parjitāswapati,
gajapati, narapati Rajatrayādhipati.
Sri Maj Jaya Sinha Deva vijayarājye.॥

Now, we know that Jaya Sinha Deva was the son of Gaya Karna Deva, and the younger brother of Nara Sinha Deva. Who then was Vāma Deva? In the Bharhut inscription the very same titles are given to Nara Sinha Deva, who is also said to have bowed to the feet (*pādānudhyata*) of Vāma Deva. Either Vāma must be taken as another name of Gaya Karna, or as that of the original founder of the family. At first I

thought that Vāma might have been intended for Siva himself, and this would seem to be the truth, as in the next inscription, B., Jaya Sinha's son Vijaya also bows down to the feet of Vāma Deva.

The inscription goes on to say that during the time of Kīrtti Varmma the Kaurava Mahāranak of Kakareḍi nagari, the village of Ahir-pâr-grama was given to two Brahmans on the anniversary of the death ceremony of Rānak Balarāja at Pindârchansthan.

Kakareḍi, or Kakareṛi, is a large place on the table-land at the head of the principal Pass, the Mamani Ghât, leading to the west towards Bānda and Kālanjar and Mahoba.

B.—This inscription is engraved on one plate. It records a grant made in the Samvat year 1253, on Friday, the 7th of the waxing moon of Mārgasirsha, during the reign of Vijaya Deva. The donor is Salakhana Varmma Deva, the grandson of Kīrtti Varmma Deva, of Inscription A, and the chief of Kakareḍi. The date is twenty-one years later than A, taking the Samvat to be that of Vikramāditya, which agrees with the relationship of Salakhana Varmma as grandson of Kīrtti Varmma of Kakareḍi, as well as with that of Vijaya Deva as son of Jaya Sinha Deva, the paramount lord of that country.

By my calculation the week day comes out Thursday, instead of Friday, as stated on the plate.

The inscription records the gift of the village of Nauagrama, in the district of Kakareḍi-sthāna to certain Brahmans of the Kausika gotra by name, and ends with the usual denouncement of the resusers of land, who will suffer for 60,000 years in hell.

C.—This inscription is engraved on two sheets of copper with a short postscript on the back of the second sheet, giving the names of the donees, with the measure of the land which each of them received.

The grant of the village of Rehi is dated in Kārtika of the Samvat year 1297, or A.D. 1240, and was made by Kumāra Pāla Deva, the Mahāranak of Kakareḍi, to six Brahmans of the Kaundinya gotra, named Sānge, Suhar, Mahādatta, Pem Singh, Soma Biro, and Sāmanta, of whom the

first four received 3 biswas each, and the last two only one biswa each.

The date is given in words, as well as in figures, as follows :—

Saptanavatyâdhike dwâdaśa śata Samvatsare, Ankepi 1297.

A great part of the record is taken up with the praises of the city (*Nagari*) of Kakareḍi, which is said to possess many high temples and white-washed houses, with tanks, wells, and baolis, hills and caves, gardens and big trees, learned men and beautiful women ;—such is Kakareḍi, the city of the Kaurava race !

The donor is Kumâra Pala Deva, the Mahârânak or chief of Kakareḍi, under the paramount sovereign Trailokya Varmma Deva, whose titles are exactly the same as those of Jaya Sinha Deva and Vijaya Deva, in the two preceding inscriptions A and B. As he is also called a worshipper (pâdâ-nudhyâta) of Vâma Deva, it is certain that the god Siva must be intended, and not one of his ancestors.

But the change in the name of the king is remarkable, as there can be little doubt that Trailokya Varmma Deva is the Chandel prince of Kâlanjar, who was actually reigning at the date of the inscription. He succeeded his father Paramârddi Deva in A.D. 1203, when the Muhammadans captured Kâlanjar. The only other inscription of Trailokya that I have got was found in the fort of Ajaygarh. It is dated in Samvat 1269, or A.D. 1212, when it is probable that Ajaygarh was still his capital. But, as I have shown in my notice of the Chandel kingdom, he was in full possession of Kâlanjar in A.H. 631, or A.D. 1233, when the troops of Iltitish, king of Delhi, invaded that territory for the sake of plunder. His father Paramârddi had lost Mahoba to Prithirâj ; but from the present inscription it would appear that the power of the Chandel princes was but little broken when they extended their dominion to the east, by the conquest of the Rewa territory, which they must have wrested from the Kalachuris during the reign of Trailokya himself. The Chandelas still hold possessions in the eastern portion of the Rewa territory, and they are even more numerous in the

districts of Mirzapur and Jaunpur to the north, to which they must have retired before the increasing power of the Bāghels.

D.—This inscription is engraved on three smaller plates. The paramount sovereign is named Trailokya Malla, but, as the Samvat date of 1298 is only one year later than that of the last inscription, C., there can be little doubt that the two records refer to the same king. The reigning chief of Kakareḍi is here named Prithiraja, the son of Salakshana Varmma, and therefore a brother of Kumāra Pala Deva of the previous inscription, C.

The grant gives a similar glowing description of the city of Kakareḍi-nagari as in C., with the genealogy of the donor from the Kaurava chief Chāhila downwards. The gift of the village of Barbarā to certain Brahmans of the Śāndilya gotra was made in the month of Māgha in Samvat 1298, or A.D. 1241. The names of the donees are the same as in C., with the exception of the last, namely—

Rāūt Sānge . . .	2 biswas of land.
Rāūt Suhar . . .	4 do. do.
Rāūt Mahādatta . . .	3 do. do.
Rāūt Sāmant . . .	8 do. do.
Rāūt Kirtu Yuvarāj Singh	3 do. do.

TOTAL . . . 20 biswas.

The family of the Mahārānaks, or chiefs of Kakareḍi, as derived from these four inscriptions, is as follows, with their approximate dates:—

- A. D. 1050.—Chāhila.
 „ 1075.—Durjaya. *
 „ 1100.—Bhoja Varmma Deva.
 „ 1125.—Jaya Varmma Deva.
 „ 1150.—Vatsa Raja, or Balarāja Deva.
 „ 1175.—Kirtti Varmma } brothers.
 „ 1196.—Salakhana }
 „ 1220.—Harirāja (1240) } Sons of Salakhana.
 Nāhara Varmma }
 „ 1241.—Prithvi Raja Deva }

3.—GURGI-MASÂUN.

The ruins of Gûrgi-Masaun are situated 12 miles to the east of Rewa, on an open plain, near the sources of the Mahâ Nadi River, which, at 20 miles to the north, forms the famous waterfall of Kevati-Kund.

The remains consist of a large fort called Rehuta, to the east of the village of Silchat, and a large mound 1 mile to the south-west, covered with ruined temples. The actual villages of Gûrgi and Masâun lie 1 mile to the west. On the south-east, upwards of 1 mile distant, flows the Bichia Nadi, the principal feeder of the Bihar River, which forms the great waterfall of Chachai, 368 feet in height. To the south-west of the mound of ruined temples, and more than a mile distant, there is a solitary hill called Goragad, crowned with a modern temple.¹ To the south and east, about 8 miles, the view is bounded by the Kaimur range of hills, which divides the valley of the Tons from that of the Son. In every direction the eye falls upon numerous large tanks, which form a characteristic feature of this part of Rewa. The country is generally well wooded and well cultivated.

All old Hindu cities are remarkable for the number of their *Pân-bâris*, or "Pân gardens." Mahâsthân, the old capital of North Bengal, is literally surrounded by them, and many still exist around Kanauj. The Pân gardens of Gûrgi are famous, and the cities of Allahabad and Benares are said to be chiefly supplied from this source. In fact, the shortest and most frequented route leading from Gûrgi to the north, past the Kevati-Kûnd, descends from the Vindhya Hills by the Panyâri or Panwâri Pass, on which I met numerous bullocks, laden with packs of Pân leaves, going to the Bargarh station of the Allahabad and Jabalpur Railway.

The fort of Rehuta is unanimously ascribed to Raja Karan Dahariya, who is supposed to have been a Bhar chief. But his very title of Dahariya shows that he must have been the famous Karna Deva, the Kalachuri Raja of Dâhal or

¹ See Plate XXXV, for a map of these ruins.

Chedi. His father, Gāṅgeya Deva, is known to have possessed the Rewa territory, as we have an inscription bearing his name, carved on the Argha at the foot of the Piāwan waterfall, in which he is called the Dahaliya Raja. Another inscription of Nara Sinha Deva still exists in the Alha Ghât, between the Piāwan and Kevati-Kûnd waterfalls, in which the Kalachuri Raja also takes the title of Dahaliya. It is certain, therefore, that the territory of Rewa belonged to the Kalachuri Raja Karna Deva of Dâhal, and to him we must assign the building of the fort of Rehuta. His reign extended from A.D. 1040 to 1080. Some of the temples may, perhaps, be older, as the few inscriptions which I obtained agree better in their characters with those of the earlier Kalachuri Rajas Lakshmana and Kokalla.

The fort of Rehuta, or Rehunra, or Gûrgi-Masâun, as it is usually called, is irregular in shape, as the east and west sides slope inwards from the south to the north, thus shortening the northern face by about 1,400 feet. The four faces are irregular; the east and west faces being much intended and the north and south faces being of unequal length. I make the measurements as follows:—

	Feet.
North face	1,980
South „	3,432
West „	3,168
East „	3,234
	<hr/>
TOTAL	11,814 circuit.
	<hr/>

It is difficult to measure the faces exactly, but the circuit may be taken at 12,000 feet, or $2\frac{1}{2}$ miles. According to Mr. Garrick's measurement the circuit is 452 feet greater than I make it.

The outline of the fort is well defined by the stone walls, which are still standing on all sides. They are between 10 and 11 feet thick, and were probably 20 feet in height, as they still reach 15 feet in many places. The remains of the ditch are still quite distinct, from 40 to 50 feet broad and 5 feet deep.

There are no towers or bastions now visible, although I thought that I could trace the basement of a circular tower at the south-west corner.

In the interior there are numerous stone wells, all square in form, and many mounds of stone ruins, from which the wrought stones have been removed. Every mound shows numerous broken statues, all belonging to the Brahmanical faith, excepting one near the south gate. Here there are many broken Jain statues, both seated and standing, and all naked. There is a curious two-faced lion. The head is turned at right angles to the body, so that on both sides the spectator has the lion facing him.

Everywhere the temples have been thrown down, and the cut stones removed, leaving masses of shapeless rough stones forming irregular mounds, more or less covered with jungle. There are two clumps of bamboo jungle, both of which are filled with stones and broken statues.

All sorts of absurd tales are told about Raja Karna Dahariya. It is said that he took no land rent, but only some of the iron tools of the cultivators, which he turned into gold. When the *Pādshah* heard this, he invaded the country, when the Raja entered the ground and disappeared.

There is a still more absurd story about the great number of the inhabitants of Gūrgi. A camel, laden with vermilion, on entering the town was stopped by the women, every one of whom dipped her finger in the pigment to make a red streak down the parting of her hair. The Raja fined each of them one cowrie, and the number of cowries is said to have been equal to one year's revenue. As 5,000 cowries are only equal to one rupee, the revenue must have been very small.

The great mound of temple ruins, called *Gurgaj*, is about 1,200 feet square, and from 10 to 15 feet in height. It is a mere confused mass of rough stones, the whole of the squared stones having been carried away to Rewa within the last twenty years by the Dewān of the late Mahārājā. The sites of two large temples are now marked by deep pits and the overturned colossal figures which were once enshrined inside.

On the east side of the mound there is a colossal figure of a four-armed goddess, 9 feet 3 inches high and 4 feet 7 inches broad, seated on a lion. The right leg hangs down, but the left leg is drawn up and rests on the lion. This figure is called Devi, and is, no doubt, intended for the goddess Durgâ, whose *vâhan* is a lion.

On the north-west of the mound there is a still larger sculpture of Hara-Gauri, or Siva and Pârvatî, lying on its face above a deep hole. The slab is 12 feet 8 inches long by 5 feet 3 inches broad. At the foot is the bull Nandi. The figures are partly cut clear. The great Toran gateway in front of the Raja's palace at Rewa is said to have stood in front of this temple facing the east. If the temples which occupied this mound bore any proportion to the size of the colossal figures which they enshrined, they must have been of considerable size,—certainly not less than 100 feet in height. I could not ascertain whether the temples had *completely* fallen down when the stones were removed, but all the people agreed that they were in ruins. No traces of any inscription, in fact not even a single letter, could be found on this site.

Inside the fort, and under several trees to the north of the village of Silchat, there are numerous statues of all sizes, more or less broken. There are only a few Buddhist figures, but the Jain and Brahmanical figures are numerous. The following list gives the names of such as I could recognize :—

1. Colossal figure of Hanumân.
2. Statue broken at waist, horse below : on its pedestal is inscribed—
*"Sri Lakshmi Devi Bhatâraka
 Bhagîni pranamati,"*
"Sri Lakshmi Devi, the king's sister offers adoration."
3. Standing Vishnu, 3 feet high, with Brahmâ and Siva to right and left, small.
4. Bhainsâsuri Devi, half-life size,
5. Four-armed female, bull on pedestal.
6. Broken 8-armed female, half-life size.
7. Kâli Devi, skeleton goddess.
8. Three-headed male with four arms, and canopied by a three-snake-hood.

9. Eight-armed figure of Ganesa.
10. Slab, with three snakes, middle one very stout.

There are many other figures, but none of any interest, as there are no inscriptions on them, and they are all more or less broken. The Jaina figures are numerous in the fort, but they are of the usual well-known types, and are not inscribed. The whole of the Gûrji sculptures are of the same style and age as the two specimens in Plates XXXVI and XXXVII, which were brought from Gûrji to Rewa. From the alphabetical characters of their inscriptions they must belong to the period of Kalachuri rule in the 10th and 11th centuries.

Of the early history of Rewa prior to the occupation of the Bâghels, who still hold the country, nothing whatever is known. Several existing inscriptions, however, show that it must have formed part of the dominions of the Kalachuri kings of Chedi for at least two centuries before the conquest of the Bâghelas. I have already mentioned the inscriptions of Gânggeya Deva and Narasinha Deva at the Piâwan waterfall and the Alha Ghât; but there is a third inscription, and a very long one, in a very fine temple at Chandrehe, close to the Son River, and only 20 miles to the south-east of Rewa, which must certainly have been set up by the Kalachuris of Chedi, as it is dated in Samvat 724. As the characters are those of the 10th century, the date must be recorded in the Chedi era, or $A.D. 249 + 724 = A.D. 973$, and the inscription must, therefore, belong to the time of Lakshmana, the founder of the Lakshman Sâgar at Bilhari, who reigned from about 950 to 975, or somewhat later.

But it seems highly probable that the Kalachuris must have occupied the country of Rewa for several centuries prior to A.D. 950, as the Kalachuri princes of Southern India claim to have conquered Kâlanjara before they occupied Dahala or Chedi. The tradition is thus given by Mr. Rice from a stone inscription at Harihara, dated about 1160¹ :—

“A Brahmani girl (ilâmara putri), having paid worship to Siva, seated on a hide, in order to obtain the fulfilment of her desires,

¹ Mysore Inscriptions, by Lewis Rice, p. 64.

she had a dream, in which Siva himself embraced her, and she conceived a portion of his glory. Having thus conceived, when nine months were accomplished, it happened that she bore a son named Krishna, possessed of great beauty, of surpassing courage, bearing all the marks of fortune, famous in all learning.

"He slew in Kālanjara an evil spirit of a king, who was a cannibal and followed the occupation of a barber, thus obtaining great fame among all people. Placing him between the teeth of Yama, this king Krishna, by the might of his arms, took possession of the government of his kingdom, and reducing the nine-lakh (*country of*) *Dahala mandala* to obedience to his word, ruled in peace, an ornament of the Kalachuri kula."

According to this account the progenitor of the race, named Krishna, captured Kālanjara before he occupied Dahala. He must, therefore, have crossed from Rewa; and, as the initial point of the Chedi, or Kalachuri era, is A.D. 249, it seems probable that this year may, perhaps, mark the date of the capture of Kālanjara. In this case the Kalachuris must have held the territory of Rewa for nearly one thousand years.

The old name of the country, as given by the Muhammadan historians, is *Bhath*, or *Bhath-ghora*, and sometimes *Pattah Ghorā-ghât*. Blochmann calls it *Baudah* Rewa. In the *Maâsir* it is spelt *Bhattah*.¹ It seems not impossible that *Bhath-ghora* and *Ghōra-ghât* may have some connection with *Gurgaj* and *Gurgi*. The name of *Bhath* is quite unknown at the present day, and I think it not impossible that it may have originated with some early Muhammadan corruption of the name of *Bandho-garh*.

The earliest mention that I have found of the name of *Bhati-ghor* is in the *Tabakât-i-Nâsiri* of Minhâj, under date A.H. 641, or A.D. 1243-44, when Malik Timur Khan-i-kirā is recorded to have several times plundered the territory of *Bhati-ghor* and extorted tribute. The name is also written *Bhati-ghora* and *Bhath-ghorah*.²

4.—BAIJNÂTH.

Eight miles to the west of Rewa, and about 1 mile to the north of the road leading to Sutna, stands the small village of

¹ See Blochmann's *Ain Akbari*, pp. 122—355 and 406.

² Raverty's *Tabakât-i-Nâsiri*, p. 743.

Baijnāth, which once possessed some five or six temples, of which only one is now standing. This temple was complete until the middle of the last rainy season, when, during the month of Ashādha, the mandapa fell down. The shrine was dedicated to Mahādeva as Vaidyanātha or Baijnāth, who is represented by a lingam inside. The temple consisted of a *mandapa*, or hall, 18 feet square, to the east, supported on sixteen pillars, leading through a small *antarāla*, or ante-chamber, to a sanctum, $14\frac{1}{2}$ feet square outside. The whole building was only $33\frac{1}{2}$ feet by $14\frac{1}{2}$ feet. The entrance to the sanctum is richly carved, with the usual figures of the Ganges and Jumna on the crocodile and tortoise. A figure of the bull Nandi occupies the entrance.

Lying round about there are numerous carved stones and pieces of sculpture. But the most interesting of the remains is a colossal figure of the Ganges, 7 feet 3 inches high and 4 feet 1 inch broad, which is known by the name of *Maddāvar*. It has four arms, and on the pedestal, quite detached from the figure, there is a crocodile, 2 feet $3\frac{1}{2}$ inches long.

Close by there is a large lion, and in a rude hut there is a figure of Durgā seated on a lion, now called Kālī, to whom goats are regularly sacrificed every Monday and Thursday, as well as on other uncertain days. During my stay of one day at Baijnāth no less than ten goats were sacrificed. They were brought at different times by small parties of men and women, accompanied by music. The goats were beheaded on the spot. The heads remained as the perquisite of the executioner, a Kol of the village of Baijnāth. The bodies were carried off by the sacrificers.

I recognized several other sculptures, amongst which were :—

Siva, with a canopy of seven snake-hoods, 4 feet 1 inch by 2 feet 4 inches.

Vishna, with lotus, of same size as Siva.

An annual fair is held at Baijnāth on the *Rām-navami* of Chaitra, or 9th day of the waxing moon. It is attended by thousands of people from all the surrounding country. The people of this part of the country are mostly Kols.

5.—RAYPUR-KOTHI.

Raypur is an old village in the small Bāghel state of Kothi, 14 miles to the north-west of Sutna, and the same distance to the north-east of Nāgodh. About 1850 there existed here a stone inscription, $3\frac{1}{4}$ feet long by $2\frac{1}{2}$ feet high, which was broken in two pieces. I had a rough copy of the inscription which had been taken by one of Colonel Ellis's servants. During my last tour I sent a servant of my own to get a fresh copy, but the stone was gone, and he was informed that it had been taken to Nāgodh, where Colonel Ellis resided before the Mutiny in 1857. My servant then proceeded to Nāgodh, where, after much enquiry, he learned that the stone had been taken to Sutna. He continued his journey to Sutna, where he found that only one portion of the inscription was now in existence. Of this he made a copy, which on examination I found to be the right-hand portion of the Raypur stone, comprising about one-third only of the original record.

The inscription is dated in Samvat 1408, and Sake 1273 (or A.D. 1351), Ashādha sudi 11 Budhavāsare, or Wednesday. In the 2nd line I find the name of *Nripa Sālīvāhana*, or "king Salivāhan," and in the 10th line *Sri Vira Rāja Nripa*. In the 21st line also there is the name of *Sasāngka bhūpa*, or "king Sasānka." This record most probably refers to one of the Bāghel Rajas of Rewa. There is a Sati pillar at *Gobari*, 28 miles to the west-south-west of Rewa, which certainly belongs to the same king. He is called Sri Vira Rāja Deva, and the monument is dated in Samvat 1407, or A.D. 1350, just one year earlier than the Raypur inscription. I think it probable that both records belong to the Bāghel Raja Bhairava Deva (as his name is written in the chronicles), who reigned from A.D. 1335 to 1355. I have referred to this inscription in my previous Report, *ante* page 76.

6.—KIYÂN, OR KEN RIVER.

On looking over the old maps of the country about the sources of the Ken River I found so many notes of "ruined

temples" that I determined to explore the whole country lying between Jukahi on the Jabalpur Railway and Saugor, a distance of about 120 miles. This tract includes all the main branches of the Ken, or Kiyân River, which, beginning on the east, are named as follows:—

1. The *Aloni* River rises to the south of the Sati Pahâr, near Bilhari. It is a fine, clear, rapid stream, about knee-deep, and 25 feet broad. It joins the Ken 8 miles to the north-west of the Jukahi railway station.

2. The *Ken*, or *Kiyân* River, rises to the north of the Sati Pahâr, 12 miles to the north-west of Bilhari. It flows generally down a rocky bed; and about 10 miles from its source passes between two groups of temples at Chhoti Deori and Simra. Still further to the north-east are the old villages of Suror and Paraini, which still possess some remains of antiquity.

3. The *Pâtna* River rises in the Kaimur range at Bahuriband, 20 miles to the south-west of Bilhari. It is a fine stream, and near its banks are the extensive ruins of Bargaon and Nând-Chând.

4. The *Biarme*, or *Bermi* River, rises in the Vindhya Hills 50 miles to the south-east of Saugor. It is a large river, 200 feet broad and $2\frac{1}{2}$ feet deep. Near its left bank is a famous group of Jaina temples at Kundalpur, with a few old Brahmanical shrines.

5. The *Bewas* River rises 30 miles to the south-east of Saugor. It is a much larger stream than the Ken, which it joins 12 miles to the north of Damoh, after a course of 80 miles.

6. The *Sonar* River rises in the Vindhya Hills, 30 miles to the south of Saugor, and joins the Ken, 50 miles to the north-east of Damoh. At Garha Kota it is a fine, clear, rapid stream.

7. The *Kopra* River rises 30 miles to the south-west of Damoh, and joins the Sonar, 16 miles to the north of Damoh.

After the junction of all these tributaries the Ken River becomes a fine stream, little, if at all, inferior to the Betwa. It flows through the middle of the Chandel country, having Mahoba and Khajurâha on the west, and Kâlanjar and Ajaygarh on the east.

7.—PARAINI.

Paraini is an old village on the right bank of the Ken River, 11 miles to the west of the Jukahi railway station. There are the ruins of several temples on the bank of a tank to the north of the village. The principal object is the statue of a boar, 5 feet 3 inches long, with a snake of seven hoods raising itself in front, and two human figures, male and female, to the right.

8.—SUROR.

Suror is a good-sized village, $2\frac{1}{2}$ miles from Paraini, on the left bank of the Ken River. Here there is an old Sati Pillar, with a curious inscription, giving the name of the Muhammadan king. It consists of five lines, which I read as follows :—

1. Samvat 1385 samaye 1 Jyeshtha sudi 4 Sanau | Suraudi
2. Sâthâne 1 Suratrân Mahamuda Mojdin râjye || Sri Ajitamâ
3. Deva bhujiyamâne | Brahmana anwayapam |

There is a difficulty about the name and title of the Muhammadan king. The date of Samvat 1385 is equal to A.D. 1328, which was near the beginning of the reign of Muhammad Tughlak. I would, however, hazard a guess from the title of Mojdin, that the writer's intention was to refer to Muizuddin Muhammad bin Sâm, the founder of the Muhammadan empire of Delhi, and that the name of the actual reigning king was unknown at the sources of the Ken River in the beginning of the 14th century of the Christian era.

9.—CHHOTI DEORI.

Chhoti Deori, or "the small temple," is the name of an extensive group of small temples, from thirty to forty in number, buried in dense jungle on the left bank of the Ken River, 5 miles to the west of Paraini. All of the temples faced the east, and were most probably lingam shrines. I saw four arghas and 1 lingam *in situ*, but I was unable to trace the plan of any of the temples owing to the thick covering of prickly pear bushes. The name of Chhoti Deori has reference to the greater temples at Simra, on the opposite side of the Ken River.

There is one inscribed pillar at Chhoti Deori which I have already brought to notice in my last year's report. It is inscribed about the middle of a square pillar of 13 inches each side. It gives the name of Raja Sankaragana, which is, I believe, quite peculiar to the Kalachuri line of princes. I can find no one to read the inscription, as the language is declared not to be Sanskrit. The characters are distinct enough, and are decidedly of an early date—perhaps as early as the 7th century.

10.—SIMRA.

The large village of Simra stands on the right bank of the Ken River, near the northern end of the Sati Pahar, about 10 miles from Marwāra and the Katni station of the Jabalpur Railway. To the east of the village there are the ruins of four temples, one large and three small. On the embankment of the Bara Tāl, or Great Tank, there are the remains of a fifth temple, with a lingam and two broken figures of Vishnu and Hanumān. Here also is a large slab, with a man and woman standing sculptured on it, and the following inscription—

Samvat 1355, Sake 1220,

Rām Dausat Singh patnika.

"In Samvat 1355, Sake 1220, Rām Dausat Singh's wife."

This is clearly a sati monument, dated in A.D. 1298, in memory of the wife of Rām Dausat Singh.

In the village there are squared stones lying in heaps. These are said to have been collected some twenty years ago by a Railway Saheb, who came from Marwāra to obtain stones for the bridge over the Katni River near Marwāra. An old woman stated that she remembered the great temple standing. The Saheb is said to have got his foot hurt, or his leg broken, and so left the stones lying where they now are !

From the style of carving the temples would appear to have been of the same age as those of Bilahri, or of the 10th century. The following figures belonged to the large temple, and must have formed a belt of sculpture round the walls outside. They are all from 2 feet 6 inches to 2 feet 8 inches in height—(1) four-armed Vishnu ; (2) godādhara Vishnu ; (3)

Hara-Gowri; (4) four-armed Brahmâ standing; (5) eight-armed Durgâ; (6) Vishnu sitting on Garuda; (7) Ganesa.

11.—RITHI.

The village of Rîthi is situated near the head of the Ken River, at the junction of the two roads from Jukahi and Marwâra to Damoh. It is 18 miles to the north-west of Marwâra. To the east of the village there is a long heap of cut and carved stones, the remains of some ten or twelve temples. Only one statue is now left; but there are numerous pieces of flat roofing slabs, with lotus flowers, and some eight or ten pieces of amalaka pinnacles.

The group of temples near the large tank is called *Barâh-Deoka sthân*, and there is an old statue of the Varâha incarnation of Vishnu trampling on a Nâga.

In the village there are the jambs and lintel of a richly carved doorway, with Vishnu seated on Garuda in the middle of the lintel, and a figure of the Ganges on her crocodile on the right jamb.

A portion of a roofing slab has been used as a Sati pillar, 5 feet 6 inches in height. In the upper panel there is a figure of Siva with four arms, and below are two men fighting. One is armed with bow and arrow and attended by a horse. The other is about to throw a spear.

The source of the Ken River itself does not appear to be considered holy, as there are no shrines established there.

12.—NÂND-CHÂND.

Nând-Chând is a small village, situated on an island, formed by the junction of two branches of the Kundo Nala with the Pâtna River, one of the principal tributaries of the Ken, or Kiyân River. On the bank of the Pâtna River there are some fine Hindu remains, consisting of a ruined temple and a Toran gateway, with numerous statues. The place is 8 miles to the north of the high road leading from the Jabalpur Railway to Damoh, being 25 miles to the west north-west of Marwâra, and 40 miles to the east-north-east of Damoh.

A great melâ, or fair, is held here annually on the Sivarâtri or Phâlguna badi 14, and another on the Basant of Mâgh.

The remains at Nānd-Chānd are the following:—

1. Ruined temple of Martangesar or Mritangeswara, "the Lord of the dead," a name of Siva, with a large lingam still standing *in situ*. The lingam is 6 feet 8 inches high and 2 feet $1\frac{1}{2}$ inches in diameter. At 222 feet 9 inches to the east there is a lofty Toran, or gateway, with a colossal statue on each side. These figures are 8 feet 6 inches high. They face one another at a distance of 20 feet 9 inches apart, and $17\frac{1}{2}$ feet from the gateway inside the enclosure. Each had a halo round the head, and rests one arm on the head of a male figure, 5 feet 4 inches in height.

2. To the south of the gateway lie two broken octagonal pillars of large size, 1 foot 11 inches diameter at bottom, and a very curious capital, 1 foot 11 inches broad. These may have formed another gateway.*

3. Close by, on the south, there are the ruins of several small temples—one lintel 3 feet $7\frac{1}{2}$ inches, with two pillars of portico 5 feet 4 inches high.

4. At a short distance to the south-east, on the western bank of a tank (about 150' \times 100'), there is a long row of small ruined temples, not less than ten or twelve, with about a dozen statues, nearly all of the same dimensions, averaging 4' \times 2'. Apparently these temples contained the Ashta-sakti and several lingams, besides a figure of Ganesa and one of Vishnu, a Siva with ten arms and a Hara-Gauri.

5. To the north-west of the tank there are the remains of a stone temple with lingam.

6. To the north-east, on the bank of the Pātna River, there are the remains of two temples, one of which was a lingam shrine.

Not a single inscription could be found on any of the statues.

The style of the architecture seems old—perhaps as old as 700 A.D. And, if so, the name of Sri Karna Deva cannot be of the same age, as the letters are as late as 1000 or 1100 A.D.

The gateway, or Toran, consists of two pillars, each 1 foot

* See Plate XLI for a sketch of one of these pillars.

6 inches square and 14 feet 6 inches high. They stand 7 feet apart, and support an architrave, 1 foot 7 inches in depth. The total height is 16 feet 1 inch as it now stands. The people unanimously described it as lofty enough for an elephant to pass under it, which is quite correct, as its clear height of $14\frac{1}{2}$ feet would be amply sufficient for an elephant with a rider on its back. The Toran stands $222\frac{3}{4}$ feet to the east of the temple; and at 22 feet to the west of it there are two colossal statues, each $8\frac{1}{2}$ feet high, and $20\frac{3}{4}$ feet apart, one to the right, and the other to the left, of the path leading to the temple. Apparently there has been a raised courtyard all round the temple extending as far as the Toran on the east, and surrounded by a brick wall.*

The pillars of the Toran are square for the lower 3 feet, and slightly moulded above. They are without capitals. The architrave is ornamented with five bee-hive-shaped bosses.

At a short distance from the Toran there are two broken octagonal pillars with heavy capitals of a rather early date, similar to those at Eran and Udayagiri. They are lying quite loose and detached, and there is nothing to show what they belonged to. Perhaps they formed part of the portico of one of the temples on the bank of the neighbouring tank.

To the south-east of the Toran, on the western bank of a large tank, there is a long row of small ruined temples, the walls of which were mostly made of single upright slabs. The following statues were found amongst the ruins:—

1. Siva, with 10 arms	4' 9" x 2' 0"
2. Hara-Gauri	3 7 x 2 1
3. Three-headed goddess, 4 arms	3 11 x 1 9
4. Goddess on peacock, 2 arms	4 1 x 2 0
5. Standing goddess, 4 arms	3 11 x 2 1
6. Four-armed goddess with child, seated on elephant	4 0 x 2 0
7. Nara-Sinha, 4 arms	3 8 x 2 2
8. Four-armed goddess, with bull	3 11 x 2 0
9. Ganesa, 4 arms	3 6 x 2 0
10. Goddess, with 2 arms, sitting with child, 7-hooded canopy	2 8 + 1 6

* See Plate XL for a sketch of this Toran gateway.

Each of these had a small slab temple, 2 feet 8 inches broad, and the same in depth inside. I traced eight distinct temples; but there must have been several more, chiefly very small ones. One of these, which I was able to measure, was found to be only 3 feet 1 inch by 2 feet 4 inches outside, and 2 feet $7\frac{1}{2}$ inches by 1 foot $2\frac{1}{2}$ inches inside. It was 2 feet $7\frac{1}{2}$ inches high.

Only one inscription could be found after a diligent search of two days. It was carved on a large flat slab, which was perhaps a side wall of one of the small temples. The characters may belong to the 9th or 10th century. I read it as *Sri Karna Deva*. If this is intended for the great Kalachuri king of Chedi, the date must lie between A.D. 1040 and 1080; but the style of the temple is apparently much earlier.

13.—BARGAON.

Bargaon is a large village of 500 houses. It is situated on the high road leading from the Jabalpur Railway to Damoh and Saugor. It is 8 miles to the south-west of Nānd-Chānd, and only 2 miles from the right bank of the Pātna River. It possesses a large number of ruined temples, both Brahmanical and Jain. I counted no less than thirty-five, all of which have been determined by actual survey; but several must have escaped observation, as I found it very difficult to distinguish each separate small temple amongst the great mass of ruins. Many of them are extremely small, and are only to be discovered by the square flat slabs which once formed their roofs.

The greater number of the Bargaon temples are mere confused heaps of stones. Many of the smaller ones can still be measured; but the larger ones are generally inaccessible. In several instances some portions of the doorways have been found, and in one instance the outer entrance of the great temple to the west is still standing, with a figure of Garuda carved in the middle of the lintel. This temple must, therefore, have been dedicated to Vishnu.

The temple of Somnāth, in the village, is quite different, both in style and plan, from all the other shrines at Bargaon.

They are of the usual type, with pillared mandapas and sculptured walls; but Somnāth has no pillars, and its walls are quite plain, with the exception of a single string moulding, and the edges of the flat roof. Its construction is also quite different, as its walls are perpendicular, and the stones are fastened together with iron cramps instead of being laid upon the top of one another without fastenings of any kind, like a house of cards. Unfortunately the villagers found out that these iron cramps have a value, however small, and they have accordingly cut them out with chisels from all the courses within their reach. All the upper courses above 6 feet are still in perfect preservation. Its stability has been farther ensured by the massiveness of the three stones covering the entrance, one above the other. The lowest, which forms the sculptured architrave, is 14 feet 4 inches long by 3 feet 7 inches high, and 3 feet 4 inches thick and contains 170 cubic feet. The other two are equally long, but not so high. These three stones are marked AB, CD, and EF, in the elevation given in Plate XXXVIII.

The roof, as seen at present, is a low pyramid of steps, of which the uppermost stone is the square slab that forms the top of the ceiling. But, as all these stones are rough at the sides, it is certain that they must have been hidden by the dressed stones which formed the outer faces of the walls. The roof must, therefore, have been flat outside, like those of the Gupta temples. This seems highly probable, as I found two flat slabs lying on the ground to the north and north-west, which, from their sculptured edges, must have formed part of the outer course of roofing stones.

I have given a sketch of one of these stones, Plate XXXIX.

In the plan and elevation also will be seen a string course which still exists at $13\frac{1}{2}$ feet above the plinth, or a few feet below the upper edge of the roofing slabs. This also is a peculiarity common to all the Gupta temples that I have seen. The temples of Sānchi, Udayagiri, Tigowa, Deogarh, and Pathaora, all have this string course at a few feet below the roof.

I searched diligently for other stones which might have

formed part of the outer roof, but could not find even a single fragment. Had the roof been a pyramidal spire, many of the carved stones would have been still there, as they would have been useless for common village-work. But, on the other hand, the stones of all flat roofs would have been at once available for all kinds of purposes, for the walls, for pavements, or for seats. I conclude that the villagers got upon the flat roof, cut out the iron cramps of the outer layers (the holes still exist in the two sculptured roofing stones already described), and then threw the slabs down. All the middle stones were too massive to be easily moved, and these still remain *in situ*.

Inside, the roof is formed by cutting off the corners of the sanctum by three successive overlaps until the fourth opening could be spanned by a single square slab, which must be about 10 or 11 feet square. The lower surface of this slab is carved with a large lotus flower. It is 23 feet 4 inches above the floor of the temple.

The lingam of Somnāth is 2 feet 2 inches in diameter, and 4 feet in height. It stands on a square pedestal, 6 feet 3 inches each side.

Outside, the temple is 34 feet by $24\frac{1}{2}$ feet, and the sanctum inside is 13 feet 5 inches by 12 feet 7 inches.

A very diligent search was made for inscriptions for two days, but the only result was one very long record too much injured to be read, except in a few places : see A of Plate* and a short line on a pillar reading *Sri Bhāsam Bodha tapaswi*. The large inscription is 5 feet long and 1 foot 2 inches high. A third inscription was found by a barber, standing on end and half sunk in the ground. It is 3 feet long and 1 foot broad. The upper part, or left end above ground, had been used as a sharpening stone for so long a time that a great part is now worn away. It is incomplete also at the right end. The characters are similar to those in use in the 9th and 10th centuries. In the 1st line I can read the words *Vigraha Chedi*, and in the 10th line *Kalachuri Nripa*. It is certain, therefore, that the record belongs to the Kalachuri kings of Chedi.

* Plate XXXIX—A, B, and C.

Many of the stones of the Somnāth temple also possess masons' marks of about the same age as the great inscription, but they appear to be simply the names of workmen, such as Chhitara, Bhote.

A few miles to the north of Bargaon at Nayakhera I found a slab 5 feet long and $2\frac{1}{4}$ feet broad, covered with round "cup-marks," from 1 inch to $3\frac{1}{2}$ inches in diameter, to which the boys of the village were still adding fresh ones. I counted 136 marks. The whole of these cup-marks were said to have been made by the boys. In fact, I saw a boy making one during the course of the day, and several of them looked very fresh.

14.—KUNDALPUR.

The famous Jain temples of Kundalpur are situated on the northern end of a range of low hills, on the left bank of the Bearmi River, 20 miles to the north-east of Damoh.

There was formerly held here a very grand melā, which is said to have lasted for the greater part of the month of Chaitra. The Deputy Commissioner, owing to the constant mortality that attended these meetings from the heat and great crowds, got the leading men to agree to hold the melā some time in Māgh, during the cold season. The proposal was accepted, and an agreement was signed; but when the time came for holding the melā, the people stayed away, and no melā has now been held for thirteen or fourteen years.

The Jain temples are all square blocks, with dome-roofs and pinnacles at the corners. They are all whitewashed, and look very like Muhammadan tombs.

The principal temple contains a colossal image of Mahāvira or Vardhamāna, and is known generally as Bardhmān. The pedestal is 4 feet high, and the figure is 12 × 11 feet, seated, with lions on pedestal.

There is an inscription of twenty-four lines of the time of Mahārāja-dhirājā Sri Chhatra Sāla, dated in Samvat 1757, Māgh badi 15 Somavāsare (Monday 31st December A.D. 1700). In the 4th line I find the name of Sri Vardhamāna and in the 8th line the terms Jina Mārga and Jinadharma. The temple is 16 feet square inside. On a small temple in

the courtyard there is a short inscription in large letters of two lines, as follows:—

Samvat 1501 varshe Paush sudi 2.
Gurau dine vâ Sri Guru Nâkîni sahf.

The week-day by calculation is Saturday, and not Thursday, as stated.

There are, altogether, 50 Jaina temples, of which 20 are on the hill, and 30 at the foot near the Vardhamâna Talao. A new temple, No. 51, is now building.

After some search two old Brahmanical temples were found at the foot of the hill near the Vardhamâna talao. They are both of the single slab and flat-roof pattern, and are, of course, small. Both face the north. One of them is empty, but the other still holds a standing figure of Vishnu.

These temples are similar to the flat-roofed shrines of Udayagiri, Sânci, and Tigowa, and possess the same peculiarity of a band of moulding running round the body of the building at the level of the roof of the portico. The pillars of the portico are indented at the angles, and the plinth is surmounted by a simple and bold moulding, but the walls are quite plain.

The larger temple is only 13 feet long by 7 feet broad, and the other is a few inches less. They are weather-stained and mouldy, and look very old; but there is nothing to show their exact age. They probably belong to the later Gupta period, about 600 A.D., but the figure of Vishnu does not appear to be so old—see Plate XLII for a plan and elevation of the larger temple. The slab walls are 9 inches thick in both temples, and the roofs are formed of two large slabs, one covering the sanctum, and the other the portico. The construction is simple and durable. Temples of this kind would, in fact, last for ages, if not attacked by violence, or the roots of trees. This is clearly shown by the great numbers of these small slab temples which still exist in Gwalior and Malwa, as well as in Bundelkhand and Rewa.

15.—HINDORIA.

Hindoria is a large old town, 10 miles to the north-east of Damoh. It possesses numerous Sati pillars, of which the old-

est that I could find was dated in Samvat 1113, or A.D. 1056. There are also many carved stones and remains of temples. The jambs of a temple doorway were found built up in the entrance gateway of a Chatri, with the original sill of the door placed on the top as a lintel. The jambs have the figures of the Ganges and Jumna standing on the crocodile and tortoise, as usual.

As Hindoria is in the open country, leading from Damoh to Kundalpur and Hutta, and so on *viâ* Nagodh to Allahabad it could not escape the destructive zeal of the Muhammadar kings of Malwa, who would appear to have been quite as tyrannical as the fanatical iconoclasts of Bengal.

16.—DAMOH.

Damoh is a large old town, situated at the foot of a high hill, 45 miles to the east of Saugor. Every old building has been destroyed, and there now remains only the shrine of the Muhammadan saint Ghāzi Miah, and the fort built of Hindu ruins.

I got a fragment of a large Sanskrit inscription of twenty-five lines, but the date is gone. I got also copies of the inscriptions from two Sati pillars, dated respectively in Samvat 1336 and 1341. The latter one gives the name of *Damoh-sthāna* at the beginning of the 2nd line, in the time of Rau Sri Jaya Sinha.

Standing at the Kacheri there is a Muhammadan inscription, which was brought from the fort, and is said to have been originally over the western gate. It is dated in the year A.H. 880, or A.D. 1475, in the reign of Ghiās Shāh, of Malwa. The following is the text of this record with its translation, which has been kindly prepared for me by Maulvi Ata Rahmān.

یارب این عرصہ دمرہ پتھان در ہمہ حال	باد معزروس و معزوں از تن و ذل زوال
مقطع عرصہ مذکور ملک مخلص ملک	کہ آسای ہمہ اشرار بکرد استیصال
دائی علم و علم صاحب سیف اسعد و قلم	ماہی کُفر وستم و اہب کان زر و مال
خاص خواس شہنشاہ غیاث الدنیا	بادشاہ ہمہ آفاق و ملک ذوالاقبال

پیش دروازه غیر پیش مورس گشته این فیصل اسے کہ مرتب شدہ از مقطع حال
در سنہ و ہجری و ہشتاد و دیگر پنج ہجری ہستی و چہارم بدہ تاریخ زمانہ سوال
ای رضامی صفی شاہ و خواصش چہ کنی زانکہ ناید صفی شان بیان اقرار

1. O God ! May this land of Damoh remain safe in the world under all circumstances, and protected from disturbances and the disgrace of decay.

2. The donor of the aforesaid tract of land, the friend of the country, who has pulled up by the roots the sources of all evil.

3. The master of letters and banners, the wielder of the sword and the pen, the destroyer of infidelity and iniquity, the giver of mines of gold and of wealth.

4. The chosen one of the personal attendants of the king Ghiâs-ud-dunya, the ruler of the world from horizon to horizon, and the most conspicuous of monarchs.

5. Opposite the western gate of the fort this breast-work has been built by the above donor,

6. In the year 885, on the 24th of Shawâl.

7. O Raghâni (Poet) dost thou try to sing the praises and peculiar virtues of this king ! His praise cannot be compassed by the descriptive power of language.

17.—BIYA-KUND.

Biya Kûnd is a hot spring in the small state of Bijâwar in Bundelkhand. It is just 40 miles due south from the cantonment of Nowgong.

The Kûnd is really a cave, and a rent has been made in the rock to let in light. The pool is 50 feet long and 32 feet broad. Rude irregular steps have been cut in the rock ; and shelters have been formed in different places, by raising pillars in front of overhanging rocks.

A great mēla is held on the 15th of Mâgh badi, when several thousands of people are said to assemble.

I had repeatedly heard of this famous Kûnd, and of a Bhim-lâth, or monolith, near it ; and I was much disappointed that there was nothing of any interest at so holy a place.

Near Dargoa (or Dargama), on the high road leading up to the Kûnd, there is a very long cave, but not lofty, as people are obliged to stoop constantly in going along it.

There are several pools of water. A Fakir formerly lived in this cave. It is several hundred feet long, but very narrow and very winding, and irregular in shape.

18.—SAURAI.

Saurai is a large old village, which must have derived its name from the *Sauras* or *Savaras*, as there are still sixty houses of them in this one place. It is 27 miles to the west of Shâhgarh, and 9 miles to the north of Madanpur.

It possesses three stone temples, which are said to be of the Chandel time, and are all attributed to Baniyas. The largest one is a Jain temple, dedicated to Adinâth, whose image is still inside with a bull on the pedestal.

The other two temples are Vaishnavi, with Vishnu over the middle of the door.

The best preserved of these temples is a Jaina structure, facing the north. It has a small portico in front, 10 feet 2 inches square, the whole temple being only 21 feet 6 inches long by 13 feet broad. But, in spite of its small size, it is a fine building, as it is richly ornamented outside with two rows of sculptures, of which some are the usual naked standing figures, of the Jains, while the rest are Brahmanical figures. On one face of each bracket capital of the portico there is a human figure carved, with his head downwards. These figures are sunken and appear to be of later work.

In the village there are two slab-built temples dedicated to Vishnu, whose image is over the middle of the doorway, with those of Brahma and Siva at the sides. The slabs forming the walls are 8 inches thick. Both temples have porticoes. See Plate XLII for a plan of the larger temple.

On an upright slab at a well there is an inscription of six lines as follows:—

1. Samvat 1707 varshe, Jeth sudi 7, saumavâsare ;
2. Nripa Sri Sâhi Jalân arnal, Sri Nawâb Sar—
3. -dâr Khân, Parigane Dhâmoni, moje Saurai, Chaudhari
4. Hari Chandan Lodhi Thâkur ; tasya pu. Chaudhari A-
5. * va * Dâs Kua banwayo. Likhitam Mâdho-
6. -patvâris. Bhavatu Mangalam.

"In the Samvat year 1707 on the 7th of the waxing moon of Jyeshtha, on Monday, during the reign of the king Sri Shâh Jahân, and under the government of Sri Nawâb Sardâr Khân, in the Parganah of Dhâmoni, and town of Saurai, the son of Chaudhari Hari Chandan Lodi, Chaudhari Dâs, made this well. Written by Mâdho Patwâri. May it be fortunate."

The date corresponds with Monday 27th May A.D. 1650.

Saurai must once have been a very flourishing place. It is well situated, on the high road leading from Jhânsi and Lalitpur through the Madanpur Pass to Saugar.

19.—MADANPUR.

The town of Madanpur is situated at the head of one of the principal passes leading from Saugar to Lalitpur, Jhânsi, and Gwalior. It was formerly a place of much consequence, as it possessed the best stone quarries in this part of the country, and several very fine temples. To this point the army of the Chauhân Prince, Prithi Raj, advanced after his conquest of Mahoba, and carved his name on the pillars of the great temple as the conqueror of Paramârdi, King of Jejâbhukti, or Jajahuti.

There is a lake of some size, formed by throwing an embankment across the valley on the north. The embankment is from 76 to 100 feet thick, and is covered with numbers of Muhammadan tombs, generally formed of carved flat slabs.

Madanpur is said to have been founded by Madana Varmma, the Chandel Raja of Mahoba; but there is at least one inscription of Samvat 1112, or A.D. 1055, which is older than Madana Varmma, who reigned from 1129 to 1165 A.D. It seems probable, therefore, that he only renamed the place, and that the old site, now called "old Madanpur," was the original city under another name, which was changed to Madanpur by Madana Varmma. This old city was situated on the ground to the north of the village, in the neighbourhood of the Jain temples. There are traces of former habitations in numerous fragments of tiles and pottery scattered about the field. This site would naturally have been deserted for the more convenient position of the new town at the end of the lake.

There are six temples at Madanpur, all more or less ruined. The oldest of these are three Jaina temples situated to the north of the town, where the original town is said to have stood. Two others are at the north-west corner of the lake, and the sixth at some distance to the north-east of the lake.

A. The principal Jain temple is only 30 feet 8 inches long by 14 feet 2 inches broad, including the porticoes. The sanctum inside is $8\frac{1}{2}$ feet by 8 feet, and contains a naked standing figure with an inscription on the pedestal. The roof is a plastered dome of modern work. Outside there is a broken pedestal with a fish on it and an inscription dated in Samvat 1212, or A.D. 1155.

B. Close by on the west there is a second Jain temple facing the last. It also has a plastered dome. It contains five statues, of which I recognised the following:—

1. Adināth, with a bull on the pedestal;
2. Chandraprabhā, with a crescent; and
3. Sambhunāth, with a horse on the pedestal.

Near these temples there are two Sati pillars, dated in Samvat 1522 and 1528, or A.D. 1465 and 1471. One of them gives the name of the king Sri Sulitān Mahmud Sāhi Khalchi, with his two chief forts of Mandugarhdūrg and Chanderidūrg, and that of the governor, Phate Khān.

The long inscription in the temple consists of eight lines. It is dated in *Samvat 1206, Vaisākha Sudi 10, Bhaume*, or A.D. 1149, Wednesday, 20th April, in the middle of the reign of Madana Varmma.¹ It gives the name of Swasti Sri Madanapura. But the rest of the inscription seems to be taken up with the names of Jaina pilgrims, who came to offer their adorations. There are several inscriptions dated as late as Samvat 1692.

The two Brahmanical temples at the north-west corner of the lake must have been very fine buildings. The sanctum of both temples is gone entirely, but many stones still remain to show that they were highly decorated. Both face the east. They were most probably dedicated to Vishnu

¹ The week day should be Tuesday, *Bhaume*, but the date *Vaisākha suri 10*, gives Wednesday

and Siva, as a colossal boar and a life-size bull are lying close by. The mandapa, or hall, of the larger temple was 40 feet square, and that of the smaller one 18 feet square. The floors of both were raised 13 feet above the ground, but the whole of the outer facing of these lofty plinths is now gone. The unfortunate proximity of the temples to the stone quarries, no doubt, led to the appropriation of the stones, both cut and uncut, which were lying so handy for removal.

The large temple with its spire must have been at least 100 feet high, and the smaller one about half that height. I noticed a few slightly curved and ornamented stones which must have belonged to the outer face of one of the spires; but the clearance of the fallen stones has been so complete that not even a guess can be made as to the style of the spires.

The roofs of the Mandapas are still in fair order. They are quite flat, like the roofs of temples of the Gupta period.

The colossal boar is 6 feet 2 inches long, with six rows of small figures carved on each side. The pedestal is broken, but one hind foot still remains. Below there is a very large Nāga, or snake, to represent the ocean from which the boar raised the earth, Prithvi, represented as a woman, whose two feet still remain.

The bull is recumbent, 3 feet 10 inches in length. There are also two large lions, each 4 feet long and 4 feet high.

There are several short inscriptions in these two temples, of which some are of real interest and importance, as they give the date of the victory of Prithi Rāj Chauhān over the Chandel Prince Paramārdi Deva. The three records in the large temple I have already published;* but as they are very short they may be repeated, as a mistake was made in the name of the conquered country, which, owing to the break in a single letter, was read as "Jejākasukti," instead of "Jejākabhukti." These three short inscriptions are as follows:—

A. No. 9—Sri Chāhumāna vansye-
-na Prithvi Raja bhu-
-bhujā Paramārdi narendra-
-sya desoya mudavasyata.

* Archaeological Survey of India, Vol. X, p. 98, and Plate XXXII, Nos. 9, 10, and 11.

Here we have the names of Prithvi Raja, the Chāhumāna Raja, and of his antagonist Paramārdi, the Chandel Raja, coupled together.

B. No. 10—Aum! Aruno-rājasya pautrena Sri
Someswara Sununā Jejāka-
-bhukti desoyam Prithvi rājenā
lunitah S. 1239.

In this record we have the genealogy of the Chauhān chief given as the son of Someswara, and the grandson of Aruno Raja, with the name of the conquered country Jejāka-bhukti, and the date of Samvat 1239, or A.D. 1172.

C. No. 11—Aum! Chandrasekhara, Bhawāniya,
Tryambaka Tripurāntaka,
Chaksha Vidyādhara Deva
Twam nauti pranatah sada.

Here the names of *Chandra-sekhara*, the “moon-crested,” *Bhawāniya*, the “husband of Bhawāni,” *Tryambaka* the “three-eyed,” *Tripurāntaka*, the “conqueror of (the demon) Tripura” are the titles of Siva. I conclude, therefore, that the larger temple, in which these inscriptions are recorded, must have been dedicated to Siva.

In the smaller temple there are two long inscriptions of different dates, of which the later one gives the perfect reading of the name of the country as *Jejākabhukti mandala*, with the same date of Samvat 1239. It reads as follows:—

1. Aum! Jyam hisenā Chandalam vyamāne Jejākabhukti
mandalasya Sri Chahumānānwaya Kīrtti Chandra
Prithvi Na-
-rendrasya jaya prasastih ||S. 1239.

2.

The other inscription, which is only four years earlier, reads as follows:—

1. Aum! Sam. 1235 Srāvaṇa badi 1 Bikaurapathake Ma-
hārājaputra Sri Alhana Deva Sri Aditya māsam
2. Pratidatta 2 || angrepi Sonadāsya tasya mātā
Garddabha grikshanti ||

The village of Bikaura still exists as Great and Little Bikaura, on the left bank of the Jāmini River, 5 miles to the south-west of Madanpur. It possesses some small ruined temples.* Alhana Deva must have belonged to the royal family of the Chandels of Mahoba.

The temple to the north-east of the lake is a very small one, completely surrounded by jungle. It is a small slab-walled building, with a spire, only $7\frac{1}{2}$ feet square. Apparently it was dedicated to Śiva, as there is a bull lying on the ground in front, with a group of Mahādeva and Pārvati, and on the back wall there is a figure of Śiva with ten arms, and on one of the sides a figure of the skeleton goddess Kālī, with ten arms. There is also a row of small figures with dancing girls in the angles. The temple is rather pretty, in spite of its small size. The upper part of the spire is gone.

20.—LALITPUR.

Lalitpur is a large town, about halfway between Jhānsi and Madanpur, and 20 miles to the east of Chanderi. It is pleasantly situated on the left bank of the Sajad River, a tributary of the Jāmini. Its name is said to have been given to it in honour of queen Lalitā Devi, of whom a story is told which I have related in another place, with several variants from different localities. On this last visit the story was somewhat varied as follows:—

“Raja Sumer Singh had the disease called *Jalandhar*, or “dropsy,” in his stomach, and as his case baffled the doctors, he started on a pilgrimage to Ajudhya. On the way he and his Rāni stopped at a pool, on the present site of Lalitpur. Here the Rāni dreamed that if her husband would eat some of the *kāi* (*conserve*) of the pool, he would be cured. He ate some accordingly, and was cured. Again, the Rāni had a dream that there was treasure buried under a tree on the embankment of the tank. A hole was dug under the tree and the treasure taken up. The Raja then called the tank Sumer Sāgar, or Tāl, and founded a town which was named Lalitāpura after his Rāni.”

In the town there is a small masjid, 19 feet 4 inches square, built entirely of Hindu materials, or, perhaps, it is part

* Markhera, on the opposite bank of the river, also has a small temple.

of a Hindu temple, only slightly altered. It is called Bāsa and bears an inscription in Nāgari letters of the time of Firoz Shah. The erection of the masjid must, therefore, be later than the date of this inscription, Samvat 1415, or A.D. 1358. Feroz is called (line 6) *Rājādhirāja pati Sri Suratān Peroja Sāhi*. The destruction of the Hindu buildings in this part of the country would appear to have been due to the zeal of the Khalji rulers of Malwa, who ruled after Feroz.

The pillars of the masjid apparently must have belonged to three or four different temples, as they are of very different sizes, as well as of different patterns. There are six fluted pillars of sixteen sides, which are very fine specimens of Hindu work. Close by, in a Parwār Baniya's house, I saw four more of these fluted pillars. Some portions of fretted eaves now ornament the outside of the masjid; but the flat-roof is hidden by a common battlement.

21.—SURA HAR.

Surahar is an old town on the high road between Lalitpur and Chanderi. It possesses a small temple, only 12 feet 8 inches square outside, with three figures of Vishnu in niches outside. The door faces the west. There is also an old Sati pillar, on which occurs the name of the village.

22.—JHALONI.

At Jhaloni, 16 miles to the north of Chanderi, the road to Gwalior passes over a low range of hills with a lake at foot. On the top of the pass there is a tall slab, 18 feet in height, called *chira*, or "the slab," with an inscription in seven lines of Nāgari letters, dated in Samvat 1351 and Saki 1216, or A.D. 1294. The letters are very badly formed, and I cannot make out the purport of the record.

23.—TERAHI.

Terahi is an old village, 5 miles to the south-east of Ranod. It possesses two temples of considerable age and

importance, as they probably date from the beginning of the 10th century. Both temples are small, but one of them possesses a richly ornamented Toran gateway in good preservation. The larger temple, inside the village, is only 19 feet long by 14 feet broad, including its porch. The smaller temple, outside the village, is only 15 feet 6 inches long by 12 feet 3 inches broad, including its porch, but it has a fine Toran gateway in front at a distance of 18 feet, which, being 20 feet high and of the same breadth as the temple itself, adds much to its dignity.

There are inscriptions on two prostrate pillars close by, both bearing dates in the 10th century of the *Samvat*. One is 910 *Bhādrapada badi 4 Sanau*, or Saturday, 29th July, 853 A.D. On that day the *Mahā Sāmantādhipati* of Madhubana, named Sri Guna Raja Unda-Bhata, a great warrior, made a gift to the temple of Sri Chāndiya. Madhuban is clearly the old name of the district in which Terahi is situated, although the name is not known at the present day. The *Mohwar* River, on which Terahi and Rajapur are situated, probably preserves the old name. Ranod, which is only 5 miles distant, is in the same district, and was no doubt the residence of the chief. At Kadwāha, only 1 mile to the south of Terahi, there are four standing temples, and the ruins of nine others. This place gave its name to a pargana in Samvat 1380, or A.D. 1323. But there are short records of pilgrims on the temple pillars with the dates of Samvat 1124 and 1162, or A.D. 1067 and 1105.

The date of the second inscription is doubtful. It looks like 920 *Bhādrapada badi 14, Sanichare*. But the week day does not agree with this year, nor does it agree with any other decimal year of the 10th century. It records a gift by Sri Ru * * * Bhata to the goddess Ambikā. The name of the donor is much injured, and has no titles, as in the first record. But the latter half of the name Bhata would seem to connect him with the first record.

These temples were accidentally discovered by my draughtsman Jamna Shanker Bhatt, when searching for a village named Makhoba, which once possessed a temple with

a long inscription. A small hamlet of this name was found, but it had no temple, and apparently never had one.

24.—RĀJAPUR.

Another discovery was made by the same man at Rājapur, only a few miles from Terahi. Rājapur is a large village situated on the Mohwar Nadi, 6 miles to the east of Ranod, and 4 miles to the south-west of Mayapur. About 1 mile to the north-east of the village, and on the bank of the Mohwar River, a Buddhist stūpa in nearly perfect order was discovered. The stūpa is built entirely of stone, and chiefly of small stones. It stands on a square base, or plinth, of 60 feet 9 inches side. On this rises a cylindrical drum 43 feet 8 inches in diameter and 11 feet high. Above it rises a second cylindrical drum, 35 feet 8 inches in diameter and 11 feet high, and over this rises the dome of the stūpa, 27 feet 8 inches in diameter and 22 feet high, the upper part being a simple hemisphere. The whole building is, therefore, 49 feet 6 inches in height. It is perfectly plain, without even a hand of moulding.

The people call it *Kothīla Math*, which may be translated as the "Tower Temple," but they have no tradition as to its purpose or the name of its builder. This stūpa is, I believe, the only remaining trace of Buddhism in the wide tract of the Northern Gwalior territory. There are numerous Buddhist remains at Besnagar, Bhilsa, and Udayagiri, on the southern border of the Gwalior state; but I have not seen, during the long course of my wanderings, any traces of Buddhism in the northern parts of Sindhia's dominions.

There is a strange legend attached to the Kothīla Math which would make it a monument erected over the remains of a brother and sister who had become man and wife in ignorance of their relationship. A Banjāra's wife having died, leaving two young children, a boy and a girl, the father made the boy over to one friend and the girl to another. The two Banjāras having died, the boy and girl were married to each other by the friends. After some time the girl


observed a mark on her husband's head, and told him that she formerly had a brother with a similar mark. He then remembered that he had a sister very like her, and the two having become aware of their relationship prayed that their sin might be forgiven. Then the earth opened beneath them, and they were swallowed up. The Kothila tower was then built on the spot out of the wealth which the brother and sister had left behind.

INDEX.

	PAGE		PAGE
A			
Adesar, Hill	125	Cave at Kevati-kund	115
Adisathra, of Ptolemy	93	— at Biya-kund	169
Ahugi, Temples	126	Chamba, Inscriptions	134
Ajaygarh, Fort	46	Chandela Kingdom	77
—, Inscriptions	48	— Rajas	80
Alha Ghât, Inscriptions	114	— Inscriptions	81
Aloni River	157	Chilla, Stone-house of Alha and Udai	8
B			
Bachaund, or Bachon	54	Chini, old Mound	134
Bâghelkhand, or Rewa	103, 141	Chitrakuta Hill	10
Bâghel Rajas, List of	107	Chhoti-Deori, Temples	100, 158
Baijnâth, old Temple	154	D	
Balanti-purgon of Ptolemy	94	Damoh, Inscriptions	168
Bardi and Bhopârî	128	Dibhor, Tank and Temple	124
Bardaotis of Ptolemy	92	Durga-kho, Caves and Inscip- tions	128
Bar-Dewal, great Temple	4	E	
Bargaon, Temples	101, 163	Empalathra of Ptolemy	92
Bermi River	157	G	
Besâni, Inscription	101	Gânggeya Deva, Inscription	112
Bettigi of Ptolemy	94	Ganj, large old village	96
Bewas River	157	Ginja Hill, Inscription	119
Bhima Sena's Inscription	110	Gobari, Inscription	76
Bhûli, Inscription	130	Gonda, Temples	13
Bilhariya, Temples	19	Gupt-Godâvari	13
Biya-kund, Cave	169	Gûrgi-Masaun	149
Bolingæ of Ptolemy	92	H	
Bridama of Ptolemy	93	Haliya, long Inscription	121
C			
Cave of Dragon at Kosam	2	Hindoria, Ruins	167
— of Rikhian	7		
— of Vasubandhu at Rosam	3		


	PAGE		PAGE
I			
Inscriptions at Ajaygarh . . .	48	Kosam, or Kausāmbi . . .	1
————— Haliya . . .	121	Kundalpur, Jain Temples . . .	166
————— Kevati-kund			
cave . . .	115	L	
————— Kevati-kund		Lakhura, old site . . .	95
Sati pillars . . .	116	Lalitpur, Temple . . .	175
————— Alha Ghāt . . .	114		
————— Mahoba . . .	70	M	
————— Kālanjar . . .	33	Madanpur, Temples . . .	171
Inscription on Dahi copper-		————— Inscriptions . . .	173
plate . . .	74	Mahoba, Inscriptions . . .	70
————— at Gobari . . .	76	Malaita of Ptolemy . . .	93
————— at Raypur Kothi . . .	76	Maniyagarh Fort . . .	69
————— of Chandel Rajas . . .	81	Marhia, old site . . .	100
————— at Lakhuria . . .	98	Marpha, great Fort . . .	18
————— at Jasso . . .	99		
————— at Chhoti Deori . . .	100	N	
————— at Besāni . . .	101	Nachna, or Kuthara, Temple . . .	95
————— at Piāwan . . .	112	Nadubandagar of Ptolemy . . .	92
————— at Ginja Hill . . .	119	Nānd-chānd, Temples . . .	160
————— at Damoh . . .	168	Nilkanth, Temple, Kālanjar . . .	32
————— at Durga-kho . . .	128		
J			
Jayapura-durg, or Ajaygarh . . .	46	P	
Jejakabhukti, or Jejāhuti . . .	173	Pabhosa, or Prabhāsa Hill . . .	2
Jhaloni, Inscription . . .	176	Paraini, Statue of Boar . . .	158
K			
Kakareri, Inscriptions . . .	146	Parapiotæ of Ptolemy . . .	93
Kālanjara, Fort . . .	20	Pātna River . . .	157
————— Inscriptions . . .	33	Phullitæ of Ptolemy . . .	93
————— History . . .	22	Piāwan, Inscription . . .	112
Kālpī, old buildings . . .	131	Poruari of Ptolemy . . .	93
Katka, obelisk . . .	120	Prithivi Raja, Inscription of . . .	173
Kevati-kund, or Keonti . . .	115, 141	Ptolemy's Map of India . . .	90
————— Sati pillars . . .	116		
Khajurāha . . .	55	R	
————— Inscriptions . . .	63	Rājapur, Buddhist Stūpa . . .	178
Kiyān, or Ken, River . . .	156	Rāsin, or Rājavāsini . . .	15
Kondali of Ptolemy . . .	93	Raypur-Kothi, Inscription . . .	76, 156
Kopra River . . .	157	Rewa, or Bāghalkhand . . .	103, 141
		Rikhian, Caves . . .	7
		Rithi, ruined Temples . . .	160
		Rithora, two ruined Temples . . .	4

S		PAGE		PAGE
Sagabaza of Ptolemy . . .		92	Temples at Ahugi . . .	126
Sageda, Metropolis of Ptolemy		93	———— Saurai . . .	170
Sandrabatis of Ptolemy . . .		91	———— Bar Dewal . . .	4
Sarwan, Story of		41	———— Rithora	4
Sâstri Samvatsara, or Sapt			———— Gonda	13
Rikhi Kâl		136	———— Bilhariya	19
Saurai, Temples		170	———— Nilkanth, Kâlanjar	32
Scopur, Statues		130	———— Nachna-kuthara . .	95
Simra, Inscription	101, 159		———— Choti Deori	100
Sorte, Nomades of Ptolemy . .		94	———— Bargaon	101, 163
Statue of Hasti-vâhini Devi . .		144	———— Nand-Chând	160
———— colossal, of Ganges . .		155	Terahi, Temples and Inscript-	
———— of Boar, at Paraini . .		158	tions	176
Stûpa, Buddhist, at Râjapur . .		178	Tholobana of Ptolemy	93
Surahar, Sati pillar		176	Toran Gateway at Nând-Chând	160
Suror, Inscription		158	Trailokya Varmma Deva . . .	147
Sultânpur, in Jalandhar, Doâb		133	Trailokya Malla	148
			Tura, Hermit's cell	126
T			V	
Tamasis of Ptolemy		91	Vâkâtaka, Râja's Inscription .	98
Temples at Madanpur		171		
———— Baijnâth		154		



VOL. XXI. KOSA MBI. PLATE II.


Illustrated at the Survey of India Office, Calcutta, September 1885.




10 5 0 10 20 30 40 50 feet

A Cunningham del

BAR-DEWAL TEMPLE ON THE JUMNA.






A. Cunningham del.


Engraved at the Survey of India Office, Calcutta September 1886

TEMPLES OF VISHNU AND LAKSHMI.




R A S I N .

TEMPLE OF CHANDÂ-MAHESWARI.




0 10 20 30 Feet

A. Cunningham del.




A. Cunningham, del.


P. Statue of Water-Carrier.



Q. Statue of Water-Carrier.



L. At Ganes. Gate.




K. In Cell near Nilakantha.



A. S. 1186.

दशग्रीवीस ज
म नि स्य पुत्राः
१०५६ अक्षय काली
पञ्चवर्षोदवा ॥ अक्ष
पत्नी सा न स्या भसी ॥
अक्ष मा पति पत्या वती ॥
लाघौ रौ



S. 1208.

B

A

2

4

6

8

10

12

14

16

18

पुनर्वत १२०८ भाद्रपद १८
 सनौ ॥ ३ ययुपुत्र १८
 ममलोका नां नानावे
 दाकियका नीयको ॥ १८
 श्रीमीय ना उत श्री लौपा
 लेपुत्र अने नकी डा युडे ॥
 नोवयेन प्रति पादनं अत
 तदन नत्रं श्री श्री कन गिक
 वक्रान श्री लखे ठकान श्री
 का ल गा ॥ १८ श्री मदी वना
 का श्री पास ला मे गला हड्डा
 निरुन १३ मं कनि आत न १२
 पने पे नदी पते दकु गा श्री गो
 प्र को रूप्य ग्रामो वीदि अणि का
 मीयता गो पाशा अयादा ॥ १८
 ग के वा स ॥ १८ ना खे न श्री
 मन्मद नवर्षा गा ॥ १८ श्री
 सुवकास पुट

S. 1237.

पुनर्वत १२१० आषाढ
 सुदि २ लो मे जय पुत्र १८
 यमममलोका नां ना उत
 श्री वीने ना ते कला पुत्र कुनि
 पं को टि आया मीय अने न
 द ति के वौया पादनं भा ॥ १८
 दु बि मान देश वो मु त प्र न नि प
 ति पादनं यतां तदनं त व
 श्री श्री कन ए वरे मे १२
 का ल आ १२ पते रस्य
 नौ ली वा

2

4

6

8

10

C

S. 1243.

पुनर्वत १२१३ अश्वि सुदि १८
 जय पुत्र १८ यममलोका
 नां ना उत श्री मी सुत ना उत
 न न पुत्र कु वि यका नीये को
 टि आया मीये अने न वी ने नि
 वात ला वि प्रति पादनं कानं
 द्या त व श्री श्री कन पावने
 ठा १२ सै क नि आ १२ सै

2

4

6

8

D

S. 1269.

पुनर्वत १२६९ भाद्रपद १८
 ममलोका नां नानावे
 दाकियका नीयको ॥ १८
 श्रीमीय ना उत श्री लौपा
 लेपुत्र अने नकी डा युडे ॥
 नोवयेन प्रति पादनं अत
 तदन नत्रं श्री श्री कन गिक
 वक्रान श्री लखे ठकान श्री
 का ल गा ॥ १८ श्री मदी वना
 का श्री पास ला मे गला हड्डा
 निरुन १३ मं कनि आत न १२
 पने पे नदी पते दकु गा श्री गो
 प्र को रूप्य ग्रामो वीदि अणि का
 मीयता गो पाशा अयादा ॥ १८
 ग के वा स ॥ १८ ना खे न श्री
 मन्मद नवर्षा गा ॥ १८ श्री
 सुवकास पुट

2

4

6


From Impressions

J. on Rock near Tirhowan Gate.


२
 ४
 ६
 ८
 १०
 १२
 १४

2
 4
 6
 8
 10
 12
 14

A. Base of Colossal Statue of Hanumān.




D. Lakshminath Temple.




B. Fragment.



J. Left door Jamb Jain Temple.



E. Vāman Temple.



From Impression

H

[The page contains dense handwritten text in Devanagari script, which is mostly illegible due to extreme fading and significant ink bleed-through from the reverse side. The text appears to be organized into several vertical columns.]

A. CHAUNSAT JOGINI.

माहेश्वरी हिंयलाऊ

B. GHANTAI TEMPLE.

1. कैमिचंद्रः 2. स्वस्ति श्री साधु

C. STATUE OF SÂNTINATH.

संवत् १०८३ श्रीमत - - - - - श्रीशान्तिनाथस्य प्रतिम

D. STATUE OF SAMBHUNÂTH.

७॥सवत् १२१५ माघशुदि ५ श्रीबन्धन वन्धुदेव

E. KHANDÂRIYA TEMPLE.

1. दशार्ण → *on the under side of an Architrave*

F. CHITR-GUPT TEMPLE.

1. पारवस 2. मुहव 3. कहील

G. DEVI-JAGADÂMBÂ TEMPLE.

1. जिलयव 2. देवीकुण

H. VISWANÂTH TEMPLE.

1. श्रीशक्ति 2. श्रीदिवणय 3. श्रीमिदिरता


J. KUNWAR MATH.

वासला 5 times

K. STATUE OF SHANMUKHA.

देवगुप्तसिद्धिः रुद्रकेशी उद्दिष्टः
अर्थात् स्यात् सत्त्वोचितो वन्द्यः


A. IDGAH WALL.



From Impressions.

Lithographed at the Survey of India, Benares, 1880.

Wall of Fort.



2

4

6

8


10

12

14

16

Broken Slab.



D. Statue of Nemināth. S. 1211.

व गोलातर्कस्तेसापुसाठेतुसाधुलारवृतप्रपुत्रेगाहू
 श्रीमन्नदनवर्मदेवपञ्चसेर११आषाढसुदि३




उदैकलेजालू जीलूणवेनित्यप्रणमत्रि॥

सनौ॥ ॐ ॥ देव श्रीनेमिना व॥ रूप कावलक्षण॥

G. On Pedestal with Figures.



संवत् १२४४ आषाढ सु दि २५ वै॥ ॐ ॥ कालजराविपति
 श्रीमत्यमर्द्धदेव पादानामही प्रवर्द्धमानकल्याणविजयराशे

From Impressions.



A. Cunningham, del


Lithographed at the Survey of India Office, Calcutta, November 1880



O—Cave-holes with figures of Lions.


S—Small Statues in Niches.

T—Trellises of Stone.



A. Cunningham, del.

Lithographed at the Survey of India Office, Calcutta, November 1891.



A. Cunningham, del.

NACHNA KUFARA

On a loose Slab



On the Edge of the Slab



BESÂNI

On a Slab



JASSO

Natural Lingam



From Impressions.

CHHOTI
DEORI.

ॐ नमो भगवते वासुदेवाय ॥ १ ॥
 श्रीगणेशाय नमः ॥ २ ॥
 कलकटदण्डाय नमः ॥ ३ ॥
 दण्डाय नमः ॥ ४ ॥
 पुनः पुनः ॥ ५ ॥
 वासुदेवाय नमः ॥ ६ ॥
 कलकटाय नमः ॥ ७ ॥
 दण्डाय नमः ॥ ८ ॥
 पुनः पुनः ॥ ९ ॥
 वासुदेवाय नमः ॥ १० ॥
 कलकटाय नमः ॥ ११ ॥
 दण्डाय नमः ॥ १२ ॥
 पुनः पुनः ॥ १३ ॥
 वासुदेवाय नमः ॥ १४ ॥
 कलकटाय नमः ॥ १५ ॥
 दण्डाय नमः ॥ १६ ॥
 पुनः पुनः ॥ १७ ॥
 वासुदेवाय नमः ॥ १८ ॥
 कलकटाय नमः ॥ १९ ॥
 दण्डाय नमः ॥ २० ॥
 पुनः पुनः ॥ २१ ॥
 वासुदेवाय नमः ॥ २२ ॥
 कलकटाय नमः ॥ २३ ॥
 दण्डाय नमः ॥ २४ ॥
 पुनः पुनः ॥ २५ ॥
 वासुदेवाय नमः ॥ २६ ॥
 कलकटाय नमः ॥ २७ ॥
 दण्डाय नमः ॥ २८ ॥
 पुनः पुनः ॥ २९ ॥
 वासुदेवाय नमः ॥ ३० ॥

PIAWAN
ROCK.

ALHA-GHAT.

ॐ नमो भगवते वासुदेवाय ॥ १ ॥
 श्रीगणेशाय नमः ॥ २ ॥
 कलकटदण्डाय नमः ॥ ३ ॥
 दण्डाय नमः ॥ ४ ॥
 पुनः पुनः ॥ ५ ॥
 वासुदेवाय नमः ॥ ६ ॥
 कलकटाय नमः ॥ ७ ॥
 दण्डाय नमः ॥ ८ ॥
 पुनः पुनः ॥ ९ ॥
 वासुदेवाय नमः ॥ १० ॥
 कलकटाय नमः ॥ ११ ॥
 दण्डाय नमः ॥ १२ ॥
 पुनः पुनः ॥ १३ ॥
 वासुदेवाय नमः ॥ १४ ॥
 कलकटाय नमः ॥ १५ ॥
 दण्डाय नमः ॥ १६ ॥
 पुनः पुनः ॥ १७ ॥
 वासुदेवाय नमः ॥ १८ ॥
 कलकटाय नमः ॥ १९ ॥
 दण्डाय नमः ॥ २० ॥
 पुनः पुनः ॥ २१ ॥
 वासुदेवाय नमः ॥ २२ ॥
 कलकटाय नमः ॥ २३ ॥
 दण्डाय नमः ॥ २४ ॥
 पुनः पुनः ॥ २५ ॥
 वासुदेवाय नमः ॥ २६ ॥
 कलकटाय नमः ॥ २७ ॥
 दण्डाय नमः ॥ २८ ॥
 पुनः पुनः ॥ २९ ॥
 वासुदेवाय नमः ॥ ३० ॥

From Impressions.

View of Hill from the South




INSCRIPTION IN RED PAINT.

Eye Copy.


བཤམ་མཁོན་ལོ་མཐུ་སྐྱོང་། འཇམ་པུ་པུ་ཏེ་མཆེ་བཟུང་།
 ཡུ་ཏུ་མཐོ་མཁོན་ལོ་མཐུ་པུ་ཏེ་མཆེ་བཟུང་། ཡུ་ཏུ་མཐོ་མཁོན་ལོ་མཐུ་པུ་ཏེ་མཆེ་བཟུང་།
 ཡུ་ཏུ་མཐོ་མཁོན་ལོ་མཐུ་པུ་ཏེ་མཆེ་བཟུང་།

Reduced Tracing

བཤམ་མཁོན་ལོ་མཐུ་སྐྱོང་། འཇམ་པུ་པུ་ཏེ་མཆེ་བཟུང་།
 ཡུ་ཏུ་མཐོ་མཁོན་ལོ་མཐུ་པུ་ཏེ་མཆེ་བཟུང་། ཡུ་ཏུ་མཐོ་མཁོན་ལོ་མཐུ་པུ་ཏེ་མཆེ་བཟུང་།



Rude Sketches of Animals
in Red Paint.



2 ॐ नमो भगवते 3 नमो भगवते नमः

4 ॐ नमो भगवते नमः 5 ॐ नमो भगवते नमः

6 ॐ नमो भगवते नमः 7 ॐ नमो भगवते नमः

8 ॐ नमो भगवते नमः 9 ॐ नमो भगवते नमः 10 ॐ नमो भगवते नमः


11 ॐ नमो भगवते नमः 12 ॐ नमो भगवते नमः 13 ॐ नमो भगवते नमः 14 ॐ नमो भगवते नमः

15 ॐ नमो भगवते नमः 16 ॐ नमो भगवते नमः

17 ॐ नमो भगवते नमः 18 ॐ नमो भगवते नमः


19 ॐ नमो भगवते नमः 20 ॐ नमो भगवते नमः

21 ॐ नमो भगवते नमः 22 ॐ नमो भगवते नमः 23 ॐ नमो भगवते नमः



A. Cunningham, del.

Lithographed at the Survey of India Office, Calcutta, September 1855.



From CŪRŪ.




Photo-stylin 8

Survey of India Office, Calcutta, August 1885.




Figure 1. Detail of the relief carving.

$$(\mathbf{M}^{(1)}, \mathbf{E}^{(1)}) \rightarrow (\mathbf{M}^{(2)}, \mathbf{E}^{(2)}) \rightarrow \dots \rightarrow (\mathbf{M}^{(n)}, \mathbf{E}^{(n)})$$



SOMNATH TEMPLE

FACE OF EAST DOOR



GARDUL TEMPLE

FACE OF EAST DOOR



A. Long Inscription—13 lines—5 Ft. × 1' 2".

सांख्यिकविद्यावशापेक्ष

देवदेवदेवदेव

B. Broken Inscription—11 lines—3 Ft. × 1'.

द्विषियन्तवैश्व


श्रीकृष्णमिश्रकृष्णकलशपिठपत्नीः

On Face of Pillar.

c. श्रीनारायणोद्यमपक्षी


Masons Marks on Somnath Temple.

केका गमा कीरफ वसकि देवे दूं क म सि सि ऊने ऊने श्री
+ त एं क म




A. Cunningham del.

Lithographed at the Survey of India Office, Calcutta, November 1888.



A. Cunningham, del



A Cunningham, del

Lithographed at the Survey of India Office, Calcutta, November 1888.

